

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X028-2A	I000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	272		272
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	143		143
20200100	EARTH EXCAVATION	CU YD	100		100
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	434	434	
20400800	FURNISHED EXCAVATION	CU YD	294		294
20700220	POROUS GRANULAR EMBANKMENT	CU YD	962	962	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	564	564	
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5		0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	48		48
28000305	TEMPORARY DITCH CHECKS	FOOT	100		100
28000400	PERIMETER EROSION BARRIER	FOOT	765		765
28100107	STONE RIPRAP, CLASS A4	SQ YD	115	115	
28200200	FILTER FABRIC	SQ YD	115	115	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	191		191
40600300	AGGREGATE (PRIME COAT)	TON	4		4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	373		373
40600990	TEMPORARY RAMP	SQ YD	27		27
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	425		425
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	153		153
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	91		91
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	7		7
44000100	PAVEMENT REMOVAL	SQ YD	91		91
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1304		1304
48101200	AGGREGATE SHOULDERS, TYPE B	TON	79		79
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	573	573	
50800105	REINFORCEMENT BARS	POUND	38,700	38,700	

SUMMARY OF QUANTITIES (Cont'd)			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X028-2A	I000
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1720	1720	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	246.1	246.1	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250		250
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	54		54
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4
63200310	GUARDRAIL REMOVAL	FOOT	550		550
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2		2
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	68		68
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2760		2760
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	23		23
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2760		2760
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9		9
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6		6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
* A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	9		9
* A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	9		9
* A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	9		9
* D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	9		9
* Z0054505	ROCK FILL - REPLACEMENT	TON	890	890	