

RESURFACING SCHEDULE														
STATION TO STATION	LENGTH	AVERAGE WIDTH OF RESURFACING (PAVEMENT PLUS HMA SHOULDERS)	AREA	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELLING BINDER (MACHINE METHOD) N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP	
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	SQ YD	
95+25.00 TO 95+30.00	5.00	24.0	13.3	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	13.3	
95+25.00 TO 95.55.00	30.00	24.0	80.0	80.0	0.0	0.0	0.0	8.0	0.2	0.0	6.8	2.3	0.0	
95+55.00 TO 250+81.00	15526.00	24.0	41402.7	0.0	41402.7	0.0	0.0	4140.3	82.8	1743.6	3496.7	1049.7	0.0	
250+81.00 TO 251+56.00	75.00	24.0	200.0	0.0	0.0	200.0	0.0	20.0	0.4	8.4	16.9	5.7	0.0	
251+56.00 TO 259+08.00	752.00	32.0	2673.8	0.0	0.0	2005.3	668.4	267.4	5.3	112.5	225.5	0.0	0.0	
259+08.00 TO 260+34.00	126.00	32.0	448.0	0.0	0.0	336.0	112.0	44.8	0.9	18.9	37.8	0.0	0.0	
260+34.00 TO 261+88.00	154.00	32.0	547.6	0.0	0.0	410.7	136.9	54.8	1.1	23.0	46.2	0.0	0.0	
261+88.00 TO 262+31.00	43.00	32.0	152.9	0.0	0.0	114.7	38.2	15.3	0.3	6.4	12.9	0.0	0.0	
262+31.00 TO 263+20.00	89.00	32.0	316.4	0.0	0.0	237.3	79.1	31.6	0.6	13.3	26.7	0.0	0.0	
263+20.00 TO 267+37.00	417.00	32.0	1482.7	0.0	0.0	1112.0	370.7	148.3	3.0	62.4	125.0	0.0	0.0	
267+37.00 TO 272+50.00	513.00	32.0	1824.0	0.0	0.0	1368.0	456.0	182.4	3.6	76.8	153.8	0.0	0.0	
272+50.00 TO 274+00.00	150.00	32.0	533.3	0.0	0.0	400.0	133.3	53.3	1.1	22.4	45.0	0.0	0.0	
274+00.00 TO 274+75.00	75.00	24.0	200.0	0.0	0.0	200.0	0.0	20.0	0.4	8.4	16.9	5.7	0.0	
274+75.00 TO 340+20.00	6545.00	24.0	17453.3	0.0	17453.3	0.0	0.0	1745.3	34.9	735.0	1474.0	468.3	0.0	
340+20.00 TO 340+50.00	30.00	24.0	80.0	80.0	0.0	0.0	0.0	8.0	0.2	0.0	6.8	2.3	0.0	
340+45.00 TO 340+50.00	5.00	24.0	13.3	0.0	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	13.3	
TOTALS			67421	160	58856	6384	1995	6742	135	2831	5691	1534	27	