

PAVEMENT MARKING SCHEDULE	LENGTH	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH
95+25.00 TO 241+12.00	14587.0	32521.0	32521.0	4380.0	487.0	182.0
241+12.00 TO 250+83.00	971.0	3155.8	3155.8	288.0	32.0	12.0
250+83.00 TO 261+08.00	1025.0	3331.3	3331.3	312.0	34.7	13.0
261+08.00 TO 263+48.00	240.0	540.0	540.0	72.0	8.0	3.0
263+48.00 TO 273+35.00	987.0	3207.8	3207.8	300.0	33.3	12.0
273+35.00 TO 281+04.00	769.0	3076.0	3076.0	228.0	25.3	10.0
281+04.00 TO 290+04.00	900.0	2925.0	2925.0	276.0	30.7	11.0
290+04.00 TO 340+50.00	5046.0	11203.5	11203.5	1512.0	168.0	63.0
TOTALS		59960.0	59960.0	7368.0	819.0	306.0

PAVEMENT PATCHING SCHEDULE	CLASS D PATCHES, TYPE II 14 INCH	CLASS D PATCHES, TYPE III 14 INCH	CLASS D PATCHES, TYPE IV 14 INCH
LOCATION	SQ YD	SQ YD	SQ YD
US 45 (NB)	488.0	18.0	0.0
US 45 (SB)	409.0	19.0	100.0
TOTALS	897.0	37.0	100.0

PERMANENT SURVEY MARKERS, TYPE I

LOCATION (STATION)	DESCRIPTION (PC, PT, PI, POT)	QUANTITY (EACH)
231+94.29	P. O. T.	1
244+58.82	P. C.	1
247+08.82	P. I.	1
249+58.82	P. T.	1
250+80.76	P. C.	1
256+05.77	P. I.	1
261+30.76	P. T.	1
273+95.21	P. I.	1
288+50.88	P. O. T.	1
TOTAL =		9