

PAVEMENT MARKING SCHEDULE

STATION TO STATION			SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING, LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER
LOCATION			(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)
0+05	TO	0+00	1	1	0.30		1	0
0+00 BK = 20+00 AH			0	0	0.00		0	0
20+00	TO	0+00	400	500	133.30		500	25
0+00 BK = 0+00 AH			0	0	0.00		0	0
0+00	TO	7+59	152	1462	50.60		1462	9
7+59	TO	9+68.5	60	329	20.10		329	3
9+68.5	TO	33+34	455	749	151.60		749	30
33+34	TO	44+16	216	2270	72.10	2270		14
44+16	TO	73+72	591	6152	197.10	6152		37
73+72	TO	103+00	586	7868	195.20	7868		37
103+00	TO	106+77	75	1508	25.10	1508		5
106+77	TO	108+40	33	652	10.90	652		2
108+40	TO	111+26	57	1122	19.10	1122		4
111+26	TO	113+97	54	955	18.10	955		3
113+97	TO	116+80	57	920	18.90	920		4
116+80	TO	118+29	30	484	9.90	484		2
118+29	TO	139+76.35	429	5403	143.20	5403		27
139+76.35 BK = 142+70.95 AH			0	0	0.00	0		0
142+70.95	TO	379+18.09	4729	51738	1576.50	51738		296
379+18.09 BK = 0+00 AH			0	0	0.00	0		0
0+00	TO	45+77	915	10298	305.10	10298		57
TOTAL			8841	92410	2947	89369	3041	553

PAVING SCHEDULE

LOCATION			BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	TEMPORARY RAMP	TEMPORARY RAMP, SPECIAL	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	AGGREGATE SHOULDERS, TYPE B
LOCATION			(GALLON)	(TON)	(SQ YD)	(SQ YD)	(TON)				(TON)
0+05	TO	0+00	2.00	0.04	14.40			1.68		811.40	
0+00 BK = 20+00 AH											
20+00	TO	0+00	879.14	17.58	194.90			672.00		8000.00	
0+00 BK = 0+00 AH			0.00	0.00							
0+00	TO	7+59	269.87	5.40			38.00	226.69		2698.67	
7+59	TO	9+68.5	67.51	1.35				56.70		675.06	
9+68.5	TO	33+34	684.26	13.68			136.90	574.03		6833.67	
33+34	TO	44+16	359.36	7.19				287.77	3425.78		15.16
44+16	TO	73+72	896.18	17.92				717.32	8539.56		76.99
73+72	TO	103+00	940.30	18.81				770.11	9168.00		44.10
103+00	TO	106+77	139.63	2.79				110.84	1549.89		25.21
106+77	TO	108+40	57.05	1.14				39.55	570.50		
108+40	TO	111+26	121.60	2.43	123.00			69.40	1175.78		
111+26	TO	113+97									
113+97	TO	116+80	116.34	2.33	123.33	5.80		68.67	1163.44		
116+80	TO	118+29	56.33	1.13		5.80		43.81	521.50		
118+29	TO	139+76.35	625.07	12.50				521.09	6203.46		60.40
139+76.35 BK = 142+70.95 AH											
142+70.95	TO	379+18.09	6922.77	138.46				5738.37	68313.96		646.44
379+18.09 BK = 0+00 AH											
0+00	TO	45+77	1328.51	26.57	86.67	5.80		1110.69	13222.44		128.20
TOTAL			13466	269	334	227	175	11009	113855	19019	997

