

RESURFACING SCHEDULE												
STATION TO STATION		LENGTH	AVERAGE WIDTH OF RESURFACING (PAVEMENT PLUS HMA SHOULDERS)	AREA	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
		FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD
655+75.00	TO 656+05.00	30.00	24.0	80	80	0	0	8	0.2	7	2	13.3
656+05.00	TO 722+38.00	6633.00	24.0	17688	0	17688	0	1769	35.4	1486	614	0.0
722+38.00	TO 733+10.00	1072.00	27.0	3216	0	3216	0	322	6.4	270	95	0.0
733+10.00	TO 749+90.00	1680.00	24.0	4480	0	4480	0	448	9.0	376	150	0.0
749+90.00	TO 760+65.00	1075.00	27.0	3225	0	3225	0	323	6.5	271	102	0.0
760+65.00	TO 811+09.00	5044.00	24.0	13451	0	13451	0	1345	26.9	1130	462	0.0
811+09.00	TO 823+47.00	1238.00	27.0	3714	0	3714	0	371	7.4	312	111	0.0
823+47.00	TO 834+49.00	1102.00	27.0	3306	0	3306	0	331	6.6	278	103	0.0
834+49.00	TO 845+28.00	1079.00	24.0	2877	0	2877	0	288	5.8	242	95	0.0
845+28.00	TO 846+51.00	123.00	30.0	410	0	410	0	41	0.8	34	9	0.0
846+51.00	TO 846+81.00	30.00	30.0	100	100	0	0	10	0.2	8	3	13.3
846+81.00	TO 847+85.00	104.00	BRIDGE - PAVING OMISSION									
847+85.00	TO 848+15.00	30.00	30.0	100	100	0	0	10	0.2	8	3	13.3
848+15.00	TO 848+35.00	20.00	30.0	67	0	67	0	7	0.1	6	2	0.0
848+35.00	TO 885+39.00	3704.00	24.0	9877	0	9877	0	988	19.8	830	338	0.0
885+39.00	TO 885+69.00	30.00	28.0	93	0	0	93	9	0.2	8	3	0.0
885+69.00	TO 887+87.00	218.00	VAR.	856	0	0	856	86	1.7	72	21	83.3
TOTALS												
				62684	280	62311	949	6354	127	5337	2115	123