

PAVEMENT MARKING SCHEDULE		LENGTH	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PAINT PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 24"
STATION TO STATION		FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	FOOT	FOOT
655+75.00	TO 714+93.00	5918.0	13196	13196	1776	197.3	74	0	0
714+93.00	TO 724+53.00	960.0	3120	3120	288	32.0	12	0	0
724+53.00	TO 727+54.00	301.0	1204	1204	96	10.7	4	0	0
727+54.00	TO 739+18.00	1164.0	3623	3623	348	38.7	15	0	0
739+18.00	TO 744+36.00	518.0	1166	1166	156	17.3	6	0	0
744+36.00	TO 754+60.00	1024.0	3328	3328	312	34.7	13	0	0
754+60.00	TO 755+93.00	133.0	532	532	36	4.0	2	0	0
755+93.00	TO 764+49.00	856.0	2782	2782	252	28.0	11	0	0
764+49.00	TO 881+47.00	11698.0	26147	26147	3504	389.3	146	0	0
881+47.00	TO 884+91.00	344.0	1118	1118	108	12.0	4	0	0
884+91.00	TO 887+30.00	239.0	956	956	72	8.0	3	32	0
887+30.00	TO 887+74.00	44.0	99	99	12	1.3	1	0	27
TOTALS		23199	57270	57270	6960	773.3	291	32	27

PAVEMENT PATCHING SCHEDULE	PAVEMENT PATCHING, TYPE I	PAVEMENT PATCHING, TYPE II	PAVEMENT PATCHING, TYPE III	PAVEMENT PATCHING, TYPE IV
	15 INCH	15 INCH	15 INCH	15 INCH
LOCATION	SQ YD	SQ YD	SQ YD	SQ YD
IL 49 (NB)	10	460	138	36
IL 49 (SB)	10	520	112	29
TOTALS	20	980	250	65

SURVEY MONUMENT SCHEDULE			PERMANENT SURVEY MARKERS TO BE ADJUSTED	SURVEY MARKER VAULT	FURNISH AND INSTALLING PROPERTY MARKERS
STATION	O/S	DESCRIPTION	EACH	EACH	EACH
805+13	4' LT	SURVEY MARKER VAULT	1		
836+81.75	0	IRON PIN BURIED +/- 4 INCHES		1	
872+22	0	MAG NAIL IN PAVEMENT		1	1
TOTALS			1	2	1