

PAVING SCHEDULE

PAVEMENT						BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT MIX ASPHALT SURFACE REMOVAL 2 1/4"	HOT MIX ASPHALT SURFACE REMOVAL, COMPLETE	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", NIOS	POLYMERIZED LEVELING BINDER (MACHINE METHOD)	AGGREGATE SHOULDERS, TYPE B	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
STATION TO	STATION	LENGTH FEET	WIDTH FEET	AREA SQ YD	GALLON									
50+89.45	TO	51+09.45	20.0	52.7	117.1	11.7	0.2		117.1	9.8	6.6		117.1	73.2
51+09.45	TO	51+23.74	14.3	53.3	84.5	8.5	0.2		84.5	7.1	4.7			
51+23.74	TO	52+18.39	94.7	40.5	425.9	42.6	0.9		425.9	35.8	21.4			
52+18.39	TO	53+01.05	82.7	48.5	445.4	44.5	0.9		445.4	37.4	24.9			
53+01.05	TO	55+63.05	262.0	52.1	1,516.7	151.7	3.0		1516.7	127.4	84.9			
55+63.05	TO	57+64.18	201.1	44.2	987.8	98.8	2.0		987.8	83.0	59.4			
57+64.18	TO	64+48.88	684.7	40.2	3,057.6	305.8	6.1		3057.6	256.8	171.2			
64+48.88	TO	65+07.77	58.9	38.0	248.6	24.9	0.5		248.6	20.9	13.9			
65+07.77	TO	65+53.08	45.3	41.7	209.9	21.0	0.4		209.9	17.6	10.7			
65+53.08	TO	66+37.79	84.7	49.5	465.9	46.6	0.9		465.9	39.1	26.1			
66+37.79	TO	67+22.47	84.7	47.5	446.9	44.7	0.9		446.9	37.5	25.0			
67+22.47	TO	71+21.24	398.8	51.8	2,295.1	229.5	4.6		2295.1	192.8	128.5			
71+21.24	TO	71+46.24	25.0	54.0	150.0	15.0	0.3	150.0		12.6	6.3			
71+46.24	TO	72+02.20	56.0	52.4	325.8	32.6	0.7	325.8		27.4	13.7			
72+02.20	TO	76+63.83	461.6	43.2	2,215.8	221.6	4.4	2215.8		186.1	93.1	11.7		
76+63.83	TO	80+17.07	353.2	36.8	1,444.4	144.4	2.9	1444.4		121.3	60.7	29.8		
80+17.07	TO	82+32.47	215.4	34.0	813.7	81.4	1.6	813.7		68.4	34.2	16.2		
82+32.47	TO	82+65.95	33.5	30.0	111.6	11.2	0.2	111.6		9.4	4.7	1.4		
82+65.95	TO	93+00.00												
93+00.00	TO	95+10.00	210.0	26.0	606.7	60.7	1.2	606.7		51.0	25.5	8.5		
95+10.00	TO	95+25.00	15.0	26.0	43.3	4.3	0.1			3.6	1.8	3.0	43.3	40.0
SOUTH I-57/70 RAMPS			20.0	Variable	491.0	49.1	1.0			41.2	27.5		491.0	73.5
NORTH I-57/70 RAMPS			20.0	Variable	450.0	45.0	0.9			37.8	25.2		450.0	73.2
PROJECT TOTALS			3,442		16,954	1,696	34	5,668	10,302	1,424	870	71	1101	260