

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKING SCHEDULE				SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 6"	TEMPORARY PAVEMENT MARKING-LINE 8"	TEMPORARY PAVEMENT MARKING-LINE 12"	TEMPORARY PAVEMENT MARKING-LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING -LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	PRISMATIC CURB REFLECTORS
STATION		STATION	FEET	FT.	SQ. FT.	FT.	FT.	FT.	FT.	FT.	FT.	SQ. FT.	FT.	FT.		FT.	FT.	EACH	EACH
50+89.42	TO	52+19.71	130.3	27.6		483.4			36.6		200.0		483.4			36.6		2	8
52+19.71	TO	52+99.71	80.0			80.0				18.5	26.7		80.0				18.5	0	0
52+99.71	TO	65+54.33	1,254.6	1,046.0	62.4	4,934.7	261.6			18.0	1,925.3	62.4	4,934.7	261.6			18.0	7	82
65+54.33	TO	66+36.53	82.2			82.2				18.4	27.4		82.2				18.4	0	0
66+36.53	TO	72+00.96	564.4	2,288.0	93.6	2,493.8	297.2			44.4	1,370.5	93.6	2,493.8	297.2			44.4	33	9
72+00.96	TO	73+45.86	144.9															0	0
73+45.86	TO	80+09.96	664.1	1,326.9	83.2	3,604.6	116.9		85.8	27.4	1,649.2	83.2	3,604.6	116.9		85.8	27.4	37	0
80+09.96	TO	82+65.95	256.0	1,126.4		832.0					371.2		832.0					3	0
82+65.95	TO	93+00.00	1,034.1															0	0
93+00.00	TO	95+25.00	225.0	990.0		731.3					326.3		731.3					3	0
SOUTH I-57/70 RAMPS								201.1	260.4		434.0				201.1	260.4			12
NORTH I-57/70 RAMPS								211.5	290.0		468.6				211.5	290.0			12
PROJECT TOTALS			4,436	6,805	239	13,242	676	413	673	127	6,799	239	13,242	676	413	673	127	85	123

PATCHING SCHEDULE

LOCATION	CLASS B PATCHES, TYPE II, 12" SQ. YD	CLASS B PATCHES, TYPE III, 12" SQ. YD	PAVEMENT FABRIC SQ. YD	SAW CUTS FOOT	DOWEL BARS EACH
US 45 NB / SB	412.4	43.3	43.3	3,075.0	1,372.0
TOTALS	412.4	43.3	43.3	3,075.0	1,372.0

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

LOCATION				EA.
57+11.85	TO	57+61.85	LT.	1.0

GUARDRAIL REMOVAL

LOCATION				LENGTH
57+36.85	TO	57+61.85	LT.	25 FT.