

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 RURAL			CODE NO	ITEM	UNIT		1000 RURAL		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	204	204			542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	90	90		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	50	50			542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	76	76		
20200100	EARTH EXCAVATION	CU YD	1260	1260			542D1075	PIPE CULVERTS, CLASS D, TYPE 2 30"	FOOT	103	103		
20300100	CHANNEL EXCAVATION	CU YD	436	436			63200310	GUARDRAIL REMOVAL	FOOT	15	15		
20400800	FURNISHED EXCAVATION	CU YD	2665	2665			* 63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3		
* 25000200	SEEDING, CLASS 2	ACRE	1.75	1.75			66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	12	12		
* 25000314	SEEDING, CLASS 4B	ACRE	0.5	0.5			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	210	210			67100100	MOBILIZATION	L SUM	1	1		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	210	210			70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	210	210			70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
* 25100115	MULCH, METHOD 2	ACRE	9	9			70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
25100630	EROSION CONTROL BLANKET	SQ YD	65	65			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	630	630			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	452	452		
28000305	TEMPORARY DITCH CHECKS	FOOT	90	90			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10291	10291		
28000400	PERIMETER EROSION BARRIER	FOOT	1522	1522			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3583	3583		
28000500	INLET AND PIPE PROTECTION	EACH	14	14			* 72000100	SIGN PANEL - TYPE 1	SQ FT	41	41		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2572	2572			* 72000200	SIGN PANEL - TYPE 2	SQ FT	16	16		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	22	22			72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	79	79		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4			* 73000100	WOOD SIGN SUPPORT	FOOT	156	156		
40600300	AGGREGATE (PRIME COAT)	TON	13	13			* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10291	10291		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	511	511			* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	384	384			78300100	PAVEMENT MARKING REMOVAL	SQ FT	250	250		
40600990	TEMPORARY RAMP	SQ YD	22	22			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	7		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	832	832			* A2006920	TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9	9		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	23	23			* A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9		
44000100	PAVEMENT REMOVAL	SQ YD	1153	1153			* B2001260	TREE, CORNUS ALTERNIFOLIA (PAGODA DOG WOOD), 3' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	2	2		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	533	533			* B2001316	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2		
44000400	GUTTER REMOVAL	FOOT	602	602									
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	116	116									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	67	67									
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1									
50105225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	31	31									
54213450	END SECTIONS 15"	EACH	6	6									
54213465	END SECTIONS 30"	EACH	4	4									

* SPECIALTY ITEM

FILE NAME =	USER NAME = tharp1	DESIGNED - R. THARP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	DR&SBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\pw_work\PWIDOT\THARPR\dm52424\d876132-shr-S00.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN - R. THARP	REVISED -			322&2	95-AC & 32B-I	WASHINGTON	63	3	
PLOT DATE = 12/10/2009	DATE - 7/29/2009	CHECKED - A. MUEHLFELD	REVISED -			CONTRACT NO. 76132					
		DATE - 7/29/2009	REVISED -			SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	