6/28/2007

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 76323

IDOT HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
202001-01	EARTH MEDIAN DITCH CHECK
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
406001-05	ENTRANCE RAMP TERMINAL (FLEXIBLE RAMP PAVEMENT ADJACENT TO FLEXIBLE MAINLINE PAVEMENT)
406101-04	EXIT RAMP TERMINAL (FLEXIBLE RAMP PAVEMENT ADJACENT TO FLEXIBLE MAINLINE PAVEMENT)
420401-08	BRIDGE APPROACH PAVEMENT
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
542206-01	REINFORCED CONCRETE END SECTIONS FOR PIPE CULVERTS 1050 mm (42") THRU 1500 mm (60") DIAMETER SKEWED WITH ROADWAY
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
542311-01	GRATING FOR CONCRETE FLARED END SECTION FOR 600 mm (24") THRU 1300 mm (54") PIPE
542401-01	METAL END SECTION FOR PIPE CULVERTS
542606-01	REINFORCED CONCRETE PIPE TEE
601001-03	SUB-SURFACE DRAINS
601101-01	CONCRETE HEADWALL FOR PIPE DRAIN
602401-02	MANHOLE, TYPE A
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	CAST IRON STEPS
604001-03	FRAME AND LIDS, TYPE 1
604101-01	MEDIAN INLET FOR 600 mm (24") REINFORCED CONCRETE PIPE
609006-05	BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
630001-08	STEEL PLATE BEAM GUARDRAIL
630201-06	PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
631011-06	TRAFFIC BARRIER TERMINAL TYPE 2
631026-05	TRAFFIC BARRIER TERMINAL TYPE 5 & 5A
631031-08	TRAFFIC BARRIER TERMINAL TYPE 6
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
642001-01	SHOULDER RUMBLE STRIPS
665001-02	WOVEN WIRE FENCE
666001-01	RIGHT OF WAY MARKERS
667101-01	PERMANENT SURVEY MARKERS
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5 m AWAY
701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 m TO 600 mm FROM PAVEMENT EDGE
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 4.5 m TO 600 mm FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5 m AWAY
701602-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
702001-06	TRAFFIC CONTROL DEVICES
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
780001-02	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

LEGEND

	EXISTING DITCH
	PROPOSED STANDARD DITCH (SEE TYPICAL SECTIONS)
	PROPOSED SPECIAL DITCH
	PROPOSED DITCH SUMMIT
BOP	BEGINNING OF PROFILE GRADE
EOP	END OF PROFILE GRADE
TBR	ITEM TO BE REMOVED
	RIPRAP
	TREE TO BE REMOVED (INDIVIDUAL)
	EARTH MEDIAN DITCH CHECK (STD 202001)
	TREES TO BE REMOVED (AREA)

INDEX OF SHEETS

1	COVER SHEET
2-3	GENERAL NOTES, STANDARDS, INDEX OF SHEETS AND LEGEND
4-7	SUMMARY OF QUANTITIES
8-15	TYPICAL SECTIONS
16-29	SCHEDULES OF QUANTITIES
30-33	GENERAL LAYOUT & HORIZONTAL CONTROL
34-44	HORIZONTAL CONTROL TIES
45-79	FAP 310 (IL 255) PLAN AND PROFILE SHEETS
80-87	INTERCHANGE RAMP PROFILES
88-89	SUPERELEVATION TABLES
90-136	PLAT OF HIGHWAYS SHEETS
137-142	CLEAR ZONE AND SLOPE TRANSITION SHEETS
143-150	INFIELD RAMP GRADING PLAN SHEETS
151-166	RAMP TERMINAL DETAIL SHEETS
167-187	PAVEMENT MARKING PLAN SHEETS
188-195	STORM WATER POLLUTION PREVENTION PLAN
196-243	SOIL STRATA PLAN AND PROFILE SHEETS
244-252	ROCK CREEK CULVERT PLANS
253-258	GUARDRAIL AND SHOULDER WIDENING DETAILS
259-260	HEADWALL DETAILS
261-262	BRIDGE APPROACH PAVEMENT (SPECIAL) DETAILS
263-265	MISCELLANEOUS DETAILS
266-357	FAP 310 (IL 255) CROSS SECTIONS
358-372	CULVERT CROSS SECTIONS
373-457	RAMP CROSS SECTIONS
458-474	MISCELLANEOUS GRADING CROSS SECTIONS

Rev.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS
FAP 310 (IL 255)
SECTION 60-15
MADISON COUNTY

DRAWN BY EBB

DATE

CHECKED BY

p:\00files\00024\dmainline\detailsmisc\gnotes.dgn