

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76323

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN		
				80% FEDERAL 20% STATE		
				SEC 60-15 I000	SEC 60-15B X028-2A	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0038500	PERMANENT BARRICADES	EACH	12	12		
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	1	1		
Z0065100	SETTLEMENT PLATFORMS	EACH	1	1		
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	934	934		
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	408	408		
M2010500	TREE REMOVAL, HECTARES	HA	23.4	23.4		
M2020010	EARTH EXCAVATION	CU M	775915	775915		
M2040800	FURNISHED EXCAVATION	CU M	371210	371210		
M2500200	SEEDING, CLASS 2	HA	45.3	45.3		
M2080150	TRENCH BACKFILL	CU M	430	430		
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	4530	4530		
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	4530	4530		
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	4530	4530		
M2510115	MULCH, METHOD 2	HA	45.3	45.3		
M2510630	EROSION CONTROL BLANKET	SQ M	36525	36525		
M2800200	EARTH EXCAVATION FOR EROSION CONTROL	CU M	300	300		
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	15000	15000		
M2800400	PERIMETER EROSION BARRIER	METER	549	549		
M2801000	AGGREGATE (EROSION CONTROL)	M TON	3495	3495		
M2810109	STONE RIPRAP, CLASS A5	SQ M	432		432	
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	7826	7826		
M2810725	STONE DUMPED RIPRAP, CLASS B3	SQ M	4360	4360		
M2811840	RIPRAP FOR STILLING BASIN	M TON	5695	5695		
M2820200	FILTER FABRIC	SQ M	10917	10485	432	
M3020456	PROCESSING MODIFIED SOIL 300MM	SQ M	163342	163342		
M3101500	LIME	M TON	3359.7	3359.7		
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	M TON	29014	29014		
M4060895	CONSTRUCTING TEST STRIP	EACH	2	2		
M4075390	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 390MM	SQ M	82448	82448		
M4075400	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 400MM	SQ M	14463	14463		
M4205000	BRIDGE APPROACH PAVEMENT	SQ M	437	437		
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	1225	1225		
M4205200	PROTECTIVE COAT	SQ M	1662	1662		
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	14526	14526		
M4820600	HOT-MIX ASPHALT SHOULDERS, 200MM	SQ M	57234	57234		
M5010522	PIPE CULVERT REMOVAL	METER	54	54		
M5080105	REINFORCEMENT BARS	KG	529240	2020	527220	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAP 310 (IL 255)  
 SECTION 60-15  
 MADISON COUNTY  
 DRAWN BY EBB  
 CHECKED BY  
 DATE

Rev.