6/28/2007

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 76323

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

CULVERT SCHEDULE

STATION	SIDE	PIPE CULVERTS												REINFORCED CONCRETE PIPE TEE		
		TYPE 1 RCCP 600MM	TYPE 1 RCCP 900MM	TYPE 2 RCCP 600MM	TYPE 2 RCCP 900MM	TYPE 3 RCCP 300MM	TYPE 3 RCCP 600MM	TYPE 4 RCCP 600MM	TYPE 4 RCCP 900MM	TYPE 4 RCCP 1350MM	TYPE 4 RCCP 1800MM	TYPE 5 RCCP 1050MM	TYPE 6 RCCP 600MM	TYPE 7 RCCP 1200MM	600MM PIPE WITH 600MM RISER	900MM PIPE WITH 600MM RISER	1200MM PIPE WITH 600MM RISER
		METER													EACH		
FAP 310																	
35+291.0	LT & RT																
35+495.0	LT												48.3				
35+950.0	RT							36.5									
36+395.0	LT & RT				50.6											1	
36+737.0	LT & RT												8.2	112.2			1
36+975.0	LT & RT					8.7			69.0								
37+397.0	LT & RT																
37+450.0	RT	0.5		29.8											1		
37+700.0	LT			22.3											1		
37+956.0	LT & RT			3.5													
38+150.0	LT & RT									73.4							
38+373.0	RT			29.7											1		
39+540.0	LT			29.4											1		
39+603.0	RT						18.4										
39+700.0	LT & RT											125.7					
40+310.5	RT			30.3											1		
40+405.0	LT			11.3													
RAMP A																	
0+175.0	LT & RT																
RAMP B					22.1												
0+375.0	LT & RT																
HUMBERT RAMP C			15.6														
0+065.0	LT & RT																
HUMBERT RAMP D					18.1												
0+340.0	LT & RT																
RAMP F					19.6												
0+150.0	LT & RT										41.2						
TOTALS		0.5	15.6	156.3	110.4	8.7	18.4	36.5	69.0	73.4	41.2	125.7	56.5	112.2	5	1	1
USE		0.5	16.0	156.5	110.5	9.0	18.5	36.5	69.0	73.5	41.5	126.0	56.5	112.5	5	1	1

CULVERT SCHEDULE CONTINUED

STATION	SIDE	PRECAST REINFORCED CONCRETE FLARED END SECTIONS						CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 1200MM	GRATING FOR CONCRETE FLARED END SECTION		MEDIAN INLET (604101)	REINFORCEMENT BARS	PRECAST CONCRETE BOX CULVERT 2.4M X 2.1M	CONCRETE BOX CULVERTS	CONCRETE HEADWALLS	MANHOLES, TYPE A		MANHOLES SPECIAL 1.5M DIAMETER
		300MM	600MM	900MM	1050MM	1350MM	1800MM		600MM	900MM						1.2M DIAMETER WITH MEDIAN INLET (604101)	1.5M DIAMETER TYPE 1 FRAME OPEN LID	
		EACH						EACH	EACH		EACH	KG	METER	CU M	CU M	EACH		
FAP 310																		
35+291.0	LT & RT											527220		2878.2				
35+495.0	LT		1													1		
35+950.0	RT		1													1		
36+395.0	LT & RT			2							1							
36+737.0	LT & RT							2			1							
36+975.0	LT & RT	1		1														1
37+397.0	LT & RT											1060	103.3		21.4			
37+450.0	RT		1								1							
37+700.0	LT		1						1		1							
37+956.0	LT & RT										1	960	78.1		19.0			
38+150.0	LT & RT					2												
38+373.0	RT		1								1						1	
39+540.0	LT		1								1							
39+603.0	RT		1														1	
39+700.0	LT & RT				2													
40+310.5	RT		1								1						1	
40+405.0	LT		1														1	
RAMP A																		
0+175.0	LT & RT			2														
RAMP B																		
0+375.0	LT & RT			2														
HUMBERT RAMP C										1								
0+065.0	LT & RT			2														
HUMBERT RAMP D										1								
0+340.0	LT & RT			2														
RAMP F										1								
0+150.0	LT & RT						2											
TOTALS		1	9	11	2	2	2	2	1	3	8	529240	181.4	2878.2	40.4	2	4	1
USE		1	9	11	2	2	2	2	1	3	8	529240	181.4	2878.2	40.4	2	4	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
FAP 310 (IL 255)
SECTION 60-15
MADISON COUNTY

DRAWN BY EBB
DATE
CHECKED BY

p:\00files\00024\dmainline\schedules\schedquant015a.dgn