F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	225
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76323

ENTRANCE RAMP C

RC-SB 3 BEGINNING ELEV. 187.25

RC-SB 3

	Qu	W%
GRAY SILTY LOAM	57 S/15	24 28
BRAY & BROWN SILTY CLAY	153 S/10	
GRAY SILTY CLAY LOAM	96 B	27
	115 S/20	26
	115 B	26
GRAY & BROWN CLAY LOAM	134 S/15	23
	172 S/10	22
	134 S/15	20
	249 S/10	13
GRAY SAND (FINE TO COARSE)	NC	13 19
GRAY SANDY SILT	NC	
BROWN & GRAY SILTY SAND (FINE TO COURSE) W/SOME GRAVEL	NC	13
BROWN & GRAY GRAVELLY SAND/ GRAY CLAY LOAM	NC	11
	245 S/15	12

PROPOSED RAMP PROFILE

PROPOSED MAINLINE PROFILE
OUTSIDE EDGE OF PAVEMENT

RC-SB 2 BEGINNING ELEV. 187.35

RC-SB 2

	Qu	W%
GRAY SILT LOAM	77 S/15	23
GRAY & BROWN CLAYEY SILT	144 S/18	26
GRAY SILTY LOAM A-6(9)	144 S/15	25
	163 S/15	21
BROWN & GRAY SILTY LOAM	163 S/10	19
	144 S/10	26
	86 S/10	20
	575 S/15	17

BORING 5/22/01

RC-SB 2 ENDING ELEV. 181.0

RC-SB 3 ENDING ELEV. 177.9

BORING 5/23/01

EXISTING GROUND PROFILE

RC-SB 6

	Qu	W%
GRAY SILTY CLAY LOAM	134 S/15	25
	163 S/15	21
BROWN & GRAY CLAY LOAM	268 S/10	20
	211 S/10	20
	182 S/15	19
BROWN SANDY CLAY LOAM	NC	23
BROWN & GRAY CLAY LOAM	249 S/15	12
	278 S/10	10

RC-SB 6 BEGINNING ELEV. 185.7

RC-SB 6 ENDING ELEV. 179.1

BORING 1/7/02

SOIL STRATA PROFILE SHEETS ARE PROVIDED AS A REFERENCE FOR SOIL AND GROUNDWATER INFORMATION ONLY.

202 200 198 196 194 192 190 188 186 184 182 180

188.449 188.834 | 188.309 191.371 | 187.735 194.113 | 187.389 196.233 | 186.829 197.353 | 187.332 197.473 | 184.957 196.675 | 185.590 195.52 | 186.989 194.089 | 187.721 192.605

0+000 0+050 0+100 0+150 0+200 0+250 0+300 0+350 0+400 0+450 0+500 0+550

RAMP C PROFILE SHEET

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK		
TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK		
TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		

2:13:59 PM

p:\00files\00024\mainline\soilstrata\prof-ramp-c.dgn