EXIT RAMP D

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	227
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76323

RD-SB 6 BEGINNING
ELEV. 187.25, STA. 0+225

RD-SB 6

Qu	W%		
172 S/10	27	GRAY & BROWN SILTY CLAY	
96 S/15	27	GRAY SILTY CLAY LOAM	
115 S/15	24		
134 S/15	23	BROWN & GRAY CLAY LOAM	
153 S/15	22		
186 S/15	23		
96 S/10	21	GRAY CLAYEY GRAVELLY SAND	
NC	25		
105 S/15	13		

PROPOSED MAINLINE PROFILE
OUTSIDE EDGE OF PAVEMENT

PROPOSED RAMP PROFILE

EXISTING GROUND PROFILE

RD-SB 2 BEGINNING
ELEV. 187.32

RD-SB 2

Qu	W%		
172 S/10	28	BROWN SILTY CLAY	
96 S/20	28		
57 B	30	BROWN & GRAY SILTY CLAY LOAM	
172 S/15	26		
278 S/15	20	GRAY CLAY LOAM	
144 S/10	25		
201 S/15	22		
230 S/15	22		
364 S/15	11		
NC	17	GRAY SAND W/SOME GRAVEL	

BORING 5/9/01

RD-SB 2 ENDING
ELEV. 179.5

RD-SB 4 BEGINNING
ELEV. 187.32

RD-SB 4

Qu	W%		
163 S/10	29	GRAY & BROWN SILTY CLAY	
134 S/10	28	GRAY SILTY CLAY LOAM	
144 S/15	27		
115 S/15	26		
230 S/15	21	BROWN & GRAY CLAY LOAM	
163 S/10	25		
144 S/10	23		
144 S/10	14		
431 S/15	11	GRAY SAND W/ SOME GRAVEL	
NC	17	GRAY CLAY LOAM	
575 S/15	11	GRAY GRAVELLY SAND	
NC	16		

BORING 5/14/01

RD-SB 4 ENDING
ELEV. 179.5

BORING 5/15/01

RD-SB 6 ENDING
ELEV. 180.9

SOIL STRATA PROFILE SHEETS ARE PROVIDED AS A REFERENCE FOR SOIL AND GROUNDWATER INFORMATION ONLY.

184.915 198.142	188.745 199.097	187.128 199.447	187.347 198.797	187.690 197.147	187.336 194.517	187.531 191.567	187.917 188.771	188.021 187.783	
0+000	0+050	0+100	0+150	0+200	0+250	0+300	0+350	0+400	0+450

RAMP D PROFILE SHEET

FINAL SURVEY NOTE BOOK — NO. — BY — DATE
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED

ORIGINAL SURVEY NOTE BOOK — NO. — BY — DATE
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED

2:14:38 PM

p:\00files\00024\dmainline\soilstrata\prof-ramp-d a.dgn