

DRIVEWAY PAVEMENT REMOVAL SCHEDULE			
LOCATION	SIDE	TYPE	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
IL RTE 159			
107+55.3 TO 109+75.0	RT	BIT/CONC	712
109+75.0 TO 116+50.0	RT	BIT/CONC	1682
111+41.7	LT	CONC	134
112+74.7	LT	BIT	158
113+84.1	LT	BIT	150
116+87.1 TO 119+72.7	LT	BIT	342
119+78.0	RT	BIT	125
121+24.0	LT	BIT	116
121+33.0	RT	CONC	197
126+34.7	LT	CONC	314
127+09.3 TO 131+44.0	LT	BIT/CONC	3056
134+94.5	RT	CONC	10
135+42.9 TO 136+69.7	LT	BIT/CONC	187
137+26.0	LT	CONC	11
137+80.1	LT	CONC	9
138+54.5	LT	CONC	12
139+22.4	LT	CONC	15
142+11.2	LT	BIT/CONC	139
142+63.8	RT	CONC	13
144+55.7	RT	BIT/CONC	77
145+42.7	LT	CONC	18
145+88.6	LT	CONC	19
146+25.6	LT	CONC	23
146+66.6	LT	CONC	7
147+79.1	LT	BIT/CONC	89
148+35.0	LT	BIT/CONC	58
148+55.8	LT	CONC	7
149+32.0	LT	BIT	59
150+84.0	LT	BIT	353
152+89.8	LT	BIT	147
154+36.4 TO 154+99.2	LT	BIT	187
155+05.6 TO 155+88.6	LT	BIT/CONC	254
S CLINTON ST			
7+51.7	LT	CONC	10
8+16.3	LT	CONC	11
8+45.7	LT	CONC	43
8+53.4	RT	BIT	19
8+84.0	LT	BIT	26
8+94.5	RT	CONC	44
S LOOP ST / S CHESTNUT ST			
16+69.6	RT	BIT/CONC	32
17+67.0	RT	BIT	78
18+92.3	RT	BIT	298
19+28.7	RT	BIT	87
20+71.8	RT	CONC	22
21+07.5	LT	BIT	34
21+32.3	LT	BIT/CONC	57
HILL ST			
0+45.7 TO 0+87.0	LT	BIT	128
ALLEY @ 149+27			
0+56.6 TO 1+24.5	LT	BIT/CONC	174
JIM'S ALLEY			
0+34.3 TO 1+55.0	LT	BIT	323
0+51.8 TO 0+99.6	RT	BIT	46
CHURCH ST			
29+08.2	RT	CONC	78
29+22.8	LT	CONC	26
TEMPORARY MCKINLEY CONNECTOR			
	LT	BIT	205
TOTAL			10421

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
LOCATION	RAISED REFLECTIVE PAVEMENT MARKERS	
	ONE WAY CRYSTAL MARKER (EA)	TWO WAY AMBER MARKER (EA)
IL RTE 159		
102+00.00 TO 109+75.00	19	38
109+75.00 TO 130+00.00	51	102
130+00.00 TO 145+00.00	38	38
145+00.00 TO 156+02.00	28	56
TOTAL		370

TEMPORARY RAMP & TEMPORARY ASPHALT WEDGE SCHEDULE		
LOCATION	TEMPORARY RAMP (SQ YD)	TEMPORARY ASPHALT WEDGE (SQ YD)
IL RTE 159		
102+00.00	74.0	
WEST EOP 138+70 TO 150+10		380.0
156+02.00	50.9	
CHEROKEE DR		
	19.8	
IDLEWOOD DR		
1+20.00	20.8	
MCKINLEY AVE		
1+78.69	12.8	
S CLINTON ST		
7+26.14	21.1	
12+26.66	22.6	
S LOOP ST / S CHESTNUT ST		
16+50.00	11.7	
21+90.00	16.6	
N LOOP ST		
2+72.77	13.8	
HILL ST		
0+87.00	19.9	
ALLEY @ 149+27		
1+60.00	16.8	
JIM'S ALLEY		
1+55.00	14.8	
ALLEY @ 152+00		
10+60.47	15.6	
CHURCH ST		
27+35.00	22.1	
32+67.00	22.2	
ALLEY @ 156+02		
11+20.00	8.2	
12+75.00	8.9	
TOTALS		392.6 380.0

PAVED SHOULDER REMOVAL SCHEDULE		
LOCATION	SIDE	PAVED SHOULDER REMOVAL (SQ YD)
IL RTE 159		
102+00.00 TO 108+00.00	LT	385
	RT	533
108+00.00 TO 109+75.00	LT	39
	RT	153
109+75.00 TO 113+50.00	LT	94
	RT	105
113+50.00 TO 119+00.00	LT	97
	RT	123
119+00.00 TO 124+50.00	LT	251
	RT	255
124+50.00 TO 127+50.00	LT	108
	RT	80
127+50.00 TO 133+00.00	LT	116
	RT	74
TOTAL		2413

PCC SIDEWALK 4", SPECIAL		
LOCATION	SIDE	SIDEWALK (SQ FT)
IL RTE 159		
154+60.55 TO 155+77.51	LT	208.1
154+67.45 TO 155+80.36	RT	218.1
TOTAL		426.2

GUARDRAIL REMOVAL SCHEDULE		
LOCATION	SIDE	GUARDRAIL REMOVAL (FT)
IL RTE 159		
104+78 TO 106+69	RT	187.5
106+29 TO 108+08	LT	175.0
129+28 TO 130+05	LT	75.0
130+51 TO 133+49	LT	312.5
133+56 TO 135+32	LT	175.1
139+92 TO 141+42	LT	150.4
142+45 TO 143+97	LT	150.0
142+82 TO 144+43	RT	162.5
TOTAL		1388

PAVEMENT REMOVAL SCHEDULE		
LOCATION	PAVEMENT REMOVAL (SQ YD)	
IL RTE 159		
102+00.00 TO 108+00.00	736	
108+00.00 TO 109+75.00	228	
CHEROKEE DR		
	212	
109+75.00 TO 113+50.00	187	
113+50.00 TO 119+00.00	649	
119+00.00 TO 124+50.00	738	
124+50.00 TO 127+50.00	172	
127+50.00 TO 133+00.00	1119	
138+50.00 TO 144+00.00	5	
144+00.00 TO 149+50.00	558	
149+50.00 TO 155+00.00	122	
155+00.00 TO 156+02.00	39	
IDLEWOOD DR		
	470	
S CLINTON ST		
	1797	
MCKINLEY AVE		
	424	
RAILROAD AVE		
	114	
S LOOP ST		
	908	
S CHESTNUT ST		
	704	
ANGLE AVE		
	273	
N LOOP ST		
	591	
HILL ST		
	219	
ALLEY @ 149+27		
	390	
JIM'S ALLEY		
	359	
ALLEY @ 152+03		
	130	
CHURCH ST		
	1578	
ALLEY @ 156+02.00		
	199	
TOTAL		12921

SIDEWALK REMOVAL SCHEDULE		
LOCATION	SIDE	SIDEWALK REMOVAL (SQ FT)
IL RTE 159		
135+66.84 TO 135+79.64	LT	77.0
136+15.00 TO 136+23.11	LT	65.9
136+61.06 TO 136+67.57	LT	107.3
138+15.24 TO 138+24.63	LT	133.5
138+98.32 TO 139+09.73	LT	53.0
141+18.63 TO 141+28.26	LT	41.6
144+53.99 TO 147+66.76	LT	1467.2
145+07.98 TO 145+27.71	RT	79.4
146+29.45 TO 147+16.80	RT	661.7
147+51.91 TO 149+12.58	RT	670.4
147+92.48 TO 148+28.18	LT	181.7
148+42.09 TO 149+14.34	LT	318.0
149+48.40 TO 150+77.30	LT	561.8
149+49.04 TO 151+87.29	RT	1442.7
150+90.38 TO 151+89.15	LT	696.2
152+20.66 TO 153+81.12	RT	1707.7
152+21.77 TO 152+77.84	LT	272.5
153+01.17 TO 153+82.25	LT	945.2
154+22.89 TO 155+89.71	RT	2670.8
154+29.57 TO 155+44.25	LT	1162.9
155+64.67 TO 155+88.76	LT	122.8
TOTAL		13439.3

CURB & GUTTER REMOVAL SCHEDULE					
LOCATION	SIDE	GUTTER REMOVAL (FT)	CC&G REMOVAL (FT)	PAVED DITCH REMOVAL (FT)	NOTES
IL RTE 159					
102+00.00 TO 109+56.20	RT		766		
106+02.02 TO 109+75.00	RT			373	CONCRETE PAVED DITCH OFFSET 60' RT
109+75.00 TO 109+87.13	RT			12	CONCRETE PAVED DITCH OFFSET 60' RT
122+31.84 TO 125+18.47	LT	311			
122+46.77 TO 124+95.40	RT	249			
129+50.69 TO 129+73.50	LT			25	
129+73.50 TO 132+55.75	LT	286			
131+06.49 TO 144+76.71	RT	1382			
132+28.23 TO 132+55.24	LT			28	
132+55.75 TO 144+63.21	LT	1204			
144+62.42 TO 145+30.87	LT		67		
144+77.16 TO 147+18.16	RT		247		
145+54.41 TO 145+82.90	LT		28		
145+94.35 TO 146+17.85	LT		24		
146+33.07 TO 146+59.84	LT		26		
146+73.57 TO 147+64.37	LT		91		
147+49.48 TO 149+13.20	RT		171		
147+94.07 TO 148+21.60	LT		28		
148+44.30 TO 149+17.98	LT		80		
149+45.50 TO 150+72.28	LT		133		
149+46.69 TO 151+88.10	RT		250		
150+97.58 TO 151+84.89	LT		88		
152+19.37 TO 153+73.16	RT		159		
152+24.62 TO 152+74.14	LT		51		
153+07.78 TO 153+77.21	LT		71		
154+28.72 TO 155+89.50	RT		177		
154+29.31 TO 155+41.01	LT		117		
155+69.44 TO 155+89.32	LT		24		
CHEROKEE DR					
0+45.88 TO 0+53.74	RT			15	
0+48.39 TO 0+73.86	LT	26			
0+53.74 TO 0+74.04	RT	20			
IDLEWOOD DR					
0+32.55 TO 0+57.80	LT			34	
0+32.74 TO 0+58.24	RT			33	
0+61.36 TO 1+20.05	LT	63			
0+61.51 TO 1+20.01	RT	62			
S CLINTON ST					
7+26.15 TO 8+38.93	RT	111			
7+26.15 TO 9+69.43	LT	242			
CHURCH ST					
28+55.00 TO 29+73.31	RT		120		
28+60.68 TO 29+06.07	LT		45		
29+39.44 TO 29+66.80	LT		28		
30+25.55 TO 32+35.00	LT		211		
30+28.72 TO 32+21.43	RT		195		
TOTALS		3956	3197	520	

TEMPORARY STRIPING SCHEDULE					
LOCATION	TEMPORARY PAVEMENT MARKING (FT)				LETTERS & SYMBOLS (SQ FT)
	4" LINE		12" LINE		
	SOLID WHITE	DOUBLE SOLID YELLOW	YELLOW SKIP DASH	SOLID YELLOW	
IL RTE 159					
PRIOR TO STA. 100+00.00	965				
100+00.00 TO 109+75.00	4830	10070	260		78
109+75.00 TO 115+00.00	2625	3150	403		
115+00.00 TO 130+00.00	7085	9018	1125		
130+00.00 TO 145+00.00	7130	9006	1125		
145+00.00 TO 160+00.00	4867	4142	858	358	47
STAGE 4*					
102+00.00 TO 109+75.00	272	813		140	109
109+75.00 TO 156+02.00	1520	5298		286	656
TOTAL		74562		784	890