STRUCTURE SCHEDULE

LOCATION	STRUCTURE	SURFACE (ELEV)	INVERT (ELEV)	DEPTH (FT)	TYPE A MANHOLE (EA)			PRECAST REINFORCED CONCRETE FLAT SLAB TOP (EA)	TYPE A INLET (EA)	TYPE B INLET (EA)	INLET SPECIAL TYPE E (EA)				FRAME AND GRATE (EA)					PRECAST REINFORCED CONCRETE FLARED END SECTIONS, P.R.C. FES (EA)				BOX CULVERT END SECTIONS (EA)	
					48"	60"	72"				48"	60"	72"	DOUBLE	TYPE 1 OPEN	TYPE 1 CLOSED	TYPE 3	TYPE 4	TYPE 9	12"	24" W/GRATE	36" W/GRATE	48" W/GRATE	4'X2'	5'X5' DOUBLE
IL RTE 159																									
103+43.51, 31.7' R	INLET 1-3R	466.29	462.51	3.78					1								1								
103+61.35, 43.3' L	INLET 1-4L	465.99	462.49	3.50					1								1								
104+42.41, 34.1' L	MH 1-5L	465.95	462.08	3.87	1			1								1									
104+42.61, 41.4' L	INLET 1-5L	465.72	462.15	3.57					1								1								
104+74.81, 29.6' R	INLET 1-4R	465.83	461.92	3.91					1								1								
104+74.80, 22.2' R	MH 1-4R	466.06	461.85	4.21	1			1								1									
105+37.04, 22.1' R	MH 1-5R	465.83	461.54	4.29	1			1								1									
105+49.29, 45.1' R	FES 1-5R	465.00	461.02	3.98																1					
105+55.35, 54.1' R	FES 1-2R	462.98	457.98	5.00																	1				
105+41.31, 30.1' L	MH 1-6L	465.65	461.58	4.07	1			1								1									
105+41.88, 37.4' L	INLET 1-6L	465.42	461.65	3.77					1								1								
105+73.44, 29.3' R	INLET 1-5R	465.46	461.91	3.55					1								1								
105+98.29, 54.1'R	MH 1-2R	463.10	458.11	4.99			1									1									
106+33.91, 33.1' R	MH 1-1R	464.74	458.23	6.51			1									1									
106+58.15, 23.7' L	MH 1-7L	465.33	461.00	4.33	1											1									
106+58.60, 31.0' L	INLET 1-7L	465.10	461.06	4.04					1								1								
106+92.22, 41.9' L	FES 1-7L	463.84	460.84	3.00																1					
107+41.78, 33.1' R	INLET 1-6R	465.38	458.55	6.83									1												
107+90.21, 29.3' L	INLET 1-8L	464.82	460.82	4.00					1								1								
107+90.18, 34.1' L	HW 1-8L	465.00	460.72	4.28																					
108+06.07, 46.1' L	FES 1-9L	464.15	461.15	3.00																1					
108+09.56, 37.0' L	INLET 1-9L	465.25	461.25	4.00							1														
108+11.07, 57.8' L	DOUBLE BOX DS	463.50	457.98	5.52																					1
108+12.52, 67.2' L	FES 1-10L	464.50	461.52	2.98																1					
108+29.85, 72.5' L	INLET 1-10L	465.00	461.70	3.30						1							1								
108+60.17, 72.5' L	INLET 1-11L	465.00	462.00	3.00					1								1								
108+72.40, 39.5' L	INLET 1-12L	464.76	461.76	3.00					1								1								
108+81.94, 57.4' L	DOUBLE BOX US	463.70	458.19	5.51																					1
108+86.94, 46.1' L	FES 1-12L	464.60	461.60	3.00																1					
108+83.11, 33.1' R	INLET 1-7R	464.84	458.97	5.87									1												
109+50.03, 29.3' L	INLET 1-13L	464.16	461.16	3.00					1								1								
109+50.00, 50.1' L	FES 1-13L	463.95	460.95	3.00																1					
109+49.97, 33.1' R	INLET 1-8R	464.72	459.17	5.55									1												
110+02.75, 29.3' L	INLET 1-14L	464.26	461.26	3.00					1								1								
110+02.73, 50.2' L	FES 1-14L	464.05	461.05	3.00																1					
110+05.22, 33.1' R	INLET 1-9R	464.83	459.34	5.49									1												
110+19.62, 56.3' L	OUTLET 1-14L	462.93	458.93	4.00																				1	
110+43.89, 22.0' L	MH 1-14L	464.66	459.06	5.60			1	1								1									
110+45.56, 31.1' R	MH 1-11R	464.96	459.47 460.47	5.49			1									1									
110+51.19, 41.9' R	INLET 1-11R	463.80	460.80	3.00					1								1								
110+77.98, 22.0' L	MH 1-15L	464.81	459.16 460.16	5.65			1	1								1									
110+78.01, 41.1' L	INLET 1-15L	464.81	460.81	4.00					1						1										
112+00.00, 22.0' L	MH 1-16L	464.98	459.53	5.45			1	1								1									
112+00.02, 41.1' L	INLET 1-16L	463.96	459.96	4.00					1						1										
112+10.56, 71.9' R	INLET 1-12R	463.40	460.40	3.00					1						1										
112+10.58, 31.1' R	MH 1-12R	465.24	459.96	5.28			1									1									
112+74.71, 22.0' L	MH 1-17L	464.70	459.75 460.50	4.95			1	1								1									
112+74.74, 41.3' L	INLET 1-17L	464.67	460.67	4.00					1									1							
113+00.06, 36.1' R	INLET 1-16R	464.11	460.35	3.76							1														
113+00.09, 30.1' R	MH 1-16R	464.90	460.23	4.67			1									1									
113+31.05, 32.6' R	INLET 1-13R	464.87	460.32	4.55								1													
113+35.00, 22.0' L	MH 1-20L	464.54	459.93	4.61			1	1								1									
113+35.03, 29.3' L	INLET 1-20L	464.40	460.00	4.40						1							1								
113+50.00, 32.6' R	INLET 1-14R	464.86	460.38	4.48								1													
113+50.03, 29.3' L	INLET 1-21L	464.30	460.30	4.00						1							1								
113+50.03, 40.1' L	INLET 1-18L	464.02	461.08	2.94					1						1										
114+17.56, 22.0' L	MH 1-22L	464.68	460.18	4.50			1	1								1									
114.17.56, 29.3' L	INLET 1-22L	464.45	460.45	4.00						1							1								
114+29.00, 32.6' R	INLET 1-15R	465.05	460.62	4.43								1													
114+12.47, 46.1' L	INLET 1-19L	465.20	461.20	4.00					1						1										
114+50.02, 31.1' R	MH 1-17R	465.10	460.68	4.42	1											1									
114+50.06, 37.3' R	INLET 1-17R	464.11	460.82	3.29							1														
115+00.02, 31.1' R	MH 1-18R	465.31	460.83	4.48	1											1									
115+00.06, 38.0' R	INLET 1-18R	464.11	460.97	3.14							1														
115+13.72, 22.0' L	MH 1-23L	465.07	460.47	4.60			1	1								1									
116+58.00, 52.8' L	INLET 1-28L	466.14	461.64	4.50					1									1							
116+77.14, 11.0' L	MH 1-29L	465.14	460.96	4.18			1	1								1									
116+77.17, 29.3' L	INLET 1-29L	464.69	461.14	3.55						1							1								
116+88.53, 32.2' R	INLET 1-19R	465.20	461.40	3.80							1														
117+39.14, 43.4' L	INLET 1-36L	464.35	461.35	3.00					1						1										
117+39.17, 29.3' L	INLET 1-30L	464.61	461.26	3.35						1							1								
117+39.14, 11.0' L	MH 1-30L	465.06	461.15	3.91	1			1								1									
117+40.02, 32.2' R	INLET 1-20R	465.15	461.56	3.59							1														
117+64.09, 29.3' L	INLET 1-31L	464.65	461.51	3.14					1								1								
117+73.31, 32.2' R	INLET 1-21R	465.22	461.66	3.56							1														
118+38.16, 11.0' L	MH 1-32L	465.43	461.45	3.98	1			1								1									
118+38.18, 29.3' L	INLET 1-32L	464.89	461.63	3.26					1								1								
118+39.31, 32.2' R	INLET 1-22R	465.53	461.86	3.67							1														
119+14.79, 32.2' R	INLET 1-23R	465.95	462.09	3.86							1														
119+48.30, 11.0' L	MH 1-33L	466.07	461.78	4.29	1			1								1									
119+48.33, 29.3' L	INLET 1-33L	465.71	461.96	3.75					1								1								
SUBTOTAL (1)					10	0	13	15	24	6	9	3	4		6	23	22	2	0	7	1	0	0	1	2

Rev.

FILE NAME = P:\Projects\513501\CADD\DGN\D876830-sht-schedule.dgn	USER NAME = default	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/16/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: NTS | SHEET NO. 9 OF 16 SHEETS | STA. N/A | TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	34
		CONTRACT NO. 76830		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		