

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		LOCATION 1 SFTY-2A	LOCATION 2 SFTY-2A	CODE NO	ITEM	UNIT		LOCATION 1 SFTY-2A	LOCATION 2 SFTY-2A
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	24	24							
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6		6						
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8						
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	6	4						
*78200500	BARRIER WALL MARKERS	EACH	14	4	10						
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	2	2						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2510	1662	848						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14		14						
X0320887	POLYMER CONCRETE	CU FT	4	4							
X0321468	PLUG EXISTING DECK DRAINS	EACH	118	4	114						
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	29.8		29.8						
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	913.1	721	192.1						
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	1096	1096							
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	1096	1096							
Z0010400	CLEANING BRIDGE SEATS	SQ FT	748	236	512						
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	49.3	49.3							
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2						
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2						
Z0053750	RETROFIT CONCRETE PARAPET	FOOT	1106		1106						
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	93.6	93.6							
78200300	PRISMATIC CURB REFLECTOR	EACH	82	82							

* SPECIALTY ITEM

FILE NAME =	USER NAME = manntm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwork\FWIDOT\MANNM\dms52478\p1n16207b.dgn		DRAWN -	REVISED -		327	14-12BR-1	CLINTON	72	4			
PLOT SCALE = 50.0000 / / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 76B27				
PLOT DATE = 12/10/2009		DATE -	REVISED -		FED. ROAD DIST. NO. 8 ILLINOIS FED. AID. PROJECT							