

GUARDRAIL SCHEDULE LOCATION 1

STATIONING	LT/RT	SPBGR TY A (FEET)	TBT-TY1 SPECIAL (EACH)	TBT-TY6 (EACH)	GUARDRAIL MRKR-TYA (EACH)	TERMINAL MRKR. DIRECT APPLIED (EACH)	GUARDRAIL REMOVAL (FEET)
468+01.00 TO 469+00.00	RT	50.0		1	1		99.5
469+00.00 TO 471+13.00	RT	175.0	1		2	1	213.5
473+56.00 TO 475+00.00	LT	100.25		1	1		145.0
475+00.00 TO 476+68.00	LT	124.75	1		2	1	168.0
TOTAL		450.0	2	2	6	2	626.0

BARRIER WALL MRK. SCHEDULE LOC 1

STATIONING	LT/RT	EACH
471+12.25 TO 473+55.75	RT	2
471+12.25 TO 473+55.75	LT	2
TOTAL		4

PAVEMENT MARKING SCHEDULE LOCATION 1

STATIONING	POLYUREA PAVEMENT MARKING LINE-4" (FOOT)				POLYUREA PAVT. MRK. LINE-24" (FOOT)	POLYUREA PAVEMENT MARKING TY 1 LETTERS & SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING LINE-4" (FOOT)				TEMPORARY PAVT. MRK. LINE-24" (FOOT)	TEMPORARY PAVT. MARKING LETTERS & SYMBOLS (SQ FT)	SHORT TERM PAVEMENT MARKING (FT)	PAVEMENT MARKING REMOVAL (SQ FT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PRISMATIC CURB REFLECTORS (EACH)	
	SOLID WHITE		SOLID YELLOW		SOLID WHITE		SOLID WHITE		SOLID YELLOW		SOLID WHITE						
	LT	RT	LT	RT			LT	RT	LT	RT							
466+17.50 TO 469+00.00	475	283	250	250	12	46.8	475	283	250	250	12	46.8	28.2	307.9	9.4	22	
469+00.00 TO 475+00.00	600	600	603.5	603.5			600	600	603.5	603.5			60.0	802.2	20.0	33	
475+00.00 TO 478+18.00	318	536	318	318	12	46.8	318	536	318	318	12	46.8	31.8	551.9	10.6	27	
TOTALS	5155				24	93.6	5155				24	93.6	120.0	1662.0	40.0	82	

PAVING SCHEDULE - LOCATION 1

STATION	TO	STATION	MEDIAN REMOVAL (FOOT)	CONC. MED. SURFACE REMOVAL (SQ FT)	PAVED SHOULDER REMOVAL (SQ YD)	EARTH EXCAVATION (CU YD)	HMA BASE CSE-10 1/2" (SQ YD)	PCC BASE CSE-8 1/2" (SQ YD)	CONC. MEDIAN TYPE SM (DOWELLED) (SQ FT)	HMA SURFACE CSE., MIX "D" N70 (TON)	PCC SURFACE REMOVAL BUTT JOINT (SQ YD)
466+50.00	TO	468+45.00	194.8		484.8	26	484.8	121.3	872.7		
468+45.00	TO	471+12.80		3045.8	595.4	33	595.4	338.5	823.0	24.0	214.0
473+55.50	TO	476+00.00		2930.2	543.8	22	543.8	325.7	2685.5	24.0	214.0
476+00.00	TO	478+18.20	218.2		486.0	39	486.0	121.5	874.8		
TOTALS			413.0	5976.0	2110.0	120	2110.0	907.0	5256.0	48.0	428.0

PAVEMENT PATCHING - LOCATION 1 (ENTRANCE AT STA. 484+20)

LT/RT	CLASS A PATCHING TYPE II - 6" (SQ YD)	PATCHING REINFORCEMENT (SQ YD)	SAW CUTS (FOOT)	
			FULL DEPTH	PART. DEPTH
LT	11	11	58.0	13
RT	11	11	51.5	13
TOTAL	22	22	135.5	

PAVEMENT MARKING SCHEDULE LOCATION 2

STATIONING	THERMOPLASTIC PAVEMENT MARKING LINE-4" (FOOT)		POLYUREA PAVEMENT MARKING LINE-4" (FOOT)		TEMPORARY PAVEMENT MARKING LINE-4" (FOOT)		SHORT TERM PAVEMENT MARKING (FT)	PAVEMENT MARKING REMOVAL (SQ FT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	RAISED REFLECTIVE PAVEMENT MKRS. (BRIDGE) (EACH)	RAISED REFLECTIVE PAVT. MRKR. REMOVAL (EACH)		
	SOLID WHITE		SKIP-DASH YELLOW		SOLID WHITE								SKIP-DASH YELLOW	
	LT	RT	LT	RT	LT	RT							LT	RT
2763+91.50 TO 2766+57.50	532	66.5			532	66.5	27	199.7	9	3		3		
2766+57.50 TO 2772+91.75			1268.5	158.5	1268.5	158.5	64	475.7	21.3		8	8		
2772+91.75 TO 2775+21.75	460	57.5			460	57.5	23	172.6	7.7	3		3		
TOTALS	1116		1427		2543		114	848.0	38	6	8	14		

GUARDRAIL SCHEDULE LOCATION 2

STATIONING	LT/RT	SPBGR TY A (FEET)	TBT-TY1 SPECIAL (EACH)	TBT-TY6 (EACH)	GUARDRAIL MRKR-TYA (EACH)	TERMINAL MRKR. DIRECT APPLIED (EACH)	GUARDRAIL REMOVAL (FEET)
2763+34.75 TO 2766+66.00	RT	237.5	1	1	1	1	313
2764+74.75 TO 2766+66.00	LT	137.5	1	1	1	1	213
2772+75.50 TO 2774+94.25	RT	125	1	1	1	1	215
2772+66.66 TO 2775+69.25	LT	200	1	1	1	1	291
TOTAL		700.0	4	4	4	4	1032

BARRIER WALL MRK. SCHEDULE LOC 2

STATIONING	LT/RT	EACH
2766+79.00 TO 2772+65.00	RT	5
2766+79.00 TO 2772+65.00	LT	5
TOTAL		10

PAVING SCHEDULE - LOCATION 2

STATIONING	LT/RT	HMA BASE CSE-10 1/2" (SQ YD)	PAVED SHOULDER REMOVAL (SQ FT)	AGGREGATE SHOULDER TYPE B (TON)
2764+90.50 TO 2766+57.50	LT	171.5	148.4	6.5
2764+90.50 TO 2766+57.50	RT	148.5	148.4	13.0
2772+91.75 TO 2774+49.50	LT	162.5	140.1	6.2
2772+91.75 TO 2774+49.50	RT	140.5	140.1	12.3
TOTAL		623.0	577.0	40.0