

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN SFY-2A TOTAL QUANTITIES	I-270				IL 3		
				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		LOCATION 1 X571-MAIN 100% STATE SN 060-0042/3	LOCATION 2 X271-MAIN 100% STATE SN 060-0044/5	LOCATION 3 X271-MAIN 100% STATE SN 060-0046/7	LOCATION 4 X371-MAIN 100% STATE SN 060-0051/2	LOCATION 5 X081-MAIN 100% STATE SN 060-0320	LOCATION 6 X181-MAIN 100% STATE SN 060-0202	LOCATION 7 X171-MAIN 100% STATE SN 060-0063
50300300	PROTECTIVE COAT	SQ YD	33746	11549	4846	3182	2864	1699	6991	2615
58700300	CONCRETE SEALER	SQ FT	8793	3631	1431	1488	632	931	680	
59200101	BRIDGE WASHING NO. 1	EACH	1	1						
59200102	BRIDGE WASHING NO. 2	EACH	1	1						
59200103	BRIDGE WASHING NO. 3	EACH	1		1					
59200104	BRIDGE WASHING NO. 4	EACH	1		1					
59200105	BRIDGE WASHING NO. 5	EACH	1			1				
59200106	BRIDGE WASHING NO. 6	EACH	1			1				
59200107	BRIDGE WASHING NO. 7	EACH	1				1			
59200108	BRIDGE WASHING NO. 8	EACH	1				1			
59200109	BRIDGE WASHING NO. 9	EACH	1					1		
59200110	BRIDGE WASHING NO. 10	EACH	1						1	
59200111	BRIDGE WASHING NO. 11	EACH	1							1
67100100	MOBILIZATION	L SUM	1	0.14	0.14	0.14	0.14	0.14	0.15	0.15
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	2						1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3	1		1		1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.2	0.2	0.2	0.2	0.2		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.25			0.25		0.25	0.25
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	0.4	0.3	0.3	0.2	0.6	0.2

GENERAL NOTES:

1. FLAGMEN SHALL BE PRESENT DURING ALL CLOSURE HOURS INCLUDING LUNCH HOUR AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
2. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE IN COLOR AND SKID MOUNTED. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
3. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
4. THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL TAKE APPROPRIATE PRECAUTIONS TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.
5. ANY TRAFFIC CONTROL NOT USED SHALL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
6. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO COMMENCING OF WORK AND ORDERING OF MATERIALS.
7. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE NO AREAS OUTSIDE OF THE JOB LIMITS ARE DISTURBED. ANY AREAS DISTURBED DUE TO CONSTRUCTION ACTIVITIES SHALL BE SEEDED AT THE CONTRACTOR'S EXPENSE AND NO OTHER COMPENSATION WILL BE PERMITTED.
8. PROTECTIVE COAT SHALL ONLY BE APPLIED TO CONCRETE SURFACES.
9. CONCRETE SEALER SHALL BE APPLIED TO BEARING SEATS UNDER JOINTS.

COMMITMENTS

NONE

LIST OF STANDARDS

000001-05 701400-04 701406-05 701421-02
 701901-01 780001-02 701411-06

FILE NAME =	USER NAME = manntm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SOQ, GEN. NOTES, STDS.	DRAWN -	REVISED -	SCALE:	SHEET NO. OF SHEETS STA. TO STA.	F.A.I./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwidot\manntm\dms52470\p1n1207a.dgn		CHECKED -	REVISED -			270/2	D-8 BRIDGE CLEANING 2010-1	MADISON	12	2					
		DATE -	REVISED -			CONTRACT NO. 76045									
						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT									