

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1-000 100% STATE	-----	-----	CODE NO	ITEM	UNIT		1-000 100% STATE	-----	-----
20200100	EARTH EXCAVATION	CU YD	205	205			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
20400800	FURNISHED EXCAVATION	CU YD	30	30			70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1			70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3.6	3.6			70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3.6	3.6			70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3.6	3.6			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1222	1222		
28100105	STONE RIPRAP, CLASS A3	SQ YD	25	25			70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	419	419		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	40629	40629		
40600300	AGGREGATE (PRIME COAT)	TON	66	66			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1032	1032		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1831	1831			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	65	65		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	427	427			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	408	408		
40600990	TEMPORARY RAMP	SQ YD	375	375			78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	419	419		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3662	3662			78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40629	40629		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1032	1032		
40800030	AGGREGATE (PRIME COAT)	TON	1	1		*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	65	65		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	55	55		*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	265	265		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	43625	43625		*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	385	385		*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	36	36		*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	265	265		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	402	402		*	80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	313	313		*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	820	820		
50105220	PIPE CULVERT REMOVAL	FOOT	274	274		*	Z0010555	DITCH CLEANING	FOOT	397	397		
54248510	CONCRETE COLLAR	CU YD	8.4	8.4									
542C1063	PIPE CULVERTS, CLASS C, TYPE 2 18"	FOOT	45	45									
542C1069	PIPE CULVERTS, CLASS C, TYPE 2 24"	FOOT	262	262		*							
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	437.5	437.5									
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			805	10185	MARION	62	3
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			CONTRACT NO. 16D46				
PLOT DATE = #DATE#		DATE -	REVISED -			SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____			FED. ROAD DIST. NO. _____ (ILLINOIS) FED. AID PROJECT	