

F.A. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358 B6-00075-01-AS	WOODFORD	66	9
STA. _____ TO STA. _____		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	

TEMPORARY DITCH CHECK SCHEDULE (1 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
RIGHT SIDE				
STA. 12+00.00 RT TO STA. 17+00.00 RT	500.00	0.25	200.00	
STA. 12+00.00 RT				10
STA. 14+00.00 RT				10
STA. 16+00.00 RT				10
STA. 17+00.00 RT TO STA. 19+00.00 RT	200.00	0.66	200.00	
STA. 18+00.00 RT				10
STA. 19+00.00 RT TO STA. 21+00.00 RT	200.00	1.00	150.00	
STA. 19+50.00 RT				10
STA. 21+00.00 RT TO STA. 23+00.00 RT	200.00	1.50	50.00	
STA. 22+50.00 RT				10
STA. 23+00.00 RT TO STA. 26+00.00 RT	300.00	2.50	60.00	
STA. 23+00.00 RT				10
STA. 23+60.00 RT				10
STA. 24+20.00 RT				10
STA. 24+80.00 RT				10
STA. 25+40.00 RT				10
STA. 26+00.00 RT				10
STA. 26+00.00 RT TO STA. 30+00.00 RT	400.00	2.25	68.00	
STA. 26+55.00 RT				10
STA. 27+95.00 RT				10
STA. 28+65.00 RT				10
STA. 29+35.00 RT				10
STA. 30+00.00 RT TO STA. 35+00.00 RT	500.00	0.50	200.00	
STA. 31+00.00 RT				10
STA. 33+00.00 RT				10
STA. 35+00.00 RT TO STA. 36+25.00 RT	125	1.45	107.00	
STA. 36+05.00 RT				10
STA. 36+25.00 RT TO STA. 38+00.00 RT	175.00	2.32	65.00	
STA. 36+85.00 RT				10
STA. 37+50.00 RT				10
STA. 38+00.00 RT TO STA. 41+50.00 RT	350.00	2.21	68.00	
STA. 39+50.00 RT				10
STA. 40+20.00 RT				10
STA. 40+90.00 RT				10
STA. 41+50.00 RT TO STA. 43+50.00 RT	200.00	1.81	83.00	
STA. 41+60.00 RT				10
STA. 42+40.00 RT				10
STA. 43+20.00 RT				10
STA. 43+50.00 RT TO STA. 46+80.00 RT	330	0.62	200.00	
STA. 44+80.00 RT				10
STA. 46+80.00 RT TO STA. 48+61.00 RT	181	1.98	79.00	
STA. 47+60.00 RT				10
STA. 48+40.00 RT				10
STA. 48+61.00 RT TO STA. 49+75.00 RT	114	0.50	200.00	
STA. 49+75.00 RT TO STA. 51+00.00 RT	125	1.70	88.00	
STA. 49+90.00 RT				10
STA. 50+75.00 RT				10
STA. 51+00.00 RT TO STA. 53+00.00 RT	200	2.49	63.00	
STA. 51+20.00 RT				10
STA. 51+80.00 RT				10
STA. 52+40.00 RT				10
STA. 53+00.00 RT				10
STA. 53+00.00 RT TO STA. 56+00.00 RT	300	3.08	50	
STA. 53+50.00 RT				10
STA. 54+00.00 RT				10
STA. 54+50.00 RT				10
STA. 55+00.00 RT				10
STA. 55+50.00 RT				10
STA. 56+00.00 RT				10
STA. 56+00.00 RT TO STA. 60+00.00 RT	400	2.35	65	
STA. 56+55.00 RT				10
STA. 57+20.00 RT				10
STA. 57+85.00 RT				10
STA. 58+50.00 RT				10
STA. 59+15.00 RT				10
STA. 59+80.00 RT				10
SUBTOTAL 1				480

TEMPORARY DITCH CHECK SCHEDULE (2 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
RIGHT SIDE				
STA. 60+00.00 RT TO STA. 61+00.00 RT	100	1.10	136	
STA. 61+00.00 RT				10
STA. 63+75.00 RT TO STA. 67+25.00 RT	350	0.50	200	
STA. 65+00.00 RT				10
STA. 67+00.00 RT				10
STA. 67+25.00 RT TO STA. 70+00.00 RT	275	1.83	83	
STA. 67+75.00 RT				10
STA. 68+65.00 RT				10
STA. 69+55.00 RT				10
STA. 70+00.00 RT TO STA. 72+00.00 RT	200	2.11	71	
STA. 70+50.00 RT				10
STA. 71+25.00 RT				10
STA. 72+00.00 RT				10
STA. 72+00.00 RT TO STA. 77+50.00 RT	550	2.47	63	
STA. 72+60.00 RT				10
STA. 73+20.00 RT				10
STA. 73+80.00 RT				10
STA. 74+40.00 RT				10
STA. 75+00.00 RT				10
STA. 75+60.00 RT				10
STA. 76+20.00 RT				10
STA. 76+80.00 RT				10
STA. 77+40.00 RT				10
STA. 77+50.00 RT TO STA. 79+00.00 RT	150	2.80	54	
STA. 78+00.00 RT				10
STA. 78+50.00 RT				10
STA. 79+00.00 RT TO STA. 80+01.00 RT	101	0.50	200	
STA. 79+00.00 RT				10
STA. 80+01.00 RT TO STA. 82+15.00 RT	214	0.21	200	
STA. 81+00.00 RT				10
STA. 82+15.00 RT TO STA. 84+00.00 RT	185	1.00	150	
STA. 82+50.00 RT				10
STA. 84+00.00 RT TO STA. 86+17.00 RT	217.00	1.87	83	
STA. 84+80.00 RT				10
STA. 85+60.00 RT				10
STA. 86+17.00 RT TO STA. 87+00.00 RT	83.00	0.30	200	
STA. 86+70.00 RT				10
STA. 87+00.00 RT TO STA. 89+00.00 RT	200	3.13	48	
STA. 87+20.00 RT				10
STA. 87+70.00 RT				10
STA. 88+20.00 RT				10
STA. 89+00.00 RT TO STA. 90+00.00 RT	100	4.25	36	
STA. 89+15.00 RT				10
STA. 90+00.00 RT TO STA. 92+00.00 RT	200	2.75	56	
STA. 90+75.00 RT				10
STA. 91+30.00 RT				10
STA. 91+85.00 RT				10
STA. 92+00.00 RT TO STA. 93+00.00 RT	100	2.25	68	
STA. 92+50.00 RT				10
STA. 93+00.00 RT TO STA. 95+50.00 RT	250	0.80	200	
STA. 93+50.00 RT				10
STA. 97+75.00 RT TO STA. 99+00.00 RT	125	1.74	88	
STA. 98+00.00 RT				10
STA. 98+85.00 RT				10
STA. 99+00.00 RT TO STA. 100+00.00 RT	100	1.33	115	
STA. 100+00.00 RT				10
STA. 100+00.00 RT TO STA. 102+00.00 RT	200	0.95	200	
STA. 102+00.00 RT				10
STA. 104+00.00 RT TO STA. 107+00.00 RT	300	0.20	200	
STA. 106+00.00 RT				10
STA. 107+00.00 RT TO STA. 109+00.00 RT	200	0.80	200	
STA. 108+00.00 RT				10
STA. 109+00.00 RT TO STA. 111+25.00 RT	225	1.47	107	
STA. 109+50.00 RT				10
STA. 110+55.00 RT				10
SUBTOTAL 2				420

PLOT DATE = 10/26/09
 FILE NAME = BFILE1
 USER NAME = MUSENB

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: NOVEMBER 2009

DRAWN BY: AMPH & KLM
 CHECKED BY: JLH & RAH