

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	B6-00075-01-AS	WOODFORD	66	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

TEMPORARY DITCH CHECK SCHEDULE (3 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
RIGHT SIDE				
STA. 111+25.00 RT TO STA. 113+25.00 RT	200	1.75	88	
STA. 112+10.00 RT				10
STA. 113+00.00 RT				10
STA. 118+00.00 RT TO STA. 120+00.00 RT	200	1.20	125	
STA. 119+25.00 RT				10
STA. 120+00.00 RT TO STA. 121+50.00 RT	150	2.60	58	
STA. 120+25.00 RT				10
STA. 120+85.00 RT				10
STA. 121+45.00 RT				10
STA. 121+50.00 RT TO STA. 122+50.00 RT	100	0.53	200	
STA. 122+05.00 RT				10
STA. 122+50.00 RT TO STA. 124+00.00 RT	150	0.60	200	
STA. 123+75.00 RT				10
STA. 124+00.00 RT TO STA. 125+00.00 RT	100	1.63	94	
STA. 125+00.00 RT TO STA. 126+00.00 RT	100	1.20	125	
STA. 126+00.00 RT TO STA. 129+00.00 RT	300	1.75	88	
STA. 126+15.00 RT				10
STA. 127+00.00 RT				10
STA. 127+90.00 RT				10
STA. 128+80.00 RT				10
STA. 129+00.00 RT TO STA. 138+00.00 RT	900	0.30	200	
STA. 130+50.00 RT				10
STA. 132+50.00 RT				10
STA. 134+50.00 RT				10
STA. 136+50.00 RT				10
STA. 138+00.00 RT TO STA. 140+15.00 RT	215	0.64	200	
STA. 138+50.00 RT				10
STA. 140+15.00 RT TO STA. 145+50.00 RT	535	1.74	88	
STA. 140+90.00 RT				10
STA. 141+65.00 RT				10
STA. 142+40.00 RT				10
STA. 144+60.00 RT				10
STA. 145+50.00 RT TO STA. 148+00.00 RT	250	0.40	200	
STA. 145+50.00 RT				10
STA. 147+50.00 RT				10
STA. 148+00.00 RT TO STA. 149+00.00 RT	100	1.20	125	
STA. 149+00.00 RT				10
STA. 149+00.00 RT TO STA. 151+00.00 RT	200	0.45	200	
STA. 151+00.00 RT TO STA. 152+50.00 RT	150	1.40	107	
STA. 152+00.00 RT				10
STA. 152+50.00 RT TO STA. 154+50.00 RT	200	2.48	63	
STA. 152+90.00 RT				10
STA. 153+50.00 RT				10
STA. 154+10.00 RT				10
STA. 154+50.00 RT TO STA. 157+00.00 RT	250	0.30	200	
STA. 154+80.00 RT				10
STA. 156+80.00 RT				10
STA. 157+00.00 RT TO STA. 158+50.00 RT	150	1.55	100	
STA. 157+90.00 RT				10
STA. 158+50.00 RT TO STA. 163+70.00 RT	520	0.40	200	
STA. 159+30.00 RT				10
STA. 161+30.00 RT				10
STA. 163+30.00 RT				10
STA. 163+70.00 RT TO STA. 165+00.00 RT	130	0.31	200	
STA. 165+30.00 RT				10
STA. 165+00.00 RT TO STA. 167+00.00 RT	200	1.25	125	
STA. 166+50.00 RT				10
SUBTOTAL 3				360

TEMPORARY DITCH CHECK SCHEDULE (4 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
LEFT SIDE				
STA. 12+00.00 LT TO STA. 15+00.00 LT	300	0.51	200	
STA. 12+00.00 LT				10
STA. 14+00.00 LT				10
STA. 15+00.00 LT TO STA. 18+00.00 LT	300	0.38	200	
STA. 16+00.00 LT				10
STA. 18+00.00 LT				10
STA. 18+00.00 LT TO STA. 20+00.00 LT	200	0.87	200	
STA. 20+00.00 LT				10
STA. 22+00.00 LT TO STA. 25+00.00 LT	300	2.10	71	
STA. 22+60.00 LT				10
STA. 23+50.00 LT				10
STA. 24+25.00 LT				10
STA. 25+00.00 LT				10
STA. 25+00.00 LT TO STA. 27+00.00 LT	200	2.75	56	
STA. 25+50.00 LT				10
STA. 26+00.00 LT				10
STA. 26+50.00 LT				10
STA. 27+00.00 LT TO STA. 29+00.00 LT	200	1.75	88	
STA. 27+20.00 LT				10
STA. 28+00.00 LT				10
STA. 28+80.00 LT				10
STA. 29+00.00 LT TO STA. 32+50.00 LT	350	1.81	83	
STA. 29+60.00 LT				10
STA. 30+40.00 LT				10
STA. 31+20.00 LT				10
STA. 32+00.00 LT				10
STA. 32+50.00 LT TO STA. 35+50.00 LT	300	0.35	200	
STA. 33+50.00 LT				10
STA. 36+25.00 LT TO STA. 40+00.00 LT	375	1.59	100	
STA. 37+00.00 LT				10
STA. 38+00.00 LT				10
STA. 39+00.00 LT				10
STA. 40+00.00 LT TO STA. 44+00.00 LT	400	2.06	75	
STA. 40+00.00 LT				10
STA. 40+75.00 LT				10
STA. 41+50.00 LT				10
STA. 42+25.00 LT				10
STA. 43+00.00 LT				10
STA. 43+75.00 LT				10
STA. 44+00.00 LT TO STA. 47+00.00 LT	300	0.39	200	
STA. 45+00.00 LT				10
STA. 47+00.00 LT TO STA. 48+90.00 LT	190	1.20	125	
STA. 48+25.00 LT				10
STA. 48+90.00 LT TO STA. 49+50.00 LT	60	2.92	52	
STA. 49+50.00 LT				10
STA. 51+50.00 LT TO STA. 54+00.00 LT	250	2.32	65	
STA. 52+50.00 LT				10
STA. 53+10.00 LT				10
STA. 53+70.00 LT				10
STA. 54+00.00 LT TO STA. 59+00.00 LT	500	2.74	56	
STA. 54+25.00 LT				10
STA. 54+75.00 LT				10
STA. 55+25.00 LT				10
STA. 55+75.00 LT				10
STA. 56+25.00 LT				10
STA. 56+75.00 LT				10
STA. 57+25.00 LT				10
STA. 57+75.00 LT				10
STA. 58+25.00 LT				10
STA. 58+75.00 LT				10
STA. 59+00.00 LT TO STA. 61+00.00 LT	200	1.63	94	
STA. 59+50.00 LT				10
STA. 60+50.00 LT				10
SUBTOTAL 4				470

PLOT DATE = 11/10/09
 FILE NAME = WFL010
 PLOT SCALE = 1"=40'
 USER NAME = RUSBRK

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM DRAWN BY: AMPH & KLM

DATE: NOVEMBER 2009 CHECKED BY: J.L.H. & R.A.H.