

F.A. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358 86-00075-01-AS	WOODFORD	66	12
STA. _____ TO STA. _____		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	

AGGREGATE SURFACE COURSE, TYPE B							40200800
LOCATION		ALIGNMENT	FOR INFO ONLY			WEIGHT	
STATION	LT/RT		AREA		THICKNESS		VOLUME
			SQ.FT.	SQ.YD.	INCH	CU.YD.	TON
STA. 21+50.00	LT	COUNTY HIGHWAY #1	1205.36	133.93	6	22.32	45.76
STA. 21+50.00	RT	COUNTY HIGHWAY #1	1175.68	130.63	6	21.77	44.63
STA. 27+28.50	RT	COUNTY HIGHWAY #1	800.61	88.96	6	14.83	30.39
STA. 35+70.00	LT	COUNTY HIGHWAY #1	1244.87	138.32	6	23.05	47.26
STA. 38+50.00	RT	COUNTY HIGHWAY #1	1175.69	130.63	6	21.77	44.63
STA. 42+92.50	LT	COUNTY HIGHWAY #1	840.56	93.40	6	15.57	31.91
STA. 51+49.00	LT	COUNTY HIGHWAY #1	1245.58	138.40	6	23.07	47.29
STA. 62+00.00	LT	COUNTY HIGHWAY #1	840.68	93.41	6	15.57	31.91
STA. 89+42.00	LT	COUNTY HIGHWAY #1	1437.68	159.74	6	26.62	54.58
STA. 89+76.70	RT	COUNTY HIGHWAY #1	1216.46	135.16	6	22.53	46.18
STA. 95+50.00	LT	COUNTY HIGHWAY #1	1450.32	161.15	6	26.86	55.06
STA. 95+50.00	RT	COUNTY HIGHWAY #1	1258.49	139.83	6	23.31	47.78
STA. 102+00.00	LT	COUNTY HIGHWAY #1	1458.00	162.00	6	27.00	55.35
STA. 103+79.50	LT	COUNTY HIGHWAY #1	964.67	107.19	6	17.86	36.62
STA. 115+00.00	RT	COUNTY HIGHWAY #1	1175.69	130.63	6	21.77	44.63
STA. 117+57.00	RT	COUNTY HIGHWAY #1	1175.70	130.63	6	21.77	44.63
STA. 120+10.00	LT	COUNTY HIGHWAY #1	1455.85	161.76	6	26.96	55.27
STA. 122+95.00	LT	COUNTY HIGHWAY #1	1107.10	123.01	6	20.50	42.03
STA. 133+58.00	LT	COUNTY HIGHWAY #1	1335.39	148.38	6	24.73	50.70
STA. 143+00.00	LT	COUNTY HIGHWAY #1	1251.84	139.09	6	23.18	47.52
STA. 143+52.00	RT	COUNTY HIGHWAY #1	1800.75	200.08	6	33.35	68.36
STA. 1500+83.23	LT	TR 1500 N	763.91	84.88	6	14.15	29.00
STA. 1503+17.59	RT	TR 1500 N	776.64	86.29	6	14.38	29.48
STA. 1603+16.15	LT	TR 1600N	622.31	69.15	6	11.52	23.62
STA. 1603+16.15	RT	TR 1600N	717.68	79.74	6	13.29	27.25
TOTAL							1081.85

AGGREGATE FOR TEMPORARY ACCESS							40201000
LOCATION		ALIGNMENT	FOR INFO ONLY			WEIGHT	
STATION	RT/LT		AREA		THICKNESS		VOLUME
			SQ.FT.	SQ.YD.	INCH	CU.YD.	TON
STA. 10+00.00 TO STA. 26+88.00	RT	COUNTY HIGHWAY #1	20256.00	2250.67	2	125.04	256.33
STA. 26+88.00	RT	COUNTY HIGHWAY #1	200.00	22.22	6	3.70	7.59
STA. 27+28.50	RT	COUNTY HIGHWAY #1	436.00	48.44	6	8.07	16.55
STA. 42+92.00	RT	COUNTY HIGHWAY #1	200.00	22.22	6	3.70	7.59
STA. 42+92.50	LT	COUNTY HIGHWAY #1	360.00	40.00	6	6.67	13.67
STA. 42+92.50 TO STA. 63+00.00	LT	COUNTY HIGHWAY #1	24090.00	2676.67	2	148.70	304.84
STA. 103+79.50	LT	COUNTY HIGHWAY #1	195.00	21.67	6	3.61	7.40
STA. 103+79.50 TO STA. 116+00.00	LT	COUNTY HIGHWAY #1	14646.00	1627.33	2	90.41	185.34
TOTAL							799.31

COMBINATION CURB AND GUTTER REMOVAL		44000500
LOCATION		LENGTH
STATION TO STATION		FEET
STA. 11+00.00, 13.3' RT TO STA. 11+30.70, 10.3' RT		30.70
STA. 11+00.00, 13.9' RT TO STA. 11+32.25, 12' RT		32.25
TOTAL		62.95

AGGREGATE BASE COURSE, TYPE B									35101400
LOCATION		ALIGNMENT	LENGTH FEET	WIDTH FEET	DEPTH FEET	AREA		VOLUME CU.YD.	WEIGHT TONS
STATION TO STATION						SQ. FT.	SQ YDS		
STA. 11+00.00 TO STA. 11+50.00	COUNTY HIGHWAY #1	50.00	VARIES	1.5 to 1	1327.00	147.44	61.44	125.94	
STA. 11+50.00 TO STA. 167+00.00	COUNTY HIGHWAY #1	15550.00	26	1	404300.00	44922.22	14974.07	30696.85	
STA. 1500+45.92 TO STA. 1500+95.92	TR 1500N	50.00	VARIES	1.5 to 1	1100.00	122.22	50.93	104.40	
STA. 1500+95.92 TO STA. 1501+87.00	TR 1500N	91.08	VARIES	1	3089.70	343.30	114.43	234.59	
STA. 1502+13.00 TO STA. 1502+79.55	TR 1500N	66.55	VARIES	1	3170.20	352.24	117.41	240.70	
STA. 1502+79.55 TO STA. 1503+29.55	TR 1500N	50.00	VARIES	1 to 1.5	1028.20	114.24	47.60	97.58	
STA. 1601+10.21 TO STA. 1601+60.21	TR 1600N	50.00	VARIES	1.5 to 1	1310.00	145.56	60.65	124.33	
STA. 1601+60.21 TO STA. 1601+87.00	TR 1600N	26.79	VARIES	1	1622.10	180.23	60.08	123.16	
STA. 1602+13.00 TO STA. 1603+03.25	TR 1600N	90.25	VARIES	1	3073.50	341.50	113.83	233.36	
STA. 1603+03.25 TO STA. 1603+53.25	TR 1600N	50.00	VARIES	1 to 1.5	1100.00	122.22	50.93	104.40	
ENTRANCES									
STA. 21+50.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 21+50.00 RT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 27+28.50 RT	COUNTY HIGHWAY #1			1	136.00	15.11	5.04	10.33	
STA. 35+70.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 38+50.00 RT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 42+92.50 LT	COUNTY HIGHWAY #1			1	136.00	15.11	5.04	10.33	
STA. 51+49.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 62+00.00 LT	COUNTY HIGHWAY #1			1	136.00	15.11	5.04	10.33	
STA. 89+42.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 89+76.70 RT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 95+50.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 95+50.00 RT	COUNTY HIGHWAY #1			1	178.00	19.78	6.59	13.52	
STA. 102+00.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 103+79.50 LT	COUNTY HIGHWAY #1			1	136.00	15.11	5.04	10.33	
STA. 115+00.00 RT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 117+57.00 RT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 120+10.00 LT	COUNTY HIGHWAY #1			1	164.00	18.22	6.07	12.45	
STA. 122+95.00 LT	COUNTY HIGHWAY #1			1	146.00	16.22	5.41	11.08	
STA. 133+58.00 LT	COUNTY HIGHWAY #1			1	164.00	18.22	6.07	12.45	
STA. 143+00.00 LT	COUNTY HIGHWAY #1			1	166.00	18.44	6.15	12.60	
STA. 143+52.00 RT	COUNTY HIGHWAY #1			1	216.00	24.00	8.00	16.40	
STA. 1500+83.23 LT	TR 1500N			1	225.50	25.06	8.35	17.12	
STA. 1503+17.59 RT	TR 1500N			1	216.50	24.06	8.02	16.44	
STA. 1603+16.15 LT	TR 1600N			1	222.50	24.72	8.24	16.89	
STA. 1603+16.15 RT	TR 1600N			1	222.50	24.72	8.24	16.89	
MAILBOX TURNOUTS									
STA. 26+39.66 RT	COUNTY HIGHWAY #1			1	120.00	13.33	4.44	9.11	
STA. 42.92.50 RT	COUNTY HIGHWAY #1			1	150.00	16.67	5.56	11.39	
TOTAL					425681.70	47297.90	15820.27	32431.56	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM DRAWN BY: AMPH & KLM
 DATE: NOVEMBER 2009 CHECKED BY: JLH & RAH

PLOT DATE = *DATE*
 FILE NAME = *FILE*
 PLOT SCALE = *SCALE*
 USER NAME = *USER*