

SUMMARY OF QUANTITIES				100% STATE STRUCTURES X771-2A
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
20200100	EARTH EXCAVATION	CU YD	2499	2499
20400800	FURNISHED EXCAVATION	CU YD	10,839	10,839
20700400	PORDUS GRANULAR EMBANKMENT, SPECIAL	CU YD	122	122
25000200	SEEDING, CLASS 2	ACRE	4.25	4.25
25000350	SEEDING, CLASS 7	ACRE	4.25	4.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	382.5	382.5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	382.5	382.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	382.5	382.5
25100115	MULCH, METHOD 2	ACRE	4.25	4.25
25100630	EROSION CONTROL BLANKET	SQ YD	18,661	18,661
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	425	425
28000305	TEMPORARY DITCH CHECKS	FOOT	372	372
28000400	PERIMETER EROSION BARRIER	FOOT	4130	4130
28000500	INLET AND PIPE PROTECTION	EACH	14	14
31000600	PROCESSING LIME STABILIZED SOIL MIXTURE 12"	SQ YD	3,808	3,808
31001500	LIME	TON	77	77
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	205	205
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	782	782
40600300	AGGREGATE (PRIME COAT)	TON	15.5	15.5
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	122	122
40600990	TEMPORARY RAMP	SQ YD	356	356
40603080	HOT - MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	1455	1455
40603245	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	596	596
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	440	440
40603575	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	220	220
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32	32
40800030	AGGREGATE (PRIME COAT)	TON	0.3	0.3
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14	14
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	100	100
44000100	PAVEMENT REMOVAL	SQ YD	327	327

* SPECIALTY ITEM

SUMMARY OF QUANTITIES				100% STATE STRUCTURES X771-2A
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3734	3734
44004300	PAVEMENT BREAKING	SQ YD	3176	3176
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,056	1,056
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	75	75
48203100	HOT-MIX ASPHALT SHOULDERS	TON	544	544
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50105220	PIPE CULVERT REMOVAL	FOOT	38	38
50157300	PROTECTIVE SHIELD	SQ YD	430	430
50200100	STRUCTURE EXCAVATION	CU YD	208	208
50300225	CONCRETE STRUCTURES	CU YD	111.9	111.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	342.4	342.4
50300260	BRIDGE DECK GROOVING	SQ YD	810	810
50300280	CONCRETE ENCASEMENT	CU YD	8.6	8.6
50300300	PROTECTIVE COAT	SQ YD	1127	1127
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	1872	1872
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	90,650	90,650
50800515	BAR SPLICERS	EACH	62	62
51100100	SLOPE WALL 4 INCH	SQ YD	424	424
51201600	FURNISHING STEEL PILES HP 12 X 53	FOOT	780	780
51202000	FURNISHING STEEL PILES HP 14 X 102	FOOT	574	574
51202305	DRIVING PILES	FOOT	1,354	1,354
51203600	TEST PILE STEEL HP 12 X 53	EACH	2	2
51204000	TEST PILE STEEL HP 14 X 102	EACH	1	1
51500100	NAME PLATES	EACH	1	1
52100520	ANCHOR BOLTS, 1"	EACH	36	36
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	43	43
54215553	METAL END SECTIONS 18"	EACH	2	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2	2
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	38	38

* SPECIALTY ITEM

FILE NAME =	USER NAME = dawnsorb	DESIGNED - MTM	REVISED -
ct:\p\work\PI\1001\DAWSORNB\0176650\05	0875-3-4-500.dgn	DRAWN - JJS	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - LLO	REVISED -
	PLOT DATE = 12/17/2009	DATE - JULY 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	F.A.I. RTE. 74	SECTION (10-6HB-5)BR	COUNTY CHAMPAIGN	TOTAL SHEETS 63	SHEET NO. 3
							CONTRACT NO. 90875	
ILLINOIS FED. AID PROJECT								