

PAVING SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT (SQ YD)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)	AGGREGATE SURFACE COURSE, TYPE B (TON)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	AGGREGATE (PRIME COAT) (TON)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (TON)	INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	TEMPORARY RAMP (SQ YD)	AGGREGATE SHOULDERS (SPECIAL) (SQ YD)
MAINLINE SPRESSER STREET												
STA. 1042+52 TO STA. 1042+57											15	
STA. 1042+52 TO STA. 1042+82	87											
STA. 1042+52 TO STA. 1100+00					1,329	33.2	1,653	1,402				3,832
STA. 1042+52 TO STA. 1100+96			55									
STA. 1100+00 TO STA. 1103+60					103	2.6	127	108				240
STA. 1100+96 TO STA. 1113+36			69									
STA. 1103+60 TO STA. 1116+40					433	10.8	536	456				853
STA. 1114+56 TO STA. 1118+96			26									
STA. 1116+40 TO STA. 1120+00					103	2.6	127	108				240
STA. 1118+96 TO STA. 1161+65			40									
STA. 1120+00 TO STA. 1135+00					347	8.7	431	366				1,000
STA. 1135+00 TO STA. 1161+65					616	15.4	767		650			1,777
STA. 1147+08 TO STA. 1147+78	202											
STA. 1147+73 TO STA. 1147+78											15	
STA. 1147+92 TO STA. 1147+97											15	
STA. 1147+92 TO STA. 1148+62	202											
STA. 1161+35 TO STA. 1161+65	87											
STA. 1161+60 TO STA. 1161+65											15	
MAINLINE TOTAL	578	0	190	0	2,931	73.3	3,641	2,440	650	0	60	7,942
SIDE ROADS												
STA. 1042+80 RT (SANGAMON ROAD)	81				10	0.2	1	11			14	
STA. 1059+48 RT (CLEARING AVE.)	71				18	0.4	7	19			31	
STA. 1074+30 RT (AIRLAWN STREET)		40			10	0.2	4	10			17	
STA. 1103+30 RT (LEE NORSE DRIVE)		114			21	0.5	10	22			43	
STA. 1113+85 LT (CH 16)	108				19	0.5	9	20			41	
STA. 1113+85 RT (VANDEVEER STREET)	110				19	0.5	9	20			40	
STA. 1135+86 LT (BRIARCLIFF ROAD)	66				16	0.4	7	17			25	
STA. 1145+55 RT (BAUGHMAN ROAD)	54				13	0.3	6	14			21	
STA. 1161+35 LT (WEST AVE.)	87				11	0.3	1	11			16	
SIDE ROAD TOTAL	577	154	0	0	137	3.3	54	144	0		248	
ENTRANCES												
STA. 1042+84 LT (FE)				15								
STA. 1043+97 RT (CE)	38				10					13		
STA. 1048+41 RT (CE)	46				12					16		
STA. 1052+13 LT (CE)		40			11					14		
STA. 1052+34 RT (CE)		64			20					27		
STA. 1053+54 LT (CE)	28				9					12		
STA. 1057+65 LT (CE + MB)		30			11					15		
STA. 1062+53 RT (FE)				15								
STA. 1062+97 LT (CE)					17					22		
STA. 1064+11 LT (CE + MB)					13					17		
STA. 1068+08 LT (CE + MB)	34				12					15		
STA. 1068+89 RT (CE)		29			10					13		
STA. 1070+17 RT (CE + MB)		38			20					26		
STA. 1073+04 RT (CE)		31			10					14		
STA. 1073+90 LT (CE)	33				10					14		
STA. 1081+90 LT (CE)	36				10					12		
STA. 1084+50 LT (CE + MB)	52				17					22		
STA. 1085+00 RT (CE + MB)		49			18					23		
STA. 1085+40 LT (CE)				15								
STA. 1089+53 LT (FE)				15								
STA. 1097+02 RT (CE + MB)		40			13					18		
STA. 1100+36 RT (CE + MB)		47			15					19		
STA. 1100+58 LT (PE + MB)					9					12		
STA. 1107+81 RT (CE)	67				13					17		
STA. 1115+16 RT (CE + MB)		32			9					12		
STA. 1116+20 RT (CE)		50			10					14		
STA. 1116+71 RT (CE)		61			13					16		
STA. 1117+73 RT (CE)		31			9					11		
STA. 1119+09 RT (CE)					13					17		
STA. 1120+97 RT (CE)					14					18		
STA. 1122+52 RT (CE + MB)	18	34			16					21		
STA. 1124+14 RT (CE)	46				13					17		
STA. 1124+84 RT (CE)					13					17		
STA. 1126+20 LT (FE)				15								
STA. 1126+13 RT (CE + MB)					16					21		
STA. 1127+45 RT (CE)					13					16		
STA. 1128+83 RT (CE + MB)	31				11					15		
STA. 1129+43 RT (CE)	30				10					12		



FILE NAME = J:\09002.07\CADD\CAD\sheet\09002027-shi-	USER NAME = frankv	DESIGNED - WCB	REVISED -
schedule.dgn		DRAWN - MOS	REVISED -
PLOT SCALE = 50.0000' / in.		CHECKED - WCB	REVISED -
PLOT DATE = 11/19/2009		DATE - 9/28/09	REVISED -

**CITY OF TAYLORVILLE
SPRESSER STREET IMPROVEMENTS**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7877	09-00060-00-RS	CHRISTIAN	14	6
CONTRACT NO. 090512				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ARA-M-50670171				