

SUMMARY OF QUANTITIES					
CODE #	PAY ITEM	UNITS	TOTAL	STATE FUNDS	CONSTRUCTION TYPE CODE
20200100	EARTH EXCAVATION	CU YD	1820		I000
20800150	TRENCH BACKFILL	CU YD	76		I000
25000200	SEEDING, CLASS 2	ACRE	0.7		I000
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63		I000
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63		I000
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63		I000
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.4		I000
25100105	MULCH, METHOD 1	ACRE	0.7		I000
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200		I000
28000400	PERIMETER EROSION BARRIER	FOOT	155		I000
28000500	INLET AND PIPE PROTECTION	EACH	7		I000
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	1650		I000
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1105		I000
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	54		I000
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	958		I000
*35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	1499		I000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	562	562	I000
40600990	TEMPORARY RAMP	SQ YD	52		I000
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	693	693	I000
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	SQ YD	5503	5503	I000
*44001900	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	1658		I000
44004250	PAVED SHOULDER REMOVAL	SQ YD	449		I000
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30		I000
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	908		I000
50104400	CONCRETE HEADWALL REMOVAL	EACH	2		I000
55080050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	22		I000
55080340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	80		I000
60218500	MANHOLES, TYPE A, 4' DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1		I000
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4		I000
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1		I000
*60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	904		I000
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	254		I000
*60604900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (VARIABLE WIDTH GUTTER FLAG)	FOOT	20		I000
*60609600	COMBINATION CONCRETE CURB AND GUTTER TYPE M-6.12 (SPECIAL)	FOOT	164		I000
60618300	CONCRETE MEDIAN SURFACE 4 INCH	SQ FT	1164		I000
67100100	MOBILIZATION	L SUM	1		I000
*70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1		I000
*70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		I000
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	170		I000
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	187..		I000
70300230	TEMPORARY PAVEMENT MARKING, LINE 5"	FOOT	5229		I000
70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	781		I000
70300260	TEMPORARY PAVEMENT MARKING, LINE 12"	FOOT	240		I000
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	118		I000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	57		I000
72000200	SIGN PANEL - TYPE 2	SQ FT	59.1		I000
△ 78000300	THERMOPLASTIC PAVEMENT MARKING, LINE 5"	FOOT	4599		I000
△ 78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	240		I000
△ 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS AND SYMBOLS	SQ FT	187..		I000
△ 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 5"	FOOT	630		I000
△ 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 6"	FOOT	721		I000
△ 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 24"	FOOT	118		I000
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	65		I000
△ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	41		I000
80500100	SERVICE INSTALLATION, TYPE A	EACH	1		Y031-IF
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	733		Y031-IF
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	198		Y031-IF
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	133		Y031-IF
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	10		Y031-IF
*81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	96		Y031-IF
*81306100	JUNCTION BOX (SPECIAL)	EACH	2		Y031-IF

SUMMARY OF QUANTITIES (CONT.)					
CODE #	PAY ITEM	UNITS	TOTAL	STATE FUNDS	CONSTRUCTION TYPE CODE
81400100	HANDHOLE	EACH	3		Y031-IF
81400300	DOUBLE HANDHOLE	EACH	1		Y031-IF
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1059		Y031-IF
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	3		Y031-IF
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		Y031-IF
*86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1		Y031-IF
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		Y031-IF
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	897		Y031-IF
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	547		Y031-IF
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	969		Y031-IF
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	950		Y031-IF
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	17		Y031-IF
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	3		Y031-IF
87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1		Y031-IF
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1		Y031-IF
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1		Y031-IF
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9		Y031-IF
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		Y031-IF
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	40		Y031-IF
87900200	DRILL EXISTING HANDHOLE	EACH	1		Y031-IF
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		Y031-IF
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6		Y031-IF
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		Y031-IF
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		Y031-IF
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		Y031-IF
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		Y031-IF
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	11		Y031-IF
*X0320872	VIDEO VEHICLE DETECTION SYSTEM	FOOT	1		Y031-IF
*X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	540		Y031-IF
*X0326473	ELECTRIC CABLE IN CONDUIT, NO. 14 3C FOR VIDEO	FOOT	610		Y031-IF
*X8170245	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 12	FOOT	610		Y031-IF

*SPECIAL PROVISION

NOTE: ALL CONSTRUCTION TYPE CODE Y031-IF AND ITEMS DESIGNATED BY A Δ, ARE CONSIDERED SPECIALTY ITEMS.

FILE NAME =	USER NAME = #USER#	DESIGNED - M.T.V.	REVISED - 01-15-10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - K.M.W.	REVISED -					INTERSECTION CONSTRUCTION (BL-55 & VILLAGE CTR DR), SHERMAN, IL				666	09-00015-00 PV	SANGAMON	25	5
	PLOT SCALE = #SCALE#	CHECKED - T.T.P.	REVISED -	SCALE:				SHEET NO. 5 OF 25 SHEETS		STA.	TO STA.		CONTRACT NO.			
	PLOT DATE = #DATE#	DATE - 11/20/09	REVISED -									[ILLINOIS] FED. AID PROJECT				