

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	171
* 40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2630
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1834
40600010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1566
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	617
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1

SCHEDULE OF QUANTITIES

EARTH EXCAVATION			
LOCATION	STATION (F.A.S. 662)		CU YD
WEST APPR. (SN 018-3191)	467+66.00 TO 468+21.00		9
EAST APPR. (SN 018-3191)	473+29.00 TO 473+84.00		9
WEST ABUT. (SN 018-3194)	476+59.50 TO 476+69.50		1
EAST ABUT. (SN 018-3194)	478+54.50 TO 478+64.50		1
IL 130 INTERSECTION	497+63.44 TO 499+86.27		151
PROJECT TOTAL			171

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70									
LOCATION	STATION (F.A.S. 662)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	DEPTH (IN)	LBS/SQ YD-IN	TONS		
ROADWAY	436+50.00 TO 468+21.00	3171.00	24.00	8456.0	3	112	1421		
ROADWAY	473+29.00 TO 476+69.50	340.50	24.00	908.0	3	112	153		
ROADWAY	478+54.50 TO 498+23.44	1968.94	24.00	5250.5	3	112	882		
IL 130 INTERSECTION	498+23.44 TO 499+86.27			1037.0	3	112	174		
PROJECT TOTAL								2630	

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70									
LOCATION	STATION (F.A.S. 662)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	DEPTH (IN)	LBS/SQ YD-IN	TONS		
ROADWAY	436+50.00 TO 468+21.00	3171.00	24.00	8456.0	2	112	947		
ROADWAY	473+29.00 TO 476+69.50	320.50	24.00	854.7	2	112	96		
ROADWAY	476+49.50 TO 476+69.50	20.00	24.00	53.3	2.5	112	7		
ROADWAY	478+54.50 TO 478+74.50	20.00	24.00	53.3	2.5	112	7		
ROADWAY	478+74.50 TO 498+23.44	1948.94	24.00	5197.2	2	112	582		
IL 130 INTERSECTION	498+23.44 TO 499+86.27			1037.0	2	112	116		
PROJECT TOTAL								1755	

BITUMINOUS MATERIALS (PRIME COAT)							
LOCATION	STATION (F.A.S. 662)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	GAL/SQ YD	GALLONS	
ROADWAY	436+50.00 TO 468+21.00	3171.00	24.00	8456.0	0.1	846	
ROADWAY	473+29.00 TO 476+69.50	340.50	24.00	908.0	0.1	91	
ROADWAY	478+54.50 TO 498+23.44	1968.94	24.00	5250.5	0.1	525	
IL 130 INTERSECTION	498+23.44 TO 499+86.27			1037.0	0.1	104	
PROJECT TOTAL							1566

* PAY ITEM REQUIRES SPECIAL PROVISION



LAYOUT: MNM/DJP 10/10/07
 DRAWN: D.P. 10/10/07
 REVIEWED: MNM 10/20/08

FILE NAME =	USER NAME = Pop00836	DESIGNED - MNM/DJP	REVISED -
I:\01\jobs\01e20210\CADD\Road\Sheet\C-601.dgn		DRAWN - D.P.	REVISED -
PLOT SCALE = 1/8000'' / in.		CHECKED - MNM	REVISED -
PLOT DATE = 12/23/2009		DATE - 10/22/09	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES / SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS

F.A.S. RTE. 662	SECTION 09-00061-01-RS	COUNTY CUMBERLAND	TOTAL SHEETS 14	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 95614	