

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
8623 8609	09-00096-00-RS	MARION	22	3
FEDERAL AID PROJECT			CONTRACT 97425	

### SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK, 4" SQ FT	PCC SIDEWALK, 6" SQ FT
WEST BROADWAY		
STA. 101+00 TO 101+50	366	
STA. 101+44 LT.	30	
STA. 105+90 TO 106+23	155	
STA. 106+58 TO 106+69	42	
STA. 111+13 TO 111+23	52	
STA. 111+59 TO 111+69	52	
STA. 116+36 TO 116+46	52	
STA. 116+82 TO 119+88	1,342	
STA. 120+41 TO 120+57	120	
AT WASHINGTON	64	
AT ALLEY	48	
BROOKSIDE AVENUE		
STA. 130+33 TO 132+75	1,208	
STA. 132+75 TO 133+00		125
STA. 133+00 TO 133+42	210	
STA. 133+42 TO 133+87		218
STA. 133+87 TO 134+20	167	
STA. 134+20 TO 134+76		280
STA. 134+76 TO 136+09	669	
STA. 136+09 TO 136+41		161
STA. 136+41 TO 137+56	582	
STA. 137+56 TO 137+94		186
STA. 137+94 TO 138+18	110	
STA. 138+75 TO 140+39	850	
STA. 140+86 TO 141+04	14	
STA. 141+40 TO 143+21	886	
STA. 143+71 TO 144+64	452	
TOTAL	7,471	970

### ADJUSTMENT SCHEDULE

STATION	CENTERLINE OFFSET	LANE		WATER VALVES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED
		LEFT (SB)	RIGHT (NB)		
				EACH	EACH
BROOKSIDE AVENUE-					
131+83	1' LT.	x			1
131+40	17' RT.		x	1	
133+48	6' RT.		x	1	
134+98	6' RT.		x		1
137+75	2' RT.		x		1
138+32	1' LT.	x			1
144+70	8' RT.		x		1
144+71	2' RT.		x		1
TOTAL				2	6

### PAVEMENT SCHEDULE

STATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	LEVELING BINDER (MACHINE METHOD), N70	INCIDENTAL HOT-MIX ASPHALT SURFACING	HOT-MIX ASPHALT SURFACE REMOVAL, 2"
	GALLON	TON	TON	TON	TON	SQ YD
WEST BROADWAY -- 88+02 TO 127+38.85	1,233	24	1,728	161	26	16,671
BROOKSIDE AVENUE-- 130+15.80 TO 144+69.95	479	9	460	193	47	
TOTAL	1,712	33	2,188	354	73	16,671

### PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS							SHORT-TERM			POLYUREA PAVEMENT MARKINGS	
	SOLID WHITE 4" LANE LINE	WHITE 4" SKIP DASH LANE LINE	SOLID DOUBLE YELLOW 4" LANE LINE	SOLID YELLOW 12" DIAGONAL LINE	SOLID WHITE 24" STOP BAR	SOLID WHITE 6" CROSSWALK LINE	SOLID WHITE TURN OR THRU ARROW	YELLOW PAVEMENT MARKING	WHITE PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	SOLID WHITE 24" STOP BAR	SOLID WHITE 6" CROSSWALK LINE
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	SQ. FT.	FOOT	FOOT
WEST BROADWAY												
STA. 88+02 TO 100+40*	2,382		2,477					248		41		
STA. 100+40 RT.					20							
STA. 101+23						106						21
STA. 101+25 TO 119+58	3,558	900	3,597					366	732	183		
STA. 101+59 LT.					20							
STA. 119+58 RT.					23							
STA. 119+65						95						42
STA. 119+58 TO 120+38 LT.											52	148
STA. 120+58 LT.					27							
STA. 120+58 TO 126+37		300	1,157					116	232	58		
STA. 126+37 RT.					22							
STA. 127+37 LT.					22							
BROOKSIDE AVENUE												
STA. 130+30						82						
STA. 130+38 LT.					17							
STA. 130+38 TO 141+50			2,224									
STA. 141+50 TO 143+43			753	72				39		13		
STA. 143+43 TO 144+59	115		230					12	12	8		
STA. 144+59 RT.					24							
STA. 144+67						101						
TOTAL	6,055	1,200	10,438	72	175	384	31.2	781	976	303	52	211

NOTE: 127 RRPMS SHALL BE REMOVED ON WEST BROADWAY PRIOR TO MILLING OPERATIONS. PAVEMENT MARKERS WILL NOT BE REPLACED DURING THIS PROJECT.  
\* - LEFT EDGE LINE SHALL END AT STA. 99+45