

SIGN SCHEDULE

LOCATION	NAME	SIGNS		POSTS (FOOT)
		NO.	SQ. FT.	
SCSF&W ENTRANCE ROAD	BIKE ROUTE	D11-1	3.00	15.5
SCSF&W ENTRANCE ROAD	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
SCSF&W ENTRANCE ROAD	BICYCLE GUIDE ("5.6 MILES")	D1-1b	1.00	-
SCSF&W ENTRANCE ROAD	SINGLE ARROW	M7-1	0.75	-
SCSF&W ENTRANCE ROAD	BIKE ROUTE	D11-1	3.00	15.5
SCSF&W ENTRANCE ROAD	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
SCSF&W ENTRANCE ROAD	BICYCLE GUIDE ("5.6 MILES")	D1-1b	1.00	-
SCSF&W ENTRANCE ROAD	SINGLE ARROW	M7-1	0.75	-
SCSF&W ENTRANCE ROAD	BICYCLE WARNING	W11-1	4.00	15.0
SCSF&W ENTRANCE ROAD	SHARE THE ROAD	W16-1	3.00	-
SCSF&W ENTRANCE ROAD	BICYCLE WARNING	W11-1	4.00	15.0
SCSF&W ENTRANCE ROAD	SHARE THE ROAD	W16-1	3.00	-
STA. 0+00 LT	STOP	R1-1	2.25	13.5
STA. 0+25 RT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 0+60 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	13.5
STA. 0+60 LT	SINGLE ARROW	M7-1	0.75	-
STA. 0+60 RT	MILEPOST ("MILE 0")	M1-8	1.50	13.5
STA. 0+60 RT	MILEPOST ("MILE 0")	M1-8	1.50	-
STA. 26+30 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	13.5
STA. 26+30 LT	SINGLE ARROW	M7-1	0.75	-
STA. 27+67 RT	STOP	R1-1	2.25	13.5
STA. 27+67 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 27+90 LT	STOP	R1-1	2.25	13.5
HORSESHOE ROAD WEST	BICYCLE WARNING	W11-1	4.00	15.0
HORSESHOE ROAD WEST	SHARE THE ROAD	W16-1	3.00	-
HORSESHOE ROAD EAST	BICYCLE WARNING	W11-1	4.00	15.0
HORSESHOE ROAD EAST	SHARE THE ROAD	W16-1	3.00	-
STA. 28+55 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 28+80 RT	YIELD	R1-2	0.97	13.5
STA. 29+25 RT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 29+55 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	13.5
STA. 29+55 RT	SINGLE ARROW	M7-2	0.75	-
STA. 29+65 LT	YIELD	R1-2	0.97	13.5
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
STA. 42+00 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	13.5
STA. 42+00 LT	SINGLE ARROW	M7-1	0.75	-
STA. 42+00 RT	STOP	R1-1	2.25	13.5
STA. 42+23 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 52+80 RT	MILEPOST ("MILE 1")	M1-8	1.50	13.5
STA. 52+80 RT	MILEPOST ("MILE 1")	M1-8	1.50	-
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
STA. 61+40 LT	STOP	R1-1	2.25	13.5
STA. 61+40 RT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 63+00 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	13.5
STA. 63+00 RT	SINGLE ARROW	M7-1	0.75	-
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
STA. 73+20 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	13.5
STA. 73+20 RT	SINGLE ARROW	M7-1	0.75	-
STA. 73+80 RT	STOP	R1-1	2.25	13.5
STA. 73+90 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
STA. 74+35 LT	BIKE ROUTE	D11-1	3.00	15.0
STA. 74+35 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
STA. 74+35 LT	SINGLE ARROW	M7-1	0.75	-
STA. 105+60 RT	MILEPOST ("MILE 2")	M1-8	1.50	13.5
STA. 105+60 RT	MILEPOST ("MILE 2")	M1-8	1.50	-
STA. 125+90 RT	BIKE ROUTE	D11-1	3.00	15.0
STA. 125+90 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
STA. 125+90 RT	SINGLE ARROW	M7-1	0.75	-
LOWER ROAD	BICYCLE WARNING	W11-1	4.00	15.0
LOWER ROAD	SHARE THE ROAD	W16-1	3.00	-
STA. 127+15 LT	STOP	R1-1	2.25	13.5
STA. 127+50 LT	BIKE ROUTE	D11-1	3.00	15.0
STA. 127+50 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
STA. 127+50 LT	SINGLE ARROW	M7-1	0.75	-

SIGN SCHEDULE

LOCATION	NAME	SIGNS		POSTS (FOOT)
		NO.	SQ. FT.	
STA. 133+25 RT	CURVE WARNING	W1-1	2.25	14.5
STA. 134+05 RT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 134+20 LT	CURVE WARNING	W1-1	2.25	14.5
STA. 158+40 RT	MILEPOST ("MILE 3")	M1-8	1.50	13.5
STA. 158+40 RT	MILEPOST ("MILE 3")	M1-8	1.50	-
STA. 211+20 RT	MILEPOST ("MILE 4")	M1-8	1.50	13.5
STA. 211+20 RT	MILEPOST ("MILE 4")	M1-8	1.50	-
STA. 233+00 RT	BIKE ROUTE	D11-1	3.00	15.0
STA. 233+00 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
STA. 233+00 RT	SINGLE ARROW	M7-1	0.75	-
STA. 233+40 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 233+45 RT	STOP	R1-1	2.25	13.5
STA. 234+45 LT	BIKE ROUTE	D11-1	3.00	15.0
STA. 234+45 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
STA. 234+45 LT	SINGLE ARROW	M7-1	0.75	-
GALLATIN COUNTY HWY 7	BIKE ROUTE	D11-1	3.00	15.0
GALLATIN COUNTY HWY 7	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
GALLATIN COUNTY HWY 7	SINGLE ARROW	M7-1	0.75	-
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
265+00 LT	BICYCLE WARNING	W11-1	4.00	15.0
265+00 LT	SHARE THE ROAD	W16-1	3.00	-
267+00 RT	BICYCLE WARNING	W11-1	4.00	15.0
267+00 RT	SHARE THE ROAD	W16-1	3.00	-
STA. 264+00 RT	MILEPOST ("MILE 5")	M1-8	1.50	13.5
STA. 264+00 RT	MILEPOST ("MILE 5")	M1-8	1.50	-
STA. 271+75 RT	BIKE ROUTE	D11-1	3.00	15.0
STA. 271+75 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
STA. 271+75 RT	SINGLE ARROW	M7-1	0.75	-
GALLATIN COUNTY HWY 7	BIKE ROUTE	D11-1	3.00	16.5
GALLATIN COUNTY HWY 7	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
GALLATIN COUNTY HWY 7	SINGLE ARROW	M7-1	0.75	-
GALLATIN COUNTY HWY 7	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-

SIGN SCHEDULE

LOCATION	NAME	SIGNS		POSTS (FOOT)
		NO.	SQ. FT.	
GALLATIN COUNTY HWY 7	SINGLE ARROW	M7-2	0.75	-
GALLATIN COUNTY HWY 7	BICYCLE WARNING	W11-1	4.00	15.0
GALLATIN COUNTY HWY 7	SHARE THE ROAD	W16-1	3.00	-
STA. 272+70 LT	BIKE ROUTE	D11-1	3.00	15.0
STA. 272+70 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
STA. 272+70 LT	SINGLE ARROW	M7-1	0.75	-
STA. 292+80 RT	BIKE ROUTE	D11-1	3.00	15.0
STA. 292+80 RT	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
STA. 292+80 RT	SINGLE ARROW	M7-1	0.75	-
LANE STREET	BICYCLE WARNING	W11-1	4.00	15.0
LANE STREET	SHARE THE ROAD	W16-1	3.00	-
LANE STREET	BIKE ROUTE	D11-1	3.00	16.5
LANE STREET	BICYCLE GUIDE ("EQUALITY")	D1-1b	1.00	-
LANE STREET	SINGLE ARROW	M7-2	0.75	-
LANE STREET	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
LANE STREET	SINGLE ARROW	M7-1	0.75	-
STA. 293+70 LT	BIKE ROUTE	D11-1	3.00	15.0
STA. 293+70 LT	BICYCLE GUIDE ("GLEN O JONES LAKE")	D1-1b	1.00	-
STA. 293+70 LT	SINGLE ARROW	M7-1	0.75	-
STA. 295+75 LT	BICYCLE WARNING	W11-1	4.00	15.0
STA. 295+75 LT	SHARE THE ROAD	W16-1	3.00	-

PROJECT TOTALS 265.94 890

TREE REMOVAL SCHEDULE

STATION	WIDTH	ACRES
10+00 to 12+50	15'	0.1
27+85 to 43+00	30'	1.1
55+00 to 55+50	30'	0.1
133+50 to 134+50	40'	0.1
160+00 to 205+50	65'	6.8


TOTALS 8.2

CULVERT SCHEDULE

STATION	12" DIA CSCP TY1 (FOOT)	15" DIA CSCP TY1 (FOOT)	15" DIA CSCP TY2 (FOOT)	36" DIA CSCP TY2 (FOOT)	36" DIA CSCP TY3 (FOOT)	15" DIA RCCP (FOOT)	24" DIA RCCP (FOOT)	42" DIA RCCP (FOOT)	8'x4' PCBC (FOOT)	15" DIA SES (EACH)	24" DIA PRCFES (EACH)	8'x4' PRC END (EACH)	TRENCH BACKFILL (CU YD)	CONCRETE COLLAR (CU YD)	STONE RR A3 (TON)
0+32			52												
7+00							12			2			3.4		
16+62						30					1		2.2	0.16	
17+74						27									
25+07		26											2.4		
27+60	24												2.1		
27+98		24											3.0		
42+40						44							4.5		
73+70	24												2.2		
133+92	28												2.2		
135+75	24												2.1		
143+00	24												2.1		
153+75		28											2.4		
169+36						100							6.7		16
179+58						76							7.2		16
184+07						80							6.3		16
185+51						100							6.7		16
193+77						100							6.7		16
195+80				50									6.3		16
203+55	50												3.1		
211+00		24											2.4		
233+53								35						0.53	
TOTALS	174	102	52	50	456	101	12	35		2	1		74.0	0.69	96

PROJ. NO. ARA-TE-D009(84)
CONTRACT NO. 99292

BROWN AND ROBERTS, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
1 WESTRIDGE ROAD HARRISBURG, IL. 62946 (618) 252-8111



S.V.C.D.
ILLINOIS TRANSPORTATION
ENHANCEMENT PROGRAM
MATERIAL SCHEDULES

Drawn By: VJW
Checked By: MWR
Revisions
Scale: AS SHOWN
Field Bk: 04-096
Job Number: 04-096
Date: 05/07

14 Oct 2009 - 8:45am X:\2004\04096\oc\PLANS\3-e material schedules and typical details.dwg