

SCHEDULE OF QUANTITIES

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00118-00-RP	JACKSON	32	3
JOB NO. C-99-515-06 FED PROJ: HPP-0321(117)				
CITY OF CARBONDALE				

SIDEWALK REMOVAL

BEGIN STATION	END STATION	SQ FT
REED STATION PARKWAY CONNECTOR		
3+65.82/30.09' RT	4+19.38/23.24' RT	208.5
4+56.36/19.17' RT	4+70.07/18.89' RT	48.8
GRAND TOTAL:		257.3

COMBINATION CURB & GUTTER REMOVAL

BEGIN STATION	END STATION	LN FT
REED STATION PARKWAY		
3+61.30/1.02' RT	4+70/11.87' LT	109.5
3+65.08/24.66' RT	4+70/11.89' RT	105.7
4+11.81/18.50' RT	4+21.74/25.23' RT	12.3
4+55.30/20.84' RT	4+64.51/12.54' RT	13.1
GRAND TOTAL:		240.6

REMOVING INLETS

STATION/OFFSET	EACH
REED STATION PARKWAY	
0+48.78/43.85 RT	1.0
GRAND TOTAL:	
	1.0

STORM SEWER REMOVAL 18"

BEGIN STATION	END STATION	LN FT
ACCESS ROAD		
0+93.8/41.7' RT	0+93.8/47.7' RT	6.0
SUB-TOTAL:		6.0
REED STATION PARKWAY		
0+25.40/44.1' RT	0+45.8/43.8' RT	20.5
0+51.7/43.9' RT	0+76.5/43.9 RT	24.5
SUB-TOTAL:		45.0
GRAND TOTAL:		51.0

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

STATION/OFFSET	UNIT
ACCESS ROAD	
0+58.8/41.7' LT	12
SUB-TOTAL:	
	12
REED STATION PARKWAY	
3+47.3/24.6' LT	10
3+71.3/26.4' LT	9
SUB-TOTAL:	
	19
GRAND TOTAL:	
	31

TREE REMOVAL(OVER 15 UNITS DIAMETER)

STATION/OFFSET	UNIT
ACCESS ROAD	
0+47.5/55.9' LT	36
0+60.0/41.0' LT	16
0+61.7/40.3' LT	16
SUB-TOTAL:	
	68
REED STATION PARKWAY	
3+08.5/8.8' LT	18
SUB-TOTAL:	
	18
GRAND TOTAL:	
	86

TREE REMOVAL, ACRES

BEGIN STATION	END STATION	ACRES
ACCESS ROAD		
1+16 RT-LT	4+46 RT	0.520
1+28 LT	2+27 LT	0.040
GRAND TOTAL:		0.560

PROCESSING MODIFIED SOIL, 12"

BEGIN STATION	END STATION	SQ YD
ROUTE 13		
192+50 LT	201+03.70 LT	4075
SUB-TOTAL:		4075
ACCESS ROAD		
1+10	4+65	1462
SUB-TOTAL:		1462
REED STATION PARKWAY		
0+16	4+70	1735
SUB-TOTAL:		1735
GRAND TOTAL:		7272

LIME

BEGIN STATION	END STATION	TON
ROUTE 13		
192+50 LT	201+03.70 LT	81
SUB-TOTAL:		81
ACCESS ROAD		
1+10	4+65	29
SUB-TOTAL:		29
REED STATION PARKWAY		
0+16	4+70	35
SUB-TOTAL:		35

GRAND TOTAL: 145

COMBINATION CONCRETE CURB & GUTTER

BEGIN STATION	END STATION	M-6.06 (FT)	B-6.12 (FT)	B-6.18 (FT)	M-6.24 (FT)
ROUTE 13					
203+57.03/19.00' LT	204+57.52/19.00' LT				105.74
203+56.69/22.97' LT	204+33.06/55.59' LT	93.25			
204+41.52/53.64' LT	204+59.02/22.32' LT	43.69			
TOTAL:		136.94			105.74

BEGIN STATION	END STATION	M-6.06 (FT)	B-6.12 (FT)	B-6.18 (FT)	M-6.24 (FT)
ACCESS ROAD					
1+10/20.64' RT	3+63.69/55.14' RT			269.48	
4+02.50/79.87' RT	4+65/25.35' RT			89.88	
1+10/18.36' LT	4+65/17.50' LT			355.05	
TOTAL:				714.41	

BEGIN STATION	END STATION	M-6.06 (FT)	B-6.12 (FT)	B-6.18 (FT)	M-6.24 (FT)
REED STATION PARKWAY					
0+55.14/26.32' RT	4+70/11.89' RT			414.66	
4+02.73/12.58' RT	4+21.74/25.23' RT			23.42	
4+55.30/20.84' RT	4+63.78/12.48' RT			12.37	
0+79.88/12.49' LT	4+70/11.87' LT			391.65	
TOTAL:				842.10	

POLYMERIZED HOT MIX-ASPHALT SURFACE COURSE, MIX "D", N90

BEGIN STATION	END STATION	TON
ROUTE 13		
192+50 LT	201+03.70 LT	358
SUB-TOTAL:		358

BEGIN STATION	END STATION	TON
ACCESS ROAD		
1+10	4+65	125
SUB-TOTAL:		125

BEGIN STATION	END STATION	TON
REED STATION PARKWAY		
0+16	4+70	142
SUB-TOTAL:		142
GRAND TOTAL:		625

POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90

BEGIN STATION	END STATION	TON
ROUTE 13		
192+50 LT	201+03.70 LT	460
SUB-TOTAL:		460

BEGIN STATION	END STATION	TON
ACCESS ROAD		
1+10	4+65	160
SUB-TOTAL:		160

BEGIN STATION	END STATION	TON
REED STATION PARKWAY		
0+16	4+70	182
SUB-TOTAL:		182
GRAND TOTAL:		802

DETECTABLE WARNINGS

BEGIN STATION	END STATION	SQ FT
ACCESS ROAD		
4+52 RT		8.0
SUB-TOTAL:		8.0
REED STATION PARKWAY		
0+33 RT		10.0
4+08 RT		8.0
4+62 RT		8.0
SUB-TOTAL:		26.0
GRAND TOTAL:		34.0

PCC SIDEWALK, 4"

BEGIN STATION	END STATION	SQ FT
ROUTE 13 (ISLAND AREA)		
203+57 LT	204+58 LT	1565.0
SUB-TOTAL:		1565.0

BEGIN STATION	END STATION	SQ FT
ACCESS ROAD		
4+42.16/31.49' RT	4+65/31.49' RT	112.0
SUB-TOTAL:		112.0

BEGIN STATION	END STATION	SQ FT
REED STATION PARKWAY		
0+32.52/43.17' RT	4+14.01/18.08' RT	1938.0
4+58.30/16.59' RT	4+69.94/16.17' RT	57.0
SUB-TOTAL:		1995.0
GRAND TOTAL:		3672.0

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90

BEGIN STATION	END STATION	TON
ROUTE 13		
192+50 LT	201+03.70 LT	2228
SUB-TOTAL:		2228

BEGIN STATION	END STATION	TON
ACCESS ROAD		
1+10	4+65	426
SUB-TOTAL:		426

BEGIN STATION	END STATION	TON
REED STATION PARKWAY		
0+16	4+70	486
SUB-TOTAL:		486
GRAND TOTAL:		3140

FILE: T:\ST0305\Drawings\SCHEDULES.DWG PROJECT NAME: ST0305 PAPERSCALE: 1"=40' PLOT SCALE: 1"=40' LINE TYPE SCALE: 40' PLOT VIEW: PLOT DRAWN BY: RP PS VIEW: 1