SIGN SCHEDULE

PAY ITEM:	72000100	SIGN PANEL - TYPE 1	NO.	46
	73000105	WOOD SIGN SUPPORT, SPECIAL		49

STATION			NAME	SIGNS NO.	SIGNS SQ FT	POSTS FOOT
1000	+	0	STOP SIGN	R1-1	2.25	11.5
1000	+	0	NO MOTOR VEHICLES	R5-3	4	14.5
1000	+	0	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
1000	+	0	BIKE ROUTE	D11-1	3	14.5
1000	+	0	SINGLE ARROW	M7-1	0.75	
1000	+	0	BICYCLE WARNING	W11-1	6.25	13.5
1000	+	25	BIKEWAY NARROWS	W5-4a	2.25	
1000	+	50	INTERSECTION WARNING	W2-1	2.25	13.5
1000	+	75	BIKE ROUTE	D11-1	3	14.5
1000	+	75	DOWNTOWN	M4-13	0.33	
1000	+	75	ROUTE SIGN	M7-2	0.75	
1000	+	75	BIKE ROUTE	D11-1	3	14.5
1000	+	75	STATE PARK	M4-13	0.33	
1000	+	75	ROUTE SIGN	M7-2	0.75	
1001	+	0	BIKEWAY NARROWS	W5-4a	2.25	13.5
1003	+	90	BIKEWAY NARROWS	W5-4a	2.25	14.5
1005	+	40	BIKEWAY NARROWS	W5-4a	2.25	14.5
1008	+	90	YIELD TO PEDESTRIANS	R9-6	1.5	13.5
1008	+	90	BIKE ROUTE	D11-1	3	14.5
1008	+	90	ROUTE SIGN	M7-2	0.75	11.5
1009	+	90	BICYCLE PARKING	R9-6	1.5	11.5
1010	+	15	BICYCLE PARKING	R9-6	1.5	11.5
1010	+	60	CURVE WARNING	W1-5	2.25	13.5
1012	+	95	YIELD TO PEDESTRIANS	R9-6	1.5	13.5
1012	+	10	BIKE ROUTE	D11-1	3	14.5
1012	+	10	SINGLE ARROW	M7-1	0.75	
1012	+	15	CURVE WARNING	W1-5	2.25	13.5
1012	+	60	NO MOTOR VEHICLES	R5-3	4	14.5
1012	+	60	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
1012	+	60	STOP SIGN	R1-1	2.25	11.5
1012	+	90	BIKE ROUTE	D11-1	3	14.5
1012	+	90	SINGLE ARROW	M7-1	0.75	
1013	+	15	BIKE ROUTE	D11-1	3	14.5
1013	+	15	SINGLE ARROW	M7-1	0.75	
1025	+	10	INTERSECTION WARNING	W2-2	2.25	13.5
1026	+	5	BIKE ROUTE	D11-1	3	14.5
1026	+	5	SINGLE ARROW	M7-1	0.75	
1026	+	60	STOP SIGN	R1-1	2.25	11.5
1026	+	80	BICYCLE WARNING	W11-1	6.25	13.5
1026	+	80	SHARE THE ROAD PLAQUE	W16-1	3	
1026	+	90	BIKE ROUTE	D11-1	3	14.5
1026	+	90	STATE PARK	M4-13	0.33	
1026	+	90	SINGLE ARROW	M7-1	0.75	
1027	+	90	INTERSECTION WARNING	W2-4	2.25	13.5
20	+	50	NARROW BRIDGE	W5-2	2.25	14.5
21	+	0	STOP SIGN	R1-1	2.25	11.5
22	+	80	STOP SIGN	R1-1	2.25	11.5
23	+	40	NARROW BRIDGE	W5-2	2.25	14.5
32	+	10	BICYCLE WARNING	W11-1	6.25	13.5
32	+	10	SHARE THE ROAD PLAQUE	W16-1	3	
32	+	85	BIKE ROUTE	D11-1	3	14.5
32	+	85	SINGLE ARROW	M7-1	0.75	
33	+	10	BIKE ROUTE	D11-1	3	14.5
33	+	95	BIKE ROUTE	D11-1	3	14.5
33	+	95	SINGLE ARROW	M7-2	0.75	
34	+	60	BICYCLE WARNING	W11-1	6.25	13.5
34	+	60	SHARE THE ROAD PLAQUE	W16-1	3	
33	+	50	NO MOTOR VEHICLES	R5-3	4	14.5
33	+	50	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
1076	+	90	BIKE ROUTE	D11-1	3	14.5
1076	+	90	SINGLE ARROW	M7-1	0.75	
1143	+	0	BIKE ROUTE	D11-1	3	14.5
1143	+	0	BICYCLE GUIDE	D1-1b	1	
1143	+	0	SINGLE ARROW	M7-1	0.75	
1144	+	5	INTERSECTION WARNING	W2-1	2.25	14.5
1144	+	95	STOP SIGN	R1-1	2.25	11.5
BELGRADE SO. 100'			BIKE ROUTE	D11-1	3	14.5
BELGRADE SO. 100'			DOUBLE ARROW	M7-5	0.75	
BELGRADE SO. 300'			BICYCLE WARNING	W11-1	6.25	13.5
1145	+	0	NO MOTOR VEHICLES	R5-3	4	14.5
1145	+	0	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
BELGRADE SO. 100'			BIKE ROUTE	D11-1	3	14.5
BELGRADE SO. 100'			DOUBLE ARROW	M7-5	0.75	
BELGRADE SO. 300'			BICYCLE WARNING	W11-1	6.25	13.5
1145	+	20	STOP SIGN	R1-1	2.25	11.5
1145	+	20	NO MOTOR VEHICLES	R5-3	4	14.5
1145	+	20	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
1146	+	50	INTERSECTION WARNING	W2-1	2.25	14.5
1147	+	50	BIKE ROUTE	D11-1	3	14.5
1147	+	50	BICYCLE GUIDE	D1-1b	1	
1147	+	50	SINGLE ARROW	M7-1	0.75	
1214	+	80	BICYCLE PARKING	D4-3	1.5	13.5
1215	+	0	BIKE ROUTE	D11-1	3	14.5
1215	+	0	BICYCLE GUIDE	D1-1b	1	
1215	+	0	SINGLE ARROW	M7-1	0.75	
1215	+	0	BICYCLE GUIDE	D1-1b	1	
1215	+	0	SINGLE ARROW	M7-1	0.75	
1215	+	25	BIKE ROUTE	D11-1	3	14.5
1215	+	25	SINGLE ARROW	M7-1	0.75	
1215	+	75	INTERSECTION WARNING	W2-1	2.25	14.5
1216	+	5	NO MOTOR VEHICLES	R5-3	4	14.5
1216	+	5	EQUESTRIANS PROHIBITED	R5-3.01	2.25	
1216	+	25	STOP SIGN	R1-1	2.25	11.5
STRAWBERRY RD 50, SO.			BIKE ROUTE	D11-1	3	14.5
STRAWBERRY RD 50, SO.			BICYCLE GUIDE	D1-1b	1	
STRAWBERRY RD 50, SO.			SINGLE ARROW	M7-1	0.75	
STRAWBERRY RD 50, NO.			BICYCLE PARKING	D4-3	1.5	13.5
STRAWBERRY RD 100, NO.			BIKE ROUTE	D11-1	3	14.5
STRAWBERRY RD 100, NO.			ROUTE SIGN ARROWS	M7-6	0.75	
STRAWBERRY RD 200, NO.			BICYCLE PARKING	D4-3	1.5	13.5
STRAWBERRY RD 200, NO.			BICYCLE WARNING	W11-1	6.25	13.5
STRAWBERRY RD 200, NO.			SHARE THE ROAD PLAQUE	W16-1	3	

SIGNING QUANTITIES — SIGNS 221.24 — POSTS 807.5

PAY ITEM RECAP
PAY ITEM: RELOCATE SIGN PANELTYPE 1
ITEM CODE NO.: 72400710 * NO. 47

FROM STATION			TO STATION			QUAN	UNIT	QUANTITY
1001	+	50	1005	+	50	1	SQ FT	1
1001	+	50	1005	+	50	1	SQ FT	1
1001	+	50	1005	+	50	1	SQ FT	1
							TOTAL	3

PAY ITEM RECAP
PAY ITEM: TELESCOPING STEEL SIGN SUPPORT
ITEM CODE NO.: 72800100 0 NO. 48

SUPPORTS	STATION			LENGTH	WIDTH	UNIT	QUANTITY
HANDICAP SIGN	3	+	50	10		FOOT	10
HANDICAP SIGN	34	+	50	10		FOOT	10
HANDICAP SIGN	1215	+	50	10		FOOT	10
						TOTAL	30

PAY ITEM RECAP
PAY ITEM: WOOD SIGN SUPPORT, SPECIAL
ITEM CODE NO.: 73000105 * NO. 49

FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY
SEE PAY ITEM NO. 21 RECAP				FOOT	
				TOTAL	807.5

PAY ITEM RECAP
PAY ITEM: PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS
ITEM CODE NO.: 78001100 0 NO. 50

	STATION			LENGTH	WIDTH	UNIT	QUANTITY
ADA SPACE SYMBOL	2	+	93	3	3	SQ FT	9
ADA SPACE SYMBOL	34	+	20	3	3	SQ FT	9
ADA SPACE SYMBOL	1215	+	50	3	3	SQ FT	9
						TOTAL	27

PAY ITEM RECAP
PAY ITEM: PAINT PAVEMENT MARK ING - LINE 4"
ITEM CODE NO.: 78001110 0 NO. 51

FROM STATION			TO STATION			LENGTH	UNIT	QUANTITY
2	+	93	3	+	80	230	FOOT	230
34	+	0	34	+	60	200	FOOT	200
1215	+	0	1215	+	44	200	FOOT	200
							TOTAL	630

PAY ITEM RECAP
PAY ITEM: PAINT PAVEMENT MARKING - LINE 12"
ITEM CODE NO.: 78001150 0 NO. 52

	STATION			LENGTH	WIDTH	UNIT	QUANTITY
1000	+	0	5	12	FOOT		5
1012	+	60	5	12	FOOT		5
21	+	0	5	12	FOOT		5
33	+	10	5	12	FOOT		5
1145	+	20	5	12	FOOT		5
1145	+	40	5	12	FOOT		5
1216	+	25	5	12	FOOT		5
					TOTAL		35

PAY ITEM RECAP
PAY ITEM: BUMPER BLOCKS
ITEM CODE NO. Z0007800 * NO. 53

FROM STATION			TO STATION			LGTH	QUAN	UNIT	QUANTITY
1215	+	0	1215	+	25	25	5	EACH	5
2	+	93	3	+	80	87	11	EACH	11
							TOTAL		16

PAY ITEM RECAP
PAY ITEM: BICYCLE RACKS
ITEM CODE NO.: XX001011 * NO. 70

STATION			QUANTITY	UNIT	QUANTITY
1010	+	0	1	EACH	1
1215	+	15	1	EACH	1
34	+	0	1	EACH	1
?			1		1
?			1		1
			TOTAL		5

PAY ITEM RECAP
PAY ITEM: WOOD BOLLARD
ITEM CODE NO.: XX001472 * NO. 71

FROM STATION			TO STATION			LENGTH	QUAN	UNIT	QUANTITY
1215	+	0	1215	+	50	50	57	EACH	57
2	+	85	3	+	92	107	54	EACH	54
33	+	0	35	+	0	200	28	EACH	28
#	PARKING LOT			+					
								TOTAL	139

PAY ITEM RECAP
PAY ITEM: INFORMATION KIOSK
ITEM CODE NO.: XX001683 * NO. 72

STATION			LENGTH	NO.	UNIT	QUANTITY
1009	+	90.65	NA	1	EACH	1
1215	+	15	121515	1	EACH	1
				TOTAL		2

PAY ITEM RECAP
PAY ITEM: GRADING AND SHAPING BIKEWAY
ITEM CODE NO.: * NO. 73

FROM STATION			TO STATION			LENGTH	WIDTH	UNIT	QUANTITY
999	+	98	1008	+	84	886	14	STA	8.9
1007	+	90	1008	+	0	10	14	STA	0.1
1009	+	63	1009	+	78	15	7	STA	0.2
1009	+	88	1010	+	13	25	7	STA	0.3
1010	+	23	1010	+	68	45	7	STA	0.5
1010	+	68	1011	+	9	41	7	STA	0.4
1011	+	9	1012	+	65	156	7	STA	1.6
33	+	0	36	+	44	344	14	STA	3.4
1076	+	38	1145	+	20	6882	15	STA	68.8
1145	+	35	1160	+	44	1509	15	STA	15.1
1164	+	66	1203	+	57	3891	15	STA	38.9
1205	+	57	1216	+	44	1087	15	STA	10.9
								TOTAL	148.9

PAY ITEM RECAP
PAY ITEM: PIPE GATE
ITEM CODE NO.: XX004652 * NO. 75

STATION			QUANTITY	UNIT	QUANTITY
4	+	0	1	EACH	1
32	+	90	1	EACH	1
			TOTAL		2

PAY ITEM RECAP
PAY ITEM: FLASHING BEACON INSTALLATION
ITEM CODE NO.: X0324773 * NO. 81

COLOR	STATION			QUAN	UNIT	QUANTITY
YELLOW	BELGRADE, NO., 300'			1	EACH	1
YELLOW	BELGRADE, SO., 300'			1	EACH	1
RED	21	+	0	1	EACH	1
RED	22	+	80	1	EACH	1
				TOTAL		4

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
GRCDT	09-00038-00-BT	MASSAC	55	7
FROM STA.	TO STA.			
FEDERAL PROJECT NO. ARA-5045(009)		CONTRACT NO. 99417		