

INDEX OF SHEETS

1. COVER SHEET
2. LOCATION MAP
3. INDEX OF SHEETS, SUMMARY OF QUANTITIES
STANDARDS AND SUPERELEVATION SCHEDULE
4. TYPICAL SECTIONS
5. GENERAL NOTES & BUTT JOINT DETAILS
6. TYPICAL ENTRANCE DETAILS AND PRIVATE
ENTRANCE SCHEDULE
7. TYPICAL SIDE ROAD DETAILS AND SCHEDULE

STANDARDS

- 701001 - 02
- 701006 - 03
- 701011 - 02
- 701301 - 03
- 701306 - 02
- 701311 - 03
- 701901 - 01
- 780001 - 02
- BLR 24 - 2

SUPERELEVATION SCHEDULE

CURVE NO.	PI STA.	PROPOSED SUPER. %	ATTAIN	REMOVE
1	66+36	5.5	63+53 TO 65+07	67+63 TO 69+17
2	77+77	8.0	73+89 TO 75+49	78+20 TO 79+80
3	84+35	8.0	79+80 TO 81+40	85+61 TO 87+21
4	111+28	4.0	106+23 TO 107+44	115+05 TO 116+26
5	137+96	4.0	130+57 TO 131+78	143+90 TO 145+11
6	154+00	NC	NC	NC
7	177+71	6.0	173+63 TO 175+05	180+17 TO 181+59
8	186+33	6.5	183+09 TO 184+60	187+96 TO 189+47
9	210+00	7.0	205+65 TO 207+25	212+35 TO 213+95
10	219+86	6.0	216+23 TO 217+65	221+95 TO 223+37
11	231+89	6.5	228+55 TO 230+31	233+44 TO 235+20
12	252+40	5.0	249+43 TO 250+66	254+11 TO 255+34
13	270+79	3.0	267+67 TO 268+52	273+05 TO 273+90
14	288+30	4.0	285+58 TO 286+62	289+98 TO 291+02
15	294+60	6.5	291+45 TO 292+96	296+25 TO 297+76

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
			TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,824
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4,102
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	6,434
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,825
67100100	MOBILIZATION	L. SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,000
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	104,870
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	104,870

* SPECIALTY ITEMS