

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SITE PLAN
5	CONSTRUCTION STAGING NOTES
6	STAGE I CONSTRUCTION & STAGE I MAINTENANCE OF TRAFFIC
7	STAGE II CONSTRUCTION & STAGE II MAINTENANCE OF TRAFFIC

S.N. 016-0485

8	GENERAL PLAN & ELEVATION
9	DECK CROSS SECTION & STAGING DETAILS
10	DECK CONCRETE PATCHING

S.N. 016-0486 & S.N. 016-0487

11	GENERAL PLAN & ELEVATION
12	GENERAL PLAN & ELEVATION
13	DECK CROSS SECTION
14	DECK CROSS SECTION
15	DECK CONCRETE PATCHING
16	DECK CONCRETE PATCHING
17	DECK CONCRETE PATCHING
18	DECK CONCRETE PATCHING
19	DECK CONCRETE PATCHING

S.N. 016-0488 & S.N. 016-0489

20	GENERAL PLAN & ELEVATION
21	DECK CONCRETE PATCHING
22	DECK CROSS SECTION
23	DECK CROSS SECTION

S.N. 016-1000 & S.N. 016-1001

24	DECK CONCRETE PATCHING
----	------------------------

S.N. 016-1026

25	GENERAL PLAN & ELEVATION
26	PLAN & EXISTING DECK CROSS SECTION
27	JOINT REPLACEMENT
28	BAR SPLICER ASSEMBLY DETAILS
29	PREFORMED STRIP SEAL JOINT

S.N. 016-2454 & S.N. 016-2455

30	GENERAL PLAN & ELEVATION
31	DECK CONCRETE PATCHING

S.N. 016-2456 & S.N. 016-2457

32	GENERAL PLAN & ELEVATION
33	DECK CONCRETE PATCHING
34	DECK CONCRETE PATCHING
35	DECK CONCRETE PATCHING
36	EXPANSION JOINT DETAILS
37	PREFORMED STRIP SEAL JOINT

38	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES, PARTIAL RAMP CLOSURES (TC17)
39	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC 13).
40	PERMANENT PROTECTION SHIELD (PPS1)

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
701411-05	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS \geq 45 MPH
701421-02	LANE CLOSURE, MULTILANE, DAY OPERATION, FOR SPEEDS \geq 45 MPH TO 55 MPH
701422-02	LANE CLOSURE, MULTILANE, FOR SPEEDS \geq 45 MPH TO 55 MPH
701901-01	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

- ALL WORK SHALL BE ACCOMPLISHED IN TWO STAGES.
- THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM I.D.O.T. FIELD MAINTENANCE ENGINEERS.
- ALL PAVEMENT MARKINGS AND RAISED REFLECTORS AFFECTED BY THE BRIDGE REPAIRS SHALL BE REPLACED. NOMINAL QUANTITIES HAVE BEEN INCLUDED IN THE CONTRACT FOR THIS WORK.
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 AND (847)705-4151, FOR RAMPS, AT LEAST 72 HOURS PRIOR TO INSTALLATION OF THE TEMPORARY TRAFFIC CONTROL DEVICES.
- WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO MOTORING PUBLIC.
- PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS, AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.
- THERE IS NO REPAIR WORK NEEDED FOR S.N. 016-0483, S.N. 016-0484, S.N. 016-0985, S.N. 016-0987, S.N. 016-0046, S.N. 016-1000 & S.N. 016-2408.
- DO NOT SCALE THESE PLANS FOR CONSTRUCTION PURPOSE.
- RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) SHALL BE LOW PROFILE.

SCOPE OF WORK:

- MARK AREAS OF FULL DEPTH AND PARTIAL DEPTH REPAIRS.
- PLACE PERMANENT PROTECTIVE SHIELDING.
- PERFORM BRIDGE DECK SLAB REPAIRS.
- PERFORM JOINT REPAIRS.
- OVERLAY REMOVAL AND REPLACEMENT.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
373	0707-608 HB-I-4	COOK	40	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60C94

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS,
LIST OF STATE STANDARDS
AND GENERAL NOTES
IL. RTE. 171

SCALE: NONE
DATE: DECEMBER 8, 2008

DRAWN BY: S.J.P./A.C.S.
CHECKED BY: S.J.P./A.C.S.

CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO ILLINOIS