

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		JOLIET RD. S.N. 099-0028	IL. RTE. 53 S.N. 099-0260	IL. RTE. 53 S.N. 099-0261
			SFTY-2A	SFTY-2A	SFTY-2A	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	360	157	103	100
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	53	23	15	15
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,436	626	412	398
50157300	PROTECTIVE SHIELD	SQ YD	3,042	982	1030	1030
64200105	SHOULDER RUMBLE STRIP	FOOT	5,518	2,419	1,590	1,509
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	2	2
67100100	MOBILIZATION	L SUM	1	0.5	0.25	0.25
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.5	0.5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	2	2	2
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,202	2,150	1,026	1,026
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,101	1,075	513	513
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,101	1,075	513	513
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,737	2,611	1,590	1,536
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	3,429	1,683	1,108	638
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,326	1,326		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	247	170	39	38
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,419	685	367	367
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	395	211	92	92
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	211	211		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	37	19	9	9
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	39	21	9	9
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	104	52	52	
* 78100300	REPLACEMENT REFLECTOR	EACH	420	235	112	73
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	168	86	41	41
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5,288	3,102	1,200	986
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	39	21	9	9
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.5	0.25	0.25
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	34,146	20,335	7,893	5,918
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.25	0.25
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	27	15	6	6
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	192	138	38	16
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	945	729	128	88
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2	1	1

* SPECIALTY ITEM

FILE NAME = D:\60E59.sht.S00.dgn
PLOT DATE = 12/31/2008



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.Y.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - DECEMBER 30, 2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-55 OVER IL. RTE. 53 AND JOLIET ROAD
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2008-028 BR	WILL	29	3
CONTRACT NO. 60E59				
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				