

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A
42001300	PROTECTIVE COAT	SQ YD	41	41
50102400	CONCRETE REMOVAL	CU YD	15.0	15.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.2	15.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,830	4,830
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500	500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72	72
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	250	250
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	400	400
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	30	30
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	300	300
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	70	70
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,000	1,000
X0320887	POLYMER CONCRETE	CU FT	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	238	238
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	24	24
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	60	60
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2,760	2,760
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	36	36
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	61	61
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	1	1

* SPECIALTY ITEM

FILE NAME = D160E60-shr-S00.dgn
PLOT DATE = 12/31/2008

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - DECEMBER 30, 2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
JOLIET ROAD OVER FLAGG CREEK

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 45+65 TO STA. 46+80

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3562	430 Y-1 BR	COOK	15	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60E60