

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 90% FED. 10% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		GUARDRAIL SFTY-3J
20200100	EARTH EXCAVATION	CU YD	750	750
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1	1
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	4,400	4,400
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,350	1,350
63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	12,325	12,325
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	3
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
63200600	STEEL PLATE BEAM GUARD RAIL REMOVAL, SINGLE RAIL	FOOT	1,250	1,250
63200700	STEEL PLATE BEAM GUARD RAIL REMOVAL, DOUBLE RAIL	FOOT	12,400	12,400
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70200410	GUARDRAIL MARKERS, TYPE A	EACH	160	160
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	90	90
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1

FILE NAME = I:\PROJ\329\329\329\47\Design\ProposedPlan\329\47-RT-S00.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mready	DESIGNED - RJR	REVISED -
	DRAWN - RJR	REVISED -
PLOT SCALE = 1:8000 ' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 12/19/2008	DATE - 12/5/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

FAI 290 / FAP 342 (I-290 / IL 53) WOODFIELD ROAD TO IL 62 (ALGONQUIN ROAD) SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2008-072 GRR	COOK	10	3
CONTRACT NO. 60F73				Rev.
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				