

INDEX OF SHEETS

SHEET NO DESCRIPTION

- 1 TITLE SHEET
- 2 INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4-16 ROADWAY PLANS
- 17-18 MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
- 19 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)

STATE STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 630001-08 STEEL PLATE BEAM GUARDRAIL
- 630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
- 631011-05 TRAFFIC BARRIER TERMINAL, TYPE 2
- 631031-07 TRAFFIC BARRIER TERMINAL, TYPE 6
- 635006-03 REFLECTOR AND TERMINAL MARKER PLACEMENT
- 635011-02 REFLECTOR MARKER AND MOUNTING DETAILS
- 642001-01 SHOULDER RUMBLE STRIPS
- 667101-01 PERMANENT SURVEY MARKERS
- 701400-03 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-05 LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATIONS IS REQUIRED)
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGES OF SCHAUMBURG, HANOVER PARK, AND ITASCA.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED - ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.
5. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.
6. THE CONTRACTOR SHALL DISPOSE OF ALL CUTTINGS AND SWEEP THE SHOULDER CLEAN PRIOR TO OPENING THE TRAFFIC LANE AND SHOULDER TO TRAFFIC. ALL DISPOSAL AND SWEEPING WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF SHOULDER RUMBLE STRIPS.
7. THE CONTRACTOR SHALL RESTRIPE THE EDGE LINES AND SHOULDER DIAGONALS UPON COMPLETION OF THE MILLING OF THE RUMBLE STRIPS. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR POLYUREA PAVEMENT MARKING - LINE 4" AND LINE 12".
8. ALL EXISTING SHOULDERS ARE PCC SHOULDERS EXCEPT FROM STA. 146+83 TO STA. 147+83 AND STA. 402+30 TO STA. 424+13 EASTBOUND ELGIN-O'HARE EXPRESSWAY.

FILE NAME = N:\PROJ\3968\3968_02\Design\Proposed\Plan\3368_02-07-General Notes.dgn

CC Ciorba Group, Inc.
 CONSULTING ENGINEERS
 5507 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60656
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mready	DESIGNED - RJR	REVISED -
	DRAWN - RJR	REVISED -
PLOT SCALE = 1:8000 "/ IN.	CHECKED - WBL	REVISED -
PLOT DATE = 12/23/2008	DATE - 12/23/2008	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**FAP 345 / ELGIN O'HARE EXPRESSWAY
 US 20 (LAKE STREET) TO I-290
 INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	2008-076 I	COOK/DUPAGE	19	2
CONTRACT NO. 60F77				
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				