

## SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STU	ITEP	STU							
					70% FED 30% STATE	80% FED 20% VILLAGE	100% VILLAGE	HARTS	TOUHY	WAIKEGAN	ECT			
					1000-2A	Y003	Y060	70% FED 30% STATE	70% FED 30% STATE	70% FED 30% STATE	70% FED 30% STATE			
★	83006500	LIGHT POLE, ALUMINUM, 30 FT. M.H., 12 FT. MAST ARM	EACH	4		4								
★	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	234		234								
★	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	50		50								
★	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3						1	1	1		
★	85100100	PAINT EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2						1	1	1		
★	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1					1					
★	86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1					1					
★	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2/C	FOOT	1,372					533		839			
★	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3/C	FOOT	2,505					1,280		1,225			
★	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5/C	FOOT	1,655					1,655					
★	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,247					1,247					
★	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT	EACH	1							1			
★	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT	EACH	2					2					
★	87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT	EACH	2					2					
★	87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT	EACH	1					1					
★	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12					8		4			
★	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4					4					
★	87800400	CONCRETE FOUNDATION, TYPE E, 30" DIA	FOOT	34					34					
★	87900200	DRILL EXISTING HANDHOLE	EACH	2							1	1		
★	88030020	SIGNAL HEAD, LED, 1-FACE, 3 SECTION, MAST ARM MOUNTED	EACH	6					6					
★	88030050	SIGNAL HEAD, LED, 1-FACE, 3 SECTION, BRACKET MOUNTED	EACH	3					3					
★	88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	5					5					
★	88600100	DETECTOR LOOP, TYPE 1	FOOT	327					327					
★	88700200	LIGHT DETECTOR	EACH	3					3					
★	88800100	PEDESTRIAN PUSH BUTTON	EACH	11					4	4	3			
★	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1					
★	89502200	MODIFY EXISTING CONTROLLER	EACH	1							1			
★	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,675					1,675					
★	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2					1	1				
★	89502380	REMOVE EXISTING HANDHOLE	EACH	6					6					
★	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6					6					
	550A0040	STORM SEWER, CLASS A, TYPE 1, 10"	FOOT	15	15									
	550A0050	STORM SEWER, CLASS A, TYPE 1, 12"	FOOT	2,035	2,035									
	550A0070	STORM SEWER, CLASS A, TYPE 1, 15"	FOOT	35	35									
	550A0330	STORM SEWER, CLASS A, TYPE 2, 10"	FOOT	17	17									
	550A0340	STORM SEWER, CLASS A, TYPE 2, 12"	FOOT	59	59									
	550A0360	STORM SEWER, CLASS A, TYPE 2, 15"	FOOT	28	28									
★	K0030411	PERENNIAL, ECHINACEA PURPUREA 'MAGNUS', (MAGNUS PURPLE CONEFLOWER), 1 GALLON	EACH	14		14								
★	K0030428	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS, (PRAIRIE DROPSSEED), 1 GALLON	EACH	65		65								
★	X0300635	PLANTERS	EACH	6		6								
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	50	50									
★	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1/C	FOOT	1,214									1,214	
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	107	107									
★	X0323553	ORNAMENTAL FENCE, WROUGHT IRON	FOOT	189		189								
★	X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1									1	
★	X0325737	TEMPORARY TRAFFIC SIGNAL TIMINGS	EACH	1					1					
★	X0444100	BENCHES	EACH	2		2								
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	51			51							
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	8			8							
★	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125 MM12F SM12F	FOOT	1,214									1,214	
	X8950200	REBUILD EXISTING HANDHOLE	EACH	3						3				
	XX000959	TRASH RECEPTACLE	EACH	3		3								
●	XX001490	GATE VALVES, 8"	EACH	6			6							
★	XX002982	GATE VALVES, 6"	EACH	6			6							



USER NAME = charlke	DESIGNED - JPA	REVISED -
PLOT SCALE = N.T.S.	DRAWN - JPA	REVISED -
PLOT DATE = 1/16/2009	CHECKED - JLP	REVISED -
	DATE - 12/16/08	REVISED -

### VILLAGE OF NILES

### SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.U. RTE. 3513	SECTION 08-00107-01-PV	COUNTY COOK	TOTAL SHEETS 169	SHEET NO. 6
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT M -80031723	CONTRACT NO.	