

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STU		STU				
					70% FED 30% STATE	80% FED 20% VILLAGE	100% VILLAGE	HARTS	TOUHY	WAUKEGAN	ECT
					I000-2A	Y003	Y060	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F
★	XX003032	GATE VALVES, 12"	EACH	17			17				
	XX003949	CONSTRUCTION STAKING	L SUM	1	1						
★	XX004810	VALVE VAULTS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2				
	XX005283	BRICK PAVER CROSSWALK	SQ FT	4,850		4,850					
	XX005565	REMOVE AND RESET BRICK PAVERS	SQ FT	2,200		2,200					
★	XX005660	ELECTRIC CABLE IN CONDUIT, NO. 20, 3/C, TWISTED SHIELDED	FOOT	492				492			
★	XX005709	PAINT NEW MAST ARM POLE, UNDER 40 FEET	EACH	3				3			
★	XX005710	PAINT NEW TRAFFIC SIGNAL POST	EACH	3				2		1	
★	XX005770	STRUCTURE TO BE ABANDONED	EACH	20	20						
★	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	32		32					
★	XX007015	PERENNIAL PLANTS, PENNISETUM ALOPECUROIDES (FOUNTAIN GRASS), 1 GALLON	EACH	23		23					
	Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	61	61						
	Z0017700	DRAINAGE AND UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	10	10						
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10						
	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	49	49						
▲	Z0076600	TRAINEES	HOUR	2,000	2,000						
★	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1/C	FOOT	1,044				956		88	
★	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED COUNTDOWN TIMER	EACH	4				2		2	
★	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED COUNTDOWN TIMER	EACH	7				2	4	1	
★	XX005401	STEEL CASING PIPE 24" (BORED AND SACKED)	FOOT	120			120				
★	XX007816	GATE VALVES, 2"	EACH	1			1				
★	XX007817	BUFFALO BOX REMOVAL AND REPLACEMENT	EACH	10			10				
★	XX007818	PRESSURE CONNECTION, 16"x16"x12"	EACH	1			1				
★	XX007819	WATER SERVICE LINE, 1"	EACH	7			7				
★	XX007820	WATER SERVICE LINE, 1 1/2"	EACH	8			8				
★	XX007821	WATER SERVICE LINE, 2"	EACH	8			8				
★	XX007822	WATER SERVICE RECONNECTION (2" IN DIAMETER OR LESS)	EACH	5			5				
★	XX007823	WATER SERVICE RECONNECTION (4" IN DIAMETER OR GREATER)	EACH	4			4				
★	XX007824	BRICK PAVER ACCENT STRIP	SQ FT	9,500		9,500					
★	XX007825	ORNAMENTAL FENCE, WROUGHT IRON, SPECIAL	FOOT	151		151					
★	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2		2					
★	XX007826	POLYETHYLENE DUCT BORED AND PULLED, 1 1/4" DIA WITH ELECTRIC CABLE, 600V (XLP-TYPE USE), 3-1/C, NO. 6 AND 1/C, NO. 6 GROUND	FOOT	2,756		2,756					
★	XX007827	ORNAMENTAL LIGHTING UNIT, ALUMINUM POST WITH CAST ALUMINUM BASE, 16-FT HEIGHT, POST TOP MOUNTED LUMINAIRE, 50 WATT HPS	EACH	11		11					
★	XX007828	ORNAMENTAL LIGHTING UNIT, ALUMINUM POST WITH CAST ALUMINUM BASE, 16-FT HEIGHT, POST TOP MOUNTED LUMINAIRE, 150 WATT HPS	EACH	17		17					
★	XX007579	PAINT EXISTING LIGHTING UNIT	EACH	159		159					
★	X0323706	TRASH RECEPTACLE RELOCATION	EACH	2		2					
★	XX001186	PLANTER REMOVAL	EACH	3		3					
★	XX005186	HEMEROCALLIS 'STELLA D' ORO' (PERENNIAL DAYLILY), 1 GALLON	EACH	106		106					
★	K0030404	RUDBECKIA FULGIDA 'GOLDSTRUM' (PERENNIAL BLACK EYED SUSAN), 1 GALLON	EACH	64		64					
★	XX007829	GRASSES, PENNISETUM ALOPECUROIDES 'HAMELN' (HAMELN DWARF FOUNTAIN GRASS), 1 GALLON	EACH	81		81					
★	XX006102	LIA TRIS SPICATA (BLAZING STAR) 1 GALLON 'KOBOLD'	EACH	115		115					
★	XX007830	CLEAN AND PAINT EXISTING BENCHES	EACH	5		5					
	42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	1,500	1,500						

▲ Y080



USER NAME = char tkc	DESIGNED - JPA	REVISED -
PLDT SCALE = N.T.S.	DRAWN - JPA	REVISED -
PLDT DATE = 1/16/2009	CHECKED - JLP	REVISED -
	DATE - 12/16/08	REVISED -

VILLAGE OF NILES

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3513	08-00107-01-PV	COOK	169	7
CONTRACT NO.				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT M -8003(723)				