

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0125	96-00091-00-FP	MCHENRY	73	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #63123				

SUMMARY OF QUANTITIES					
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	STP FUNDS	CMAQ FUNDS
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	1737	1737	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	643	643	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16	
40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
40603085	HOT-MIX ASPHALT BINDER COURSE, 2 3/4", IL-19.0, N70	TON	232	232	
40603310	HOT-MIX ASPHALT SURFACE COURSE, 2", MIX "C", N50	TON	215	215	
40603340	HOT-MIX ASPHALT SURFACE COURSE, 1 1/2", MIX "D", N70	TON	127	127	
40701811	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6 1/2"	SQ YD	11665	11665	
42001300	PROTECTIVE COAT	SQ YD	4918	2101	2817
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	315	315	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	25352		25352
44000100	PAVEMENT REMOVAL	SQ YD	7797	7797	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3238	3238	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1364	1364	
44000600	SIDEWALK REMOVAL	SQ FT	495	495	
44004000	PAVED DITCH REMOVAL	FOOT	211	211	
44004250	PAVED SHOULDER REMOVAL	SQ YD	231	231	
44201759	CLASS D PATCHES, TYPE IV, 9"	SQ YD	28	28	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2676	2676	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	44	44	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	507	507	
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50200100	STRUCTURE EXCAVATION	CU YD	504	504	
50900500	ALUMINUM RAILING	FOOT	282	282	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	1	1	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	EACH	6	6	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	1	1	

REVISIONS	
NAME	DATE

CITY OF CRYSTAL LAKE

ERICK STREET (FAU 0125)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: DECEMBER 15, 2008

DRAWN BY: MJV
CHECKED BY: DES

