

ITEM 20101100 TREE TRUNK PROTECTION				
EXISTING STATION	OFFSET	LT/RT	UNITS	
ERICK STREET				
11+10.12	29.80	RT	1	
13+25.01	33.42	RT	1	
13+29.31	50.85	RT	1	
13+30.91	27.70	RT	1	
13+31.49	39.68	RT	1	
14+92.12	91.01	LT	1	
14+93.06	70.53	LT	1	
16+78.25	22.03	RT	1	
16+79.06	22.38	RT	1	
16+80.20	22.81	RT	1	
26+31.67	44.83	LT	1	
ILLINOIS ROUTE 176				
205+39.59	39.44	LT	1	
211+37.04	39.68	LT	1	
211+37.12	39.64	LT	1	
211+86.30	38.92	LT	1	
211+87.73	38.77	LT	1	
211+89.02	39.32	LT	1	
212+58.78	38.98	LT	1	
215+17.07	41.54	RT	1	
215+54.58	41.42	RT	1	
217+69.92	43.01	RT	1	
217+82.37	46.20	RT	1	
217+84.36	47.33	RT	1	
<b>TOTAL</b>			<b>23</b>	

ITEM A2001818 TREE, ACER SACCHARUM GREEN MOUNTAIN (GREEN MOUNTAIN SUGAR MAPLE), 2-1/4" CALIPER, BALLED AND BURLAPPED				
STATION	OFFSET	LT/RT	EACH	
ERICK STREET				
10+34.22	59.28	LT	1	
10+71.72	31.92	RT	1	
11+38.00	30.81	RT	1	
13+27.42	28.95	LT	1	
14+94.39	41.85	LT	1	
15+22.43	31.22	LT	1	
15+48.50	31.99	LT	1	
16+61.74	29.73	RT	1	
21+81.78	32.15	LT	1	
21+95.90	32.36	LT	1	
24+13.45	26.27	LT	1	
26+31.39	23.11	LT	1	
<b>TOTAL</b>			<b>12</b>	

LOCATION			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUITABLE EARTH EXCAVATION (CUT)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	CU YD	CU YD	CU YD	CU YD	CU YD
IL ROUTE 176							
206+00.00	TO	206+15.23	4	4	3	0	3
206+15.23	TO	206+50.00	12	15	11	0	11
206+50.00	TO	207+00.00	22	33	25	3	22
207+00.00	TO	207+50.00	19	30	23	3	20
207+50.00	TO	208+00.00	19	34	26	0	26
208+00.00	TO	208+50.00	24	51	38	0	38
208+50.00	TO	208+86.94	12	32	24	6	18
208+86.94	TO	209+00.00	4	14	11	2	8
209+00.00	TO	209+50.00	25	106	79	2	77
209+50.00	TO	210+00.00	20	105	78	2	76
210+00.00	TO	210+50.00	25	62	47	6	40
210+50.00	TO	211+00.00	29	53	39	14	26
211+00.00	TO	211+50.00	24	53	40	18	22
211+50.00	TO	212+00.00	19	45	34	26	8
212+00.00	TO	212+50.00	15	42	31	17	14
212+50.00	TO	213+00.00	12	39	29	5	25
213+00.00	TO	213+50.00	18	38	29	4	25
213+50.00	TO	214+00.00	23	47	35	2	34
214+00.00	TO	214+18.58	5	16	12	2	9
214+18.58	TO	214+50.00	5	31	23	8	15
214+50.00	TO	215+00.00	13	52	39	10	28
215+00.00	TO	215+50.00	18	39	29	5	24
215+50.00	TO	216+00.00	9	48	36	3	34
216+00.00	TO	216+50.00	8	48	36	6	30
216+50.00	TO	217+00.00	13	40	30	6	24
217+00.00	TO	217+50.00	11	36	27	2	25
217+50.00	TO	218+00.00	14	33	25	2	23
218+00.00	TO	218+50.00	12	26	19	5	14
218+50.00	TO	219+00.00	11	25	19	11	7
219+00.00	TO	219+50.00	10	21	16	14	2
219+50.00	TO	220+00.00	4	10	8	13	-5
220+00.00	TO	220+50.00	4	10	8	11	-3
220+50.00	TO	221+00.00	3	5	4	5	-2
<b>TOTALS</b>			<b>464</b>	<b>1,244</b>	<b>933</b>	<b>214</b>	<b>719</b>

ITEM D2002272 EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED				
STATION	OFFSET	LT/RT	EACH	
ERICK STREET				
17+76.19	32.74	RT	1	
17+98.86	32.74	RT	1	
<b>TOTAL</b>			<b>2</b>	

ITEM A2007920 TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED				
STATION	OFFSET	LT/RT	EACH	
ERICK STREET				
16+15.04	31.86	LT	1	
16+38.41	32.36	LT	1	
16+63.54	29.62	LT	1	
20+98.39	31.33	LT	1	
24+72.03	23.27	LT	1	
24+86.30	22.80	LT	1	
24+99.36	23.05	LT	1	
25+12.88	22.71	LT	1	
25+25.59	22.94	LT	1	
25+38.16	23.05	LT	1	
25+49.41	23.05	LT	1	
25+61.46	23.05	LT	1	
25+73.91	23.16	LT	1	
<b>TOTAL</b>			<b>13</b>	

EARTHWORK SUMMARY				
ERICK STREET				
ITEM	UNIT	STAGE 1	STAGE 2	TOTAL
EARTH EXCAVATION (20200100)	CU YD	2,701	1,572	4,275
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	261	321	585
ILLINOIS ROUTE 176				
EARTH EXCAVATION (20200100)	CU YD	1,245		1,245
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	CU YD	465		465

REVISIONS	
NAME	DATE

CITY OF CRYSTAL LAKE

ERICK STREET (FAU 0125)  
SCHEDULE OF QUANTITIES

SCALE: NONE  
DATE: DECEMBER 15, 2008

DRAWN BY: MJV  
CHECKED BY: DES

