000

INDEX OF SHEETS

COVER SHEET

GENERAL NOTES AND SUGGESTED SEQUENCE OF WORK

SUMMARY OF QUANTITIES

EXISTING TYPICAL SECTIONS

PROPOSED TYPICAL SECTIONS

PLAN AND PROFILE

TRAFFIC CONTROL AND DETOUR PLAN PILE BENT ENCASEMENT DETAIL AND LOCATIONS

ABUTMENT CURTAIN WALL DETAIL.

BRIDGE APPROACH PAVEMENT DETAIL

STEEL PLATE BEAM GUARD RAIL DETAIL

CROSS SECTIONS STA. 10+9: TO II+20 CROSS SECTIONS STA. II+20 TO 12+25

RANGE OF 3RD PM -22-

LOCATION SKETCH

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION **DIVISION OF HIGHWAYS**

PLANS FOR PROPOSED FEDERAL AID HIGHWAY

F.A.U. ROUTE 1369 (SCHICK ROAD) SECTION 08-00082-00-BR **BRIDGE REHABILITATION** PROJECT M-9003(226) C-91-314-07VILLAGE OF BARTLETT, DUPAGE COUNTY

R 9 E PROJECT BEGINS, STA. 10+90 CAROL CAROL BENCHMARK STREAM DUPAGE COUNTY FLAG IN NORTH EAST WINGWALL OF SCHICK ROAD BRIDGE OVER WEST BRANCH DUPAGE RIVER

GROSS AND NET LENGTH (SCHICK ROAD) = 210 L.F. = 0.04 MI.

PROJECT ENDS STA. 12+20

DALE V. MARTING No. 062-25264


COUNTY TOTAL SHEET 1369 08-00082-00-BR DUPAGE 13

CONTRACT NO. 63126

STRUCTURE NO. 22-302

C-91-314-07







PMC PROJECT NO. 2826 PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

HIGHWAY STANDARDS

CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER 606001-04

TRAFFIC CONTROL DEVICES 701901-01

780001-02 TYPICAL PAVEMENT MARKINGS 781001-03

TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT)

630001-08 STEEL PLATE BEAM GUARDRAIL

630201-06 PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL

631006-06 TRAFFIC BARRIER TERMINAL, TYPE IB

630301-05 SHOULDER WIDENING FOR TYPE I(SPECIAL) GUARDRAIL TERMINALS 70|502-03 URBAN LANE CLOSURE, 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE 420401-07

Bridge Approach Pavement Connector

TRAFFIC DATA

POSTED SPEED LIMIT = 35 MPH

ADT = 16,350 (CURRENT)

ADT = 21,250 (2030)

TRUCK TRAFFIC = 2%

FUNCTIONAL CLASSIFICATION: MINOR ARTERIAL ROAD

FOR JOINT UTILITY INFORMATION



1 INCH = 20 FT.

CONTRACT NO. 63126