


SUMMARY OF QUANTITIES

PAY ITEM CODE	ITEMS	UNIT	TOTAL	1000	X0802A
20200100	EARTH EXCAVATION	CU YD	450	450	
20200410	EXCAVATION (SPECIAL)	CU YD	26		26
2101625	TOPSOIL FURNISH AND PLACE , 6"	SQ YD	220	220	
25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	4.5	4.5	
25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	4.5	4.5	
25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	4.5	4.5	
25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	220	220	
28000400	PERIMETER EROSION BARRIER	FOOT	420	420	
28000510	INLET FILTERS	EACH	4	4	
28100708	STONE DUMPED RIP RAP, CLASS A4 (SPECIAL)	SQ YD	14	14	
40600100	BITUMINOUS MATERIAL PRIME COAT	GALLON	40	40	
40701981	HOT- MIX ASPHALT PAVEMENT, FULL DEPTH, 15'	SQ YD	150	150	
42001300	PROTECTIVE COAT	SQ YD	332		332
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	284		284
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	336	336	
44001600	BRIDGE WEARING SURFACE REMOVAL (SPECIAL, 3-1/2")	SQ YD	14		14
48203021	HOT- MIX ASPHALT SHOULDER, 6"	SQ YD	80	80	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	15		15
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	2,197		2,197
52100510	ANCHOR BOLTS, 3/4" DIA, 6" LG.	EACH	98		98
60604400	COMBINATION CONCRETE CURB AND GUTTER,TYPE B-6.18	FOOT	140	140	
* 63000155	STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE (SPECIAL)	FOOT	40		40
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	2	
* 63100171	TRAFFIC BARRIER TERMINAL T-B SPECIAL	EACH	2	2	
66411900	TEMPORARY FENCE	FOOT	600	600	
67000500	ENGINEERS FIELD OFFICE, TYPE B	MONTH	4	4	
67100100	MOBILIZATION	LSUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE, 4"	FOOT	110	110	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I- LINE, 4"	FOOT	140	140	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
* 78201000	TERMINAL MARKER DIRECT APPLIED	EACH	4	4	
X0300626	CURB AND GUTTER REMOVAL	FOOT	140	140	
X0320598	TEMPORARY SHEET PILING TO REMAIN IN PLACE	SQ FT	960	960	
X0320887	POLYMER CONCRETE	CU FT	62		62
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	84		84
X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	450		450
X0426200	DEWATERING	LSUM	1	1	
XX007787	CLASS SI CONCRETE	CU YD	39.0		39.0
XX003008	TRAFFIC CONTROL DETOUR	LSUM	1	1	
XZ191305	AGGREGATE SUBGRADE	TON	11	11	
XX007786	METAL SHELL PILE BENT ENCASEMENT COMPLETE	EACH	18		18

* SPECIALTY ITEMS

REVISIONS				PLOTTED BY: AMR ON				 PAVIA-MARTING & Co. 910 WEST LAKE STREET ROSELLE, IL 60172-3352 (630) 529-8800 FAX (630) 894-4910 Design Firm Professional Registration #184882376	TITLE: SCHICK ROAD BRIDGE REHABILITATION SUMMARY OF QUANTITIES	SCALE: NONE
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DESIGNED BY: VP ON	DATE: 10/27/08			
						DRAWN BY: AMR ON	JOB NO: 2826			
						CHECKED BY: VP ON				
						APPROVED BY: DVM ON	SHEET 3 OF 18			