

LOCATION	REMARKS	44002100	44004250	31103000	42100350	42100950	20028415	42001300	31200500	48300715	31100910	31100935	31100965	42000551	
		CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	SUB-BASE GRANULAR MATERIAL (SPECIAL)	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12 1/2"	PAVEMENT REINFORCE-MENT 12 1/2"	GEOTECHNICAL REINFORCEMENT	PROTECTIVE COAT	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/2"	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	PORTLAND CEMENT CONCRETE PAVEMENT 12 1/2" (JOINTED)	
		SQ YD	RT SQ YD LT SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
STAGE 1A															
79 + 17	81 + 87	MEDIAN CROSS-OVER WIDENING												354.00	495.00
83 + 13	85 + 28	MEDIAN CROSS-OVER WIDENING												145.50	257.78
STAGE 1B															
51 + 52	51 + 84	WB MAINLINE	84.92		19.13	59.44	85.67	85.67	85.67		96.33			42.93	
51 + 84	60 + 37	WB MAINLINE	2,295.76			1,607.03	2,279.04	2,279.04	2,279.04		2,563.37			1,117.46	
51 + 84	60 + 37	WB ENTRANCE RAMP FROM IL 84	1,023.99		686.96	716.79	1,014.12	1,014.12	1,014.12		1,865.40	566.94		1,309.72	
60 + 37	63 + 49	WB MAINLINE & BETWEEN WB ENTRANCE RAMP FROM IL 84	1,122.90			786.03	1,062.10	1,062.10	1,062.10		1,166.10			439.00	
60 + 37	63 + 49	WB ENTRANCE RAMP FROM IL 84	504.09	290.71		352.86	574.18	574.18	574.18		1,279.06	402.36		786.60	198.53
63 + 49	64 + 30	WB ENTRANCE RAMP FROM IL 84	134.32	30.92		94.02	149.91	149.91	149.91		270.04	93.13		191.32	
64 + 30	66 + 22	WB MAINLINE	712.45	211.96	322.34	498.72	724.57	724.57	724.57		1,148.24	359.68		685.80	
66 + 22	73 + 17	WB MAINLINE	718.82	328.15	122.06	503.17	2,764.67	2,764.67	2,764.67		3,977.58	981.24		3,605.68	
76 + 80	82 + 44	WB IL 84 ENTRANCE RAMP	1,824.30	316.76	841.97	1,277.01	848.46	848.46	848.46		1,472.70	418.90		312.04	
75 + 87	76 + 80	WB IL 84 ENTRANCE RAMP	160.70	84.75		112.49	163.60	163.60	163.60		255.40	61.13		160.29	
75 + 87	76 + 80	WB IL 84 ENTRANCE BETWEEN ML & RAMP	40.75			28.53	37.16	37.16	37.16		67.82			56.68	
73 + 17	75 + 87	WB IL 84 ENTRANCE RAMP	474.31	240.05		332.02	78.14	78.14	78.14		233.27	66.46			
73 + 17	75 + 87	WB IL 84 ENTRANCE BETWEEN ML & RAMP	405.16			283.61	445.49	445.49	445.49		1,028.31	48.67		349.45	445.49
72 + 71	73 + 17	WB IL 84 ENTRANCE RAMP	75.29	36.85	18.97	52.70	475.29	475.29	475.29		1,176.39	686.43		1,132.00	
73 + 17	83 + 04	WB MAINLINE	3,028.05	298.23		2,119.64	3,928.01	3,928.01	3,928.01		4,257.01			2,323.81	
		CONTINGENCY											2,000.00	3,000.00	
STAGE 1C															
51 + 52	66 + 22	MEDIAN	1,498.03			1,048.62	1,492.07	1,492.07	1,492.07		1,982.07			1,211.11	
STAGE 1D															
123 + 06	125 + 87	WB SCALE ENTRANCE RAMP	447.22	258.51	126.82	313.05	506.57	506.57	506.57		1,744.17	1,142.60		1,484.95	
111 + 46	123 + 06	WB SCALE ENTRANCE RAMP	1,805.75	1,057.68		1,264.03	2,094.80	2,094.80	2,094.80		2,649.00	160.87		1,607.86	
111 + 46	123 + 06	WB SCALE ENTRANCE BETWEEN ML & RAMP	1,531.10			1,071.77	2,148.26	2,148.26	2,148.26		5,167.67	213.34		1,906.06	2,412.73
83 + 04	111 + 46	WB SCALE ENTRANCE RAMP & WB IL 84 EXIT RAMP	488.16	1,542.31		341.71	3,964.97	3,964.97	3,964.97		6,925.31	2,014.68		7,119.48	
81 + 20	82 + 50	TEMPORARY PAVEMENT												67.89	
83 + 55	97 + 06	WB MAINLINE	3,949.13	520.28	1,641.94	2,764.39	6,085.89	6,085.89	6,085.89		6,536.22			4,027.02	
97 + 06	102 + 10	WB MAINLINE	1,314.13	245.37		919.89	2,014.41	2,014.41	2,014.41		2,182.41			1,357.72	
102 + 10	107 + 50	WB MAINLINE	1,446.56	255.55		1,012.59	2,903.93	2,903.93	2,903.93		3,083.93			2,173.34	
107 + 50	112 + 50	WB MAINLINE	1,329.71	228.92		930.80	2,977.84	2,977.84	2,977.84		3,144.51			2,790.22	
112 + 50	122 + 50	WB MAINLINE	2,583.80	459.74		1,808.66	7,743.04	7,743.04	7,743.04		10,133.33	2,056.96		8,513.56	
122 + 50	132 + 50	WB MAINLINE	2,620.31	481.91	1,141.34	1,834.22	5,212.49	5,212.49	5,212.49		7,144.11	1,598.29		6,754.93	
132 + 50	143 + 37	WB MAINLINE	2,842.13	524.09	1,305.03	1,989.49	4,382.03	4,382.03	4,382.03		6,212.66	1,468.29		4,428.49	
143 + 13	143 + 38	WB SCALE EXIT RAMP	39.18	20.30	11.12	27.43	41.78	41.78	41.78		67.08	33.97		61.90	
143 + 38	150 + 52	WB SCALE EXIT RAMP	1,147.19	645.32		803.03	1,129.53	1,129.53	1,129.53		2,941.92	645.94		1,351.58	1,408.44
143 + 38	150 + 52	WB SCALE EXIT BETWEEN ML & RAMP	1,609.25			1,126.48	1,408.42	1,408.42	1,408.42		2,574.83	1,408.41		2,069.49	
143 + 38	150 + 52	WB MAINLINE	1,900.62	327.78		1,330.43	2,878.60	2,878.60	2,878.60		3,116.60			1,921.03	
150 + 52	156 + 71	WB SCALE EXIT RAMP	764.73	590.85		535.31	816.42	816.42	816.42		1,176.52	568.43		1,175.93	
150 + 51	156 + 71	WB MAINLINE	1,647.17	282.82		1,153.02	2,492.06	2,492.06	2,492.06		2,699.06			1,663.34	
156 + 71	160 + 00	WB MAINLINE	859.02	160.06	384.71	601.31	1,312.00	1,312.00	1,312.00		1,858.67	437.33		1,319.31	
160 + 00	167 + 50	WB MAINLINE	1,956.67	372.57	885.20	1,369.67	3,000.00	3,000.00	3,000.00		4,250.00	1,000.00		3,960.11	
167 + 50	177 + 75	WB MAINLINE	2,723.22	461.42	1,190.46	1,906.25	4,100.00	4,100.00	4,100.00		5,808.33	1,366.67		4,095.69	
177 + 75	180 + 00	WB MAINLINE	459.27	123.36	269.58	321.49					577.76	502.76		298.77	
177 + 75	180 + 00	INSIDE WB MAINLINE SHOULDER			123.00						360.33	285.33		402.83	
177 + 75	184 + 00	OUTSIDE WB MAINLINE SHOULDER		558.00							1,048.33	840.00		1,166.39	
180 + 00	182 + 60	MEDIAN CROSS-OVER WIDENING									263.00	398.78			
STAGE 1E															
51 + 52	51 + 84	EB MAINLINE	83.17		3.97	58.22	83.08	83.08	83.08		93.71			41.52	
51 + 84	52 + 84	EB MAINLINE & EB EXIT RAMP TO IL 84	333.12	35.89	14.50	233.18	337.43	337.43	337.43		437.31	66.51		223.03	
52 + 84	54 + 35	EB MAINLINE & EB EXIT RAMP TO IL 84	620.86	112.70	19.53	434.60	625.19	625.19	625.19		777.10	101.58		371.02	
54 + 35	55 + 36	EB MAINLINE & EB EXIT RAMP TO IL 84 & IN BETWEEN	490.00	93.84	12.31	343.00	489.40	489.40	489.40		590.38	67.31		266.45	
55 + 36	57 + 99	EB MAINLINE & EB EXIT RAMP TO IL 84 & IN BETWEEN	1,548.31	230.59	28.72	1,083.82	1,554.81	1,554.81	1,554.81		2,204.89	175.12		783.46	387.30
57 + 99	66 + 21	EB MAINLINE	2,177.33	955.82	178.14	1,524.13	2,194.98	2,194.98	2,194.98		3,954.46	1,485.48		2,585.60	
57 + 99	58 + 27	EB EXIT RAMP TO IL 84	47.91	24.30	11.49	33.54	49.43	49.43	49.43		89.56	30.80		61.31	
66 + 21	68 + 43	EB MAINLINE	585.68	255.17	101.96	409.98	893.73	893.73	893.73		1,254.58	286.86		886.54	
68 + 11	68 + 43	EB ENTRANCE RAMP FROM IL 84	50.68	24.15	13.61	35.48	57.82	57.82	57.82		94.00	25.51		64.57	
68 + 43	69 + 42	EB MAINLINE & BETWEEN ENTRANCE RAMP FROM IL 84	372.06		44.38	260.44	491.65	491.65	491.65		751.76	113.56		396.46	113.56
68 + 43	69 + 42	EB ENTRANCE RAMP FROM IL 84	166.49	88.36		116.54	174.69	174.69	174.69		294.10	86.41		196.26	
69 + 42	83 + 55	EB MAINLINE AND ENTRANCE RAMP FROM IL 84	4,256.81		510.91	2,979.77	5,690.15	5,690.15	5,690.15		7,749.80	1,588.66		5,036.94	