

PIPE CULVERTS, CLASS A, TYPE 1 24" (542A0229)									
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
47	60+57	0'	618.10	60+37	56' RT	617.83	54.0	5	
							TOTAL	54.0	5

PIPE CULVERTS, CLASS A, TYPE 2 24" (542A1069)									
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
2	67+00	3.87 LT	637.86	67+00	85.56 LT	637.00	80	17	
4	81+00	0.0 LT	677.45	81+00	95.20 LT	675.79	25	0	
6	111+00	5.1' LT	686.50	111+00	105.6' LT	686.20	101	30	
8	124+97	3.92 LT	676.63	124+97	76.44 LT	676.29	69	24	
9	135+98	3.88 LT	682.61	135+98	89.96 LT	681.92	82	24	
12	161+97	0.0 LT	670.64	161+97	112.30 LT	664.56	108	61	
18	135+98	89.96 LT	681.92	136+54	215.63 LT	668.55	139	58	
30	53+05	0.9 LT	602.17	53+05	58.6 LT	601.86	59	17	
31	63+88	121.3' LT	624.29	64+22	67' LT	627.22	64	25	
37	132+00	3.82 LT	678.91	132+00	112.1' RT	678.63	116	64	
46	155+00	1.2' LT	682.51	155+00	93.6' LT	682.06	90	52	
48	62+00	0'	621.61	62+01	68.4' RT	621.25	70	37	
49	64+50	5.6' LT	627.56	64+22	67' LT	627.22	68.0	44	
	133+50 +/-			135+30			50.0	0	
							TOTAL	1121.0	453

PIPE CULVERTS, CLASS A, TYPE 2 36" (542A1081)									
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
24	124+58	194' LT	665.28	124+30	275' LT	649.70	86.0	30	
							TOTAL	86.0	30

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18" (54200643)									
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
35	86+10	2.6' RT	691.72	85+06	0.5' LT	690.78	104	0	
							TOTAL	104.0	0

INSERTION CULVERT LINER 16" (54390130)							
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT
44	104+89	123.1' LT	687.20	104+89	184.2' LT	682.70	60
						TOTAL	60

INSERTION CULVERT LINER 22" (54390170)							
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT
27	174+00	114' LT	643.27	174+01	219' LT	626.51	101
28	178+98	164.9' LT	632.76	178+98	258' LT	612.94	92
						TOTAL	193

INSERTION CULVERT LINER 28" (54390200)							
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT
25	136+87	242.2' LT	665.89	137+96	350' LT	643.78	157
						TOTAL	157.0

INSERTION CULVERT LINER 32" (54390220)							
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT
26	161+97	112.3' LT	664.56	161+98	189' LT	657.29	77
						TOTAL	77.0

CLEAN EXISTING CULVERTS (XX004033)	
STATION	EACH
59+95	1
62+30	1
63+01	1
66+27	1
66+81	1
67+19	1
79+81	1
82+00	1
104+00	1
122+49	1
124+82	1
128+99	1
134+52	1
135+06	1
135+85	1
136+81	1
137+99	1
147+63	1
173+55	1
173+97	1
175+97	1
179+16	1
183+00	1
TOTAL	23