

15 FLUSH INLET BOX FOR MEDIAN,  
STANDARD 542546 (54244405)  
STA. 173+97/0'  
RIM- 657.96  
INV- 650.20

16 CB, TA, 4'-DIA.  
TIF, OL (60200105)  
STA. 173+97/114' LT  
RIM- 649.51  
INV.- 643.27

17 REINFORCED CONCRETE  
END SECTIONS 24"  
STA. 173+97/219' LT  
CONCRETE STRUCTURES 1.0 CU YD  
(50300225)  
REINFORCEMENT BARS,  
EPOXY COATED 35 LBS (50800205)  
INV.- 626.51

27 INSERTION CULVERT LINER 22"  
(54390170)  
101'

STA. 174+01 CONCRETE HEADWALL REMOVAL (50104400)

STA. 173+97 REMOVING INLETS (60500060)

STA. 173+97 CLEAN EXISTING CULVERT (XX004033)  
110' @ 24" DIA.

STA. 167+67 REMOVE INLET BOX (X6050700)

STA. 166+98 PIPE CULVERT REMOVAL (50105220)  
(SEE NOTE 1)

STA. 167+17 REMOVE INLET BOX (X6050700)

STA. 173+55 CLEAN EXISTING CULVERT (XX004033)  
540' @ 36" DIA.

STA. 173+97 REMOVING INLETS (60500060)

MATCH LINE STA 164+00

MATCH LINE STA 178+00

STA. 175+97 CLEAN EXISTING CULVERT (XX004033)  
50' @ 24" DIA.

STA 175+14 PAVED DITCH REMOVAL (44004000)

STA 169+54 PAVED DITCH REMOVAL (44004000)

STA 172+54 PAVED DITCH REMOVAL (44004000)

EXISTING ROW

18 STA. 178+98 CONCRETE HEADWALL REMOVAL (50104400)

28 STA. 178+99 REMOVING INLETS (60500060)

17 FLUSH INLET BOX FOR MEDIAN,  
STANDARD 542546 (54244405)  
STA. 178+98/164.9' LT  
RIM- 637.47  
INV.- 632.76

18 REINFORCED CONCRETE  
END SECTIONS 24"  
STA. 178+98/258' LT  
CONCRETE STRUCTURES 1.0 CU YD  
(50300225)  
REINFORCEMENT BARS,  
EPOXY COATED 35 LBS (50800205)  
INV.- 612.94

28 INSERTION CULVERT LINER 22"  
(54390170)  
92'

EXISTING ROW

MATCH LINE STA 178+00

STA. 183+00 CLEAN EXISTING CULVERT (XX004033)  
355' @ 18" DIA.

I-80

17 STA. 179+16 CLEAN EXISTING CULVERT (XX004033)  
70' @ 24" DIA.

FILE NAME = c:\pwwork\pwwork\grant\pwwork\mms34287\208483.dwg

**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = grantpm	DESIGNED - AL	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - EPS	REVISED -
PLOT DATE = Mon Dec 15 08:36:36 2008	CHECKED - DMM	REVISED -
	DATE - Mon Dec 15 08:36:36 2008	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**I-80**  
**PROPOSED DRAINAGE PLAN**  
**STA. 164 + 00 TO STA. 191 + 50**

SCALE: 1" = 50' SHEET NO. OF SHEETS

F.A.I. RTE. 80	SECTION (81-1)R-1	COUNTY ROCK ISLAND	TOTAL SHEETS 292	SHEET NO. 148
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 64933	