



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 26, 2009

SUBJECT: FAS Route 1177 (IL 251)
Project ACRS-1177 (113)
Section 111T
LaSalle County
Contract No. 64A07
Item No. 163, March 6, 2009 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 - 5 of the Schedule of Prices.
2. Review page ii of the Table of Contents to the Special Provisions.
3. Added page 55 to the Special Provisions.
4. Revised sheets 1 - 7, 9, 10, 12, 15 - 19, 24 - 27, and 49 - 59 of the Plans.
5. Added sheets 31A - 31D to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles J. Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: George F. Ryan, Region 2, District 2; Bill Frey; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64A07

State Job # - C-92-056-09
 PPS NBR - 2-13790-0100
 County Name - LASALLE- -
 Code - 99 - -
 District - 2 - -
 Section Number - 111T

Project Number
 ACRS-1177/113/

Route
 FAS 1177

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2006714	T-QUERCUS MACR 1-3/4	EACH	14.000				
C2001548	S-CORNUS RACEMOSA 4'	EACH	20.000				
X0323660	DROP BOX NO.1	EACH	1.000				
** X0712400	TEMP PAVEMENT	SQ YD	770.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0023600	FILL EXIST CULVERTS	EACH	1.000				
** Z0030250	IMP ATTN TEMP NRD TL3	EACH	4.000				
** Z0030350	IMP ATTN REL NRD TL3	EACH	4.000				
20100110	TREE REMOV 6-15	UNIT	126.000				
20100210	TREE REMOV OVER 15	UNIT	124.000				
20100500	TREE REMOV ACRES	ACRE	0.250				
** 20200100	EARTH EXCAVATION	CU YD	4,212.000				
** 20201200	REM & DISP UNS MATL	CU YD	100.000				
25000210	SEEDING CL 2A	ACRE	1.250				
25000310	SEEDING CL 4	ACRE	0.750				
** REVISED : FEBRUARY 25, 2009							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64A07

State Job # - C-92-056-09
 PPS NBR - 2-13790-0100
 County Name - LASALLE- -
 Code - 99 - -
 District - 2 - -
 Section Number - 111T

Project Number
 ACRS-1177/113/

Route
 FAS 1177

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000400	NITROGEN FERT NUTR	POUND	180.000				
25000500	PHOSPHORUS FERT NUTR	POUND	180.000				
25000600	POTASSIUM FERT NUTR	POUND	180.000				
25000750	MOWING	ACRE	2.000				
25100115	MULCH METHOD 2	ACRE	2.000				
25100630	EROSION CONTR BLANKET	SQ YD	1,204.000				
** 28000250	TEMP EROS CONTR SEED	POUND	1,200.000				
28000300	TEMP DITCH CHECKS	EACH	60.000				
28000400	PERIMETER EROS BAR	FOOT	100.000				
28000500	INLET & PIPE PROTECT	EACH	2.000				
35101600	AGG BASE CSE B 4	SQ YD	744.000				
40603310	HMA SC "C" N50	TON	83.300				
44201383	CL C PATCH T4 12	SQ YD	549.000				
44300200	STRIP REF CR CON TR	FOOT	370.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	34.000				
** REVISED : FEBRUARY 25, 2009							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64A07

State Job # - C-92-056-09
 PPS NBR - 2-13790-0100
 County Name - LASALLE- -
 Code - 99 - -
 District - 2 - -
 Section Number - 111T

Project Number
 ACRS-1177/113/

Route
 FAS 1177

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48203021	HMA SHOULDERS 6	SQ YD	743.500				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50104400	CONC HDWL REM	EACH	1.000				
50800105	REINFORCEMENT BARS	POUND	19,200.000				
50800205	REINF BARS, EPOXY CTD	POUND	740.000				
** 51205200	TEMP SHT PILING	SQ FT	2,519.000				
51500100	NAME PLATES	EACH	2.000				
54001001	BOX CUL END SEC C1	EACH	1.000				
54003000	CONC BOX CUL	CU YD	156.400				
54010804	PCBC 8X4	FOOT	90.000				
54010808	PCBC 8X8	FOOT	198.000				
61133100	FLD TILE JUN VAULT 2D	EACH	2.000				
61140000	STORM SEWER SPEC 8	FOOT	100.000				
61140100	STORM SEWER SPEC 10	FOOT	100.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64A07

State Job # - C-92-056-09
 PPS NBR - 2-13790-0100
 County Name - LASALLE- -
 Code - 99 - -
 District - 2 - -
 Section Number - 111T

Project Number
 ACRS-1177/113/

Route
 FAS 1177

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
** REVISED : FEBRUARY 25, 2009							
63000000	SPBGR TY A	FOOT	612.500				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000				
63200310	GUARDRAIL REMOV	FOOT	898.000				
63500105	DELINEATORS	EACH	11.000				
66600105	FUR ERECT ROW MARKERS	EACH	27.000				
66700305	PERM SURV MKRS T2	EACH	4.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70100405	TRAF CONT-PROT 701321	EACH	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
** 70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	10.000				
** 70106500	TEMP BR TRAF SIGNALS	EACH	3.000				
** 70106700	TEMP RUMBLE STRIP	EACH	12.000				
** REVISED : FEBRUARY 25, 2009							

REINFORCEMENT BARS (BDE) 43
REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 44
SEEDING (BDE) 44
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 46
SILT FILTER FENCE (BDE) 47
STEEL PLATE BEAM GUARDRAIL (BDE) 48
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 48
TEMPORARY EROSION CONTROL (BDE) 48
WORKING DAYS (BDE) 49
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 49
PAYROLLS AND PAYROLL RECORDS (BDE) 53
DEMOLITION PLANS FOR REMOVAL OF EXISTING STRUCTURES 55

Revised 02/26/2009

DEMOLITION PLANS FOR REMOVAL OF EXISTING STRUCTURES

Effective: September 5, 2007

Add to the beginning of Article 501.02 of the Standard Specifications.

“The Contractor shall submit a demolition plan to the Engineer for approval, detailing the proposed methods of demolition and the amount, location(s) and type(s) of equipment to be used. With the exception of removal of single box culverts, for work adjacent to or over an active roadway, railroad or navigable waterway, the demolition plan shall include an assessment of the structure’s condition and an evaluation of the structure’s strength and stability during demolition and shall be sealed by an Illinois Licensed Structural Engineer.”

Added 02/26/2009