

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% Fed 20% State MINOR STRUCTURE Y007
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	220
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	28
20101000	TEMPORARY FENCE	FOOT	1225
20200100	EARTH EXCAVATION	CU YD	3658
20200200	ROCK EXCAVATION	CU YD	100
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
* 25000210	SEEDING, CLASS 2A	ACRE	1.25
* 25000310	SEEDING, CLASS 4	ACRE	1.25
* 25000322	SEEDING, CLASS 5A	ACRE	1.25
: 25000750	MOWING	ACRE	2.5
* 25100115	MULCH, METHOD 2	ACRE	2.5
* 25100630	EROSION CONTROL BLANKET	SQ YD	2759
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	916
28000300	TEMPORARY DITCH CHECKS	EACH	103
28000400	PERIMETER EROSION BARRIER	FOOT	200
28000500	INLET AND PIPE PROTECTION	EACH	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	195
28200200	FILTER FABRIC	SQ YD	195
35101400	AGGREGATE BASE COURSE, TYPE B	TON	323
40600990	TEMPORARY RAMP	SQ YD	59
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	200
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	31

* SPECIALTY ITEMS
:) NON PARTICIPATING 100% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% Fed 20% State MINOR STRUCTURE Y007
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	7
42001200	PAVEMENT FABRIC	SQ YD	220
44004250	PAVED SHOULDER REMOVAL	SQ YD	35
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	220
44213200	SAW CUTS	FOOT	109
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1783
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	202
51500100	NAME PLATES	EACH	2
52100510	ANCHOR BOLTS, 3/4"	EACH	8
54213453	END SECTIONS 18"	EACH	2
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	2
54213729	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 84"	EACH	1
54248510	CONCRETE COLLAR	CU YD	0.5
X0323660	DROP BOX NO. 1	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	162.5
63500105	DELINEATORS	EACH	9
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	20
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1

* SPECIALTY ITEMS
:) NON PARTICIPATING 100% STATE