

35101400 AGGREGATE BASE COURSE, TYPE B

TON	LOCATION	OFFSET	REMARKS
19	420+24 TO 421+17.6	LT	Assume 4" build up for Stage I - 8' wide PE (8" THICKNESS)
30	424+79	RT	
97	441+50 TO 446+50	RT	FE (8" THICKNESS)
89	442+00 TO 446+50	LT	
88	443+97		
323	TOTAL		

40600990 TEMPORARY RAMP

SQ YD	LOCATION	OFFSET	REMARKS
15	421+06		TO BE USED IF NEEDED TO ALLOW CURE TIME FOR CLASS B PATCHES BEFORE SURFACE PLACEMENT
15	421+37		
15	443+87		
15	444+32		
59	TOTAL		

40603310 HOT MIX ASPHALT SURFACE COURSE, MIX "C", N 50

TON	LOCATION	OFFSET	REMARKS
61	418+00 TO 425+11	RT	STAGE II
55	418+00 TO 424+50	LT	
42	441+50 TO 446+50	RT	
38	442+00 TO 446+50	LT	
4	443+87 TO 444+32	LT	
200	TOTAL		

40603340 HOT MIX ASPHALT SURFACE COURSE, MIX "D", N 70

TON	LOCATION	OFFSET	REMARKS
13	421+06 TO 421+37		PATCH
18	443+87 TO 444+32		PATCH
31	TOTAL		

40800050 INCIDENTAL HOT-MIX SURFACING

TON	LOCATION	OFFSET	REMARKS
6.8	424+79	RT	PE

42001200 PAVEMENT FABRIC

SQ YD	LOCATION	OFFSET	REMARKS
90	421+06 TO 421+37		
130	443+87 TO 444+32		
220	TOTAL		

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION	OFFSET	REMARKS
35	443+87 TO 444+32	LT	STAGE II
35	TOTAL		

44200976 CLASS B PATCHES, TYPE IV, 10 INCH

SQ YD	LOCATION	OFFSET	REMARKS
90	421+06 TO 421+37		
130	443+87 TO 444+32		
220	TOTAL		

44213200 SAW CUTS

FOOT	LOCATION	OFFSET	REMARKS
109	421+06 TO 421+37		
123	443+87 TO 444+32		
109	TOTAL		

48203021 HOT - MIX ASPHALT SHOULDERS, 6"

SQ YD	LOCATION	OFFSET	REMARKS
541	418+00 TO 425+11	RT	
493	418+00 TO 424+50	LT	
372	441+50 TO 446+50	RT	
342	442+00 TO 446+50	LT	
35	443+87 TO 444+32	LT	
1783	TOTAL		

50100300 REMOVAL OF EXISTING STRUCTURE NO. 1

EACH	LOCATION	OFFSET	REMARKS
1	421+25.0		6' X 6' Box Culvert with CMP Extensions

50100400 REMOVAL OF EXISTING STRUCTURE NO. 2

EACH	LOCATION	OFFSET	REMARKS
1	444+14.9		5' X 4' Box Culvert

50200400 ROCK EXCAVATION FOR STRUCTURES

CU YD	LOCATION	OFFSET	REMARKS
202	444+02		Assume 3.5' Depth 12' x 130'