

**66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS**

EACH	LOCATION	OFFSET	REMARKS
1	418+00	34.3' RT	
1	418+50	50' RT	
1	420+00	50' RT	
1	421+00	75' RT	
1	421+15	31.7' LT	
1	421+15	60' LT	
1	421+35	31.7' LT	
1	421+35	60' LT	
1	422+00	75' RT	
1	424+00	55' RT	
1	425+00	34.4' RT	
1	441+00	50' RT	
1	442+00	55' RT	
1	443+50	105' RT	
1	443+90	39.2' LT	
1	443+90	70' LT	
1	444+15	39.3' LT	
1	444+15	70' LT	
1	444+50	95' RT	
1	446+67	50' RT	
<b>20</b>	<b>TOTAL</b>		

**66700305 PERMANENT SURVEY MARKERS, TYPE II**

EACH	LOCATION	OFFSET	REMARKS
2	AT EACH CULVERT		
2	AT EACH CULVERT		CONTACT SURVEY DEPARTMENT
<b>4</b>	<b>TOTAL</b>		

**70300100 SHORT-TERM PAVEMENT MARKING**

FOOT	LOCATION	OFFSET	REMARKS
4	421+06 TO 421+37		
63	441+05 TO 447+31		
<b>67</b>	<b>TOTAL</b>		

**70300520 PAVEMENT MARKING TAPE, TYPE III 4"**

FOOT	LOCATION	OFFSET	REMARKS
583	441+19 TO 446+99		STAGE I (WHITE)
492	441+65 TO 446+97		STAGE II (WHITE)
316	442+53 TO 445+09		STAGE I (WHITE)
248	442+91 TO 445+23		STAGE II (WHITE)
<b>1639</b>	<b>TOTAL</b>		

**70300570 PAVEMENT MARKING TAPE, TYPE III 24"**

FOOT	LOCATION	OFFSET	REMARKS
12	441+05	RT	STOP BAR
12	447+31	LT	STOP BAR
<b>24</b>	<b>TOTAL</b>		

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION	OFFSET	REMARKS
1	421+06 TO 421+37		SHORT TERM
24	441+05	RT	STOP BAR
21	441+05 TO 447+31		SHORT TERM
194	441+19 TO 446+99		STAGE I
164	441+65 TO 446+97		STAGE II
105	442+53 TO 445+09		STAGE I
83	442+91 TO 445+23		STAGE II
24	447+31	LT	STOP BAR
<b>615</b>	<b>TOTAL</b>		

**70400100 TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION	OFFSET	REMARKS
350	442+34 TO 445+83		STAGE I

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION	OFFSET	REMARKS
250	442+84 TO 445+33		STAGE II

**78001110 PAINT PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION	OFFSET	REMARKS
11400	418+00 TO 446+50	RT & LT	white edge lines (2 applications)
11400	418+00 TO 446+50	CL	Double Yellow (2 applications)
<b>22800</b>	<b>TOTAL</b>		

**78100100 RAISED REFLECTIVE PAVEMENT MARKER**

EACH	LOCATION	OFFSET	REMARKS
1	421+25		
1	448+02		
<b>2</b>	<b>TOTAL</b>		